Historic, archived document

Do not assume content reflects current scientific knowledge, policies, or practices.

Q.73

# The MAULE 1927 SEED BOOK

## A Guide to Successful Gardening

50 Years in Business

OUR GOLDEN ANNIVERSARY

2 Great Novelties (Value 50¢) Given Free to Customers to Celebrate Our 50 Years in Business

See Page 2

Wm Henry Maule - - - - Philadelphia, Pa.

D. N. Shoemaker

# MAULE'S GIANT AMERICAN ASTERS

**4115 Collection** One packet each of the seven distinct Asters (value 80c) for **50c**

**982**—American Beauty · Pkt.10c
**989**—Astermum White · Pkt.15c
**1006**—Crego Shell Pink · Pkt.10c
**1055**—Invincible Purple · · · Pkt.10c
**1068**—King Mixed · · · · · Pkt.10c
**1104**—Semples Lavender Pkt.10c
**1111**—Heart of France · · Pkt.15c

All Postpaid

# Our Guarantee

We guarantee that all seeds, bulbs and roots sold by us shall reach our customers in good condition.

We guarantee to deliver to your door, or Post Office, by parcel post free of any extra charge, all seeds in any quantity up to and including five pounds of a kind. We also deliver postpaid all bulbs and roots offered in this book at postpaid prices. When goods offered at "not prepaid" prices are wanted by parcel post, the required postage should be added and included with your remittance.

***As To Crops***—Under the varying conditions of soil and climate it is impossible to guarantee the results, but we guarantee that you can have the money back you paid us for seeds, bulbs or roots any time within the year if you are not satisfied with the results obtained.

WM. HENRY MAULE CO.

# After 50 Years

THOUSANDS of people now in the sunset of their lives learned to know and love flowers in gardens planted with Maule seeds. Thousands of gardens exist in this country that are as old as the House of Maule; that began when we began—a half century ago, with Maule Seeds and Bulbs.

Thousands of our patrons — now mature men and women—played as little children in Maule gardens.

Treasured in our vaults are many letters that prove the existence of many gardens that for years and years have been planted with Maule Seeds.

So, may we be pardoned if we evidence some pride in the announcement of this our Golden Anniversary.

For Maule Seeds have ever been and always will be ***honest seeds.*** And the first essential to a successful garden is honest seed.

If perchance you are a new friend contemplating your first purchase from our house, you will be interested in the following outstanding facts:

Our policy has always been to sell the very highest quality at the very lowest prices; on this point we challenge all competition.

All Maule Seeds, Bulbs and Roots are scientifically and thoroughly tested for active, abundant and vigorous life. Only the most virile product is shipped. That is why Maule Seeds produce the greatest number of plants and the finest, biggest and healthiest blooms and specimens.

Everything we sell is Guaranteed with a Money-back Bond. If you are dissatisfied in any way with your results, we will refund your money without quibble, question, or delay.

More than three-fourths of our customers are professional farmers and gardeners; hundreds, yes thousands, of whom have dealt with us year after year. What does this mean? It means that these men who live by the soil trust us for one of the vital fundamentals of their existence. For no matter how intelligent, or industrious, or able the farmer or gardener may be, he cannot grow good crops with poor seed.

Maule Seeds cannot be purchased in stores, nor have we any agents or salesmen. You buy direct from us; you do not pay any middleman's profits. Therefore, our low prices for the highest quality.

In celebration of our Golden Anniversary, we are making some offers that are unusually liberal. These offers are explained in the following pages. They will interest you greatly.

You cannot plan your garden too early. The sooner you do your planning the more pleasing your results will be. Plan now; get your seeds now. Remember that back of every Maule Seed, Bulb and Root is a reputation of 50 years' square dealing.

Ours is one of the oldest and biggest seed houses in America.

# Wm. Henry Maule Co.

## HOW TO ORDER

THE following suggestions are to insure the prompt and accurate filling of your order. Always, when possible, use the order blank which accompanies this catalog. Be certain to write plainly your full name and address each time you order. Always order by the same name. If you live on a Rural Route or have a Post Office Box, give the ***number.*** If goods are to be shipped by freight or express, mention the ***name*** of your railroad station.

***How to Remit:*** All remittances should be made by money order, bank draft, registered letter or personal check; then your money is safeguarded; it cannot be lost. We accept currency and U. S. Postage Stamps, but are not responsible for such remittances if they are lost. We cannot accept foreign postage stamps. On all orders of $1.00 and more, we will pay the cost of your money order or registered letter; the amount may be deducted from your remittance.

***Transportation Charges:*** We prepay all transportation charges on practically everything we sell; the only exception being on seeds and roots listed not prepaid. If these heavy goods are wanted by parcel post, ***the amount of the postage should be added to your remittance.*** Your post master, or rural carrier, can tell you the parcel post cost.

## CARROTS!

### Our Bountiful Crop Gives You a Fine Big Bargain

WE are happy to announce that our Carrot Seed Crop is the largest we have ever harvested. Besides being plentiful, this crop is of the finest quality; all Big, Plump, Vigorous Seeds; all tested and proven for abundant, healthy life. We are passing the full benefit of our bountiful crop right on to you. We have made slashing cuts in our regular prices. These prices challenge all competition. See "Carrots" on pages 24 and 25.

All prices quoted in this catalog are subject to change and prior sale.

COPYRIGHTED, 1926, BY WM. HENRY MAULE CO., PHILADELPHIA, PA., U. S. A.

# FREE *Hundreds of Delicious Radishes and Gorgeous Poppies*

PICTURE a garden of hundreds of strikingly beautiful, long stemmed, silky poppies that *will not cost you a cent.* Think of supplying your table regularly with an abundance of big, firm, crisp, delicious radishes *also Free.* To celebrate our Golden Anniversary, to make thousands of new friends, and to please our old ones, we are making a most outstandingly liberal offer. If you will order only one dollar's worth of seeds or bulbs from this catalog, *and if you will act promptly,* we will give you *Absolutely Free* a big 50c worth of the new Maule Hybrid Poppy and the new Maule Radish. As shown on the front cover of this book, the price of these Free Seeds is 25c a packet; their value is 50c. Their quality is identical with the high quality of all Maule Seeds, and they carry the same unqualified guarantee of vigorous and abundant life. Select your seeds Now, Send your Order NOW, and the Free Radishes and Poppies, with the balance of your order, will soon be on their way to you. Remember, all you have to do is order one dollar's worth or more, seeds, bulbs, or roots, from this catalog and the Free Seeds are yours.

## *Read this Description of the Free Seeds*

### Maule's Hybrid Poppies

The distinctive features of these new poppies are their size, their rare coloring and color combinations, and the pleasing crinkly appearance of their petals—not unlike fine crepe paper. Their double and semi-double flowers run from 2 to 2½ inches in diameter, in pure white, pink, rose, salmon, salmon-orange, scarlet and crimson; also in lovely combinations of broad and narrow-banded white-edged scarlet and pink. These sturdy plants bear profusely during June and July, forming a beautiful early summer garden. Blooms cut in the early morning when half open will keep in water several days.

### The New Maule Radish

A delightful surprise to lovers of relishes—probably the *largest radish suitable for table use ever grown.* Has a slightly pinkish-tinted flesh as firm and crisp as that of the finest small size varieties. Its flavor is piquant and snappy, but not bitey. A fine looking round radish of an evenly colored rich scarlet. It has an excellent tap root, and an abundant amount of dark green foliage. Grown in good soil, the radishes will measure from 1¼ to 1½ inches across. They will mature (depending upon growing conditions) in from 30 to 40 days after sowing seed.

WM. HENRY MAULE CO.

PHILADELPHIA, PA.

**FREE** Hundreds of Gorgeous Poppies — **$2.50 Value for $1** — Hundreds of Delicious Radishes **FREE**

TO stimulate early ordering, to induce you to get your garden needs now, before our Big Rush starts, we are making a wonderful Slashed Price, 90 Day Offer. We have taken 100 of our finest, easiest growing varieties of vegetables and flowers and have ***cut the price in half.*** For only $1, sent now, you can select any 20 packets of regular 10c seeds; that is, you can have twenty 10c packets for 5c each; A Big $2 Value for only $1. ***And that is not all.*** In addition to cutting prices in half we will send you Absolutely Free a 25c packet of Poppy Seeds and a 25c packet of Radish Seeds. These gift seeds are the same as those described in detail in our other offer on the opposite page. To get the full realization of what this offer means to you, picture in your mind the ***results*** you will get: **5c** will bring you ***400 beets*** * * * **5c** will bring you ***200 cabbages*** * * * **5c** will bring you ***600 tomatoes*** * * * **5c** will bring you ***750 asters*** * * * **5c** will bring you ***600 zinnias*** * * * **5c** will bring you ***1,000 sweet pea blooms,*** and so on. All these varieties are Genuine Maule Seeds, super-tested for abundant, vigorous, virile life; all are guaranteed by the Maule Money Back Bond.

# This Is Your Selection — Regular 10¢ Packets Only 5¢

## Vegetables

Order No. **Bush Beans—Produces ¼ bushel**

(14) Burpee's Stringless Green Pod
*Early, large, round podded.*
(32) Maule's Profusion Wax
*Prolific, round, solid, stringless, yellow pods. Midseason.*

**Pole Bean—Produces ½ bushel pods**

(43) Kentucky Wonder
*Earliest, nearly round, green podded. Very prolific.*

**Pole Lima Beans—Prod. ¼ bushel pods**

(52) Maule's Evergreen
*Pods 5 to 7 in. long; 5 to 6 large green beans to a pod.*

**Bush Lima Beans—Prod. ½ bushel pods**

(58) Fordhook
*True bush form. Large, thick, tender beans. Enormous cropper.*

**Beet—Produces 400 roots**

(67) Maule's Alpha
*Early maturing, turnip shape; dark red, tender, sweet.*
(82) Maule's Market Gardeners
*Midseason sort. Large, tender, sweet. Good winter keeper.*

**Brussels Sprouts—Prod. 25 qts. sprouts**

(108) Danish Prize
*Large, solid sprouts, tender and sweet.*

**Cabbage—Produces 200 heads**

(119) Copenhagen Market
*Solid, round heads, excellent for slaws. Medium early.*
(131) Maule's Surehead
*Large, late sort. Flat solid heads. The Kraut maker.*

**Carrot—Produces 500 roots**

(145) Maule's Golden Rod
*Half-long, stump rooted; deep orange; sweet.*
(152) Maule's Danvers Half-Long
*Half-long, tapering to blunt point. Rich orange-red.*

**Cauliflower—Produces 100 heads**

(166) Maule's Always Heads
*Large, solid, white heads. Very early.*

**Celery—Produces 400 stalks**

(189) Maule's American Yellow
*Very early. One of the easiest to blanch. Crisp.*

**Sweet Corn—Produces 200 ears**

(207) Burpee's Golden Bantam
*Golden yellow ears 6 to 7 inches long, sweet as honey, extremely early.*
(222) Maule's Lead All Evergreen
*Produces ears 8 to 10 inches long; large, white, sweet; late maturing.*

**Pop Corn—Produces 300 ears**

(237) Monarch White Rice
*Large ears with pointed white grain. Good popper.*

**Cucumber—Produces 150 fruits**

(244) Maule's Extra Early
*Medium early, straight, dark green sort, 6 to 7 in. long.*
(252) Maule's Early White Spine
*The midseason, long dark green, 8 to 9 in. slicing cucumber.*

**Egg Plant—Produces 200 fruits**

(281) New York Improved Purple
*Large, oval shape, dark purple strain. Very popular.*

Order No. **Endive—Produces 200 heads**

(284) Green Curled
*Large, dark green curly leaves; blanches white.*

**Kale—Produces 1 bushel greens**

(303) Maule's Emerald Isle
*Half-dwarf, quite hardy. Long well curled green leaves.*

**Kohl Rabi—Produces 200 roots**

(310) Maule's Imperial
*Large, light green roots, small tops; hardy; productive.*

**Leek—Produces 100 roots**

(313) Giant Italian
*Large white roots; dark green foliage. Very hardy.*

**Lettuce—Produces 100 heads**

(328) Maule's Improved Hanson
*Late maturing large crumpled leaf; solid heading; heat resisting.*
(334) Maule's Big Boston
*Very large solid buttery head, smooth leaved; medium early.*
(342) Grand Rapids
*Earliest loose-leaved cutting variety. Green crumpled, fringed leaves.*

**Muskmelon—Produces 100 melons**

(351) Maule's Model
*Finest large oval-shaped, green-fleshed, medium early sweet melon.*
(364) Watter's Solid Net Rocky Ford
*Earliest, solid, netted, green fleshed, Rocky Ford melon grown.*

**Watermelon—Produces 50 melons**

(387) Maule's Panmure Allheart
*Sweetest, large, oblong-shaped, green-striped melon grown.*
(393) Kleckley Sweet
*The most popular large, oblong-shaped, dark green, sweet melon.*

**Mustard—Produces ½ bushel greens**

(421) Southern Giant Curled
*The most popular, dark green, extra curled leaved sort.*

**Okra—Produces ¼ bushel pods**

(434) White Velvet
*Produces large, round, white smooth pods. Very prolific.*

**Onion—Produces ½ bushel bulbs**

(436) Maule's Large Red Wethersfield
*Very large oval-shaped, flattened, deep red sort.*
(441) Maule's Prizetaker
*King of large yellow globe onions. Mild and sweet.*

**Parsley—Produces ¼ bushel greens**

(474) Maule's Double Curled
*Handsomest curled, dark green, beautiful crumpled sort.*

**Parsnip—Produces ½ bushel roots**

(477) Maule's White Lisbon
*Handsomest long, smooth, uniform shaped sort.*
(478) Maule's Improved Half Long
*A well known popular sort, roots smooth, easy to harvest.*

**Peas—Produces ¼ bushel pods**

(488) Maule's Earliest of All
*Earliest and hardiest Pea to plant. Very productive.*
(506) Maule's Radio
*Extremely early dwarf pea. Hardy and prolific.*
(509) Laxtonian
*Largest podded medium early dwarf sort.*

Order No. **Pepper—Produces 1000 fruits**

(533) Maule's Improved Ruby King
*Large, sweet, medium, early maturing variety. Very popular.*

**Pumpkin—Produces 20 fruits**

(554) Maule's Yellow Sweet Potato Pie
*Great pie pumpkin, large, dry and sweet.*
(556) Maule's Prize Potiron
*Largest of all. King of Mammoth.*

**Radish—Produces 400 roots**

(581) Maule's Long Scarlet
*Medium early, long, dark red, brittle and crisp sort.*
(583) Maule's Earliest Scarlet
*Extremely early; round, dark red, mild sort.*
(584) Long White Icicle
*Finest early, long white, solid and crisp radish.*

**Salsify—Produces 100 roots**

(614) Mammoth Sandwich Island
*Large, smooth white roots. The best strain.*

**Spinach—Produces ½ bushel greens**

(620) Giant Fillbasket
*Largest leaf variety, producing glossy dark green foliage.*
(624) King of Denmark
*Longest standing Spinach, producing large, round crumpled leaves.*

**Squash—Produces 50 fruits**

(628) Earliest White Bush
*Earliest of all, known as Patty Pan or Cymling.*
(632) Mammoth Golden Summer Crookneck
*Largest, golden yellow bush Squash. Very popular.*
(635) Maule's Improved Hubbard
*Acknowledged standard of quality. Winter keeping sort.*

**Swiss Chard—Prod. ½ bushel greens**

(89) Lucullus
*Large, crumpled light green leaves. Cut and come again Spinach Beet.*

**Tomato—Produces 10 bushels fruits**

(652) Maule's Success
*Large, medium early, smooth, bright red fruit. Best for table or canning.*
(657) Maule's Imperial
*Early, smooth, pink fruited, firm and sweet.*
(683) Bonny Best
*Very early, large and smooth, bright scarlet popular tomato.*

**Turnip—Produces 1 bushel roots**

(687) Red or Purple Top Strap Leaf
*Large turnip shape, white flesh, solid and sweet.*
(698) Golden Ball
*Round, smooth, yellow flesh sort. Sweet and tender.*

**Ruta Bagas—Produces 1 bushel roots**

(707) Maule's Heavy Cropping
*Largest grown. Very rich yellow flesh. Fine grained and sweet.*

## Flowers

Order No.

(898) **Acroclinium** *Mixed Colors*
(914) **Alyssum** *Little Gem*
(940) **Snapdragons** *Mixed Colors*
(1010) **Aster** *Crego Mixed Colors*
(1033) **Aster** *Earliest Blooming Mixed Colors*
(1100) **Aster** *Early Branching Mixed Colors*
(1110) **Aster** *Late Branching Mixed Colors*
(1127) **Balsam** *Mixed Colors*
(1165) **Calliopsis** *Tall Mixed*
(1185) **Candytuft** *Mixed Colors*
(1207) **Cockscomb** *Mixed Colors*
(1218) **Cornflower** *Double Mixed*
(1233) **Chrysanthemum** *Double Mixed*
(1265) **Cosmos** *Early Mixed Colors*
(1273) **Cypress Vine** *Mixed Colors*
(1294) **Dianthus (Pinks)** *Mixed Colors*
(1326) **California Poppy** *Mixed Colors*
(1374) **Strawflowers** *Mixed Colors*
(1385) **Hollyhock** *Annual Mixed*
(1404) **Moonflower** *Giant White*
(1412) **Japanese Kudzu Vine**
(1416) **Kochia or Burning Bush**
(1424) **Annual Larkspur** *Mixed Colors*
(1452) **Marigold Dwarf** *Mixed*
(1456) **Marigold Tall** *Mixed*
(1457) **Four O'Clocks** *Dwarf Mixed*
(1472) **Mignonette** *Defiance*
(1486) **Morning Glory** *Japanese Mixed*
(1536) **Nasturtium** *Tall Mixed*
(1558) **Nasturtium** *Dwarf Mixed*
(1634) **Pansy** *Extra Fine Mixed*
(1640) **Petunia** *Dwarf Bedding Mixed*
(1654) **Phlox Drummondii** *Mixed Colors*
(1672) **Poppy** *Shirley Single Mixed*
(1673) **Poppy** *Carnation Double Mixed*
(1715) **Castor Oil Bean** *Mixed Varieties*
(1723) **Scarlet Sage** *Bonfire*
(1922) **Sweet Peas** *Spencer Mixed Colors*
(1968) **Verbena** *Finest Mixed*
(2054) **Zinnia** *Giant Mixed Colors*

The results to be expected from a packet of seeds are conservatively estimated. Where soil is exceptionally good, results will be better than stated; where soil is poor and culture neglected, results will fall below our estimate.

## Please *Read Carefully* Before Ordering

This Slashed Price offer makes it especially profitable for you to send your order now, before our rush begins. But you must be prompt; you must send your order within 90 days.

To get the half price and the 50c worth of Poppies and Radishes Free you must order *at least* one dollar's worth of seeds *from the above selection.* Orders for less than $1 cannot be accepted at the cut price. But, you may order as much as you want in excess of one dollar, and at the price of only 5c per packet. And the more you order, the greater your bargain. Figuring the value of the Free Seeds at 50c, $1 brings $2.50 value, $1.50 brings $3.50 value, $3 brings $6.50 value, and so on.

ORDER BY NUMBER: You need not write a long order; just mention your choice by the numbers indicated, enclose the exactly right amount and your seeds will soon be in your possession. Order sheets, made for your convenience, will be found in the back of this book. GIFT SEEDS: Don't forget your friends during this Sale; they will appreciate the compliment of a gift of seeds.

# *Maule's Superior* Vegetable Seeds

All varieties of Vegetable Seeds and Roots both old reliable kinds and entirely new varieties are listed on the following pages. In all cases full tests have been made, conforming to the unvarying Maule rule. Some old varieties have been discarded because newer sorts listed are an improvement over them. You may be sure of every article listed. They have been proven so far as possible. Our listing merits the same confidence as shown by our customers in the past, for which we thank them.

**WE STRONGLY RECOMMEND ALL VARIETIES LISTED IN BOLD TYPE WITH CLOVER MARKS**

## Asparagus Seed

**Asparagus grows easily in any good soil; a bed well cared for lasts for years**

CULTURE.—Sow in the early Spring in drills 2 to 3 feet apart, scattering about 1 inch apart in the drills. Cover with 1 inch of soil; cultivate freely. A packet will produce about 200 plants; an ounce, about 750 plants; 4 to 5 pounds to the acre. The following spring set out the roots in a permanent bed.



4 Washington Asparagus

### ✻ *4* Washington Rust-Resistant Asparagus

**The Newest Creation in Asparagus for the Home Garden or Market**

This rust-proof asparagus is the result of years of plant breeding, conducted by the Bureau of Plant Industry of the U. S. Department of Agriculture, with the object of eliminating rust, which has heretofore proven so disastrous to asparagus crops in all sections. This strain is not only practically free from rust and other diseases, but it is also larger and more vigorous. In color it is a dark green, with a heavy overcast of rich purple. Has a tight, pointed bud, and does not branch out until well beyond the market height. Makes a clean, straight growth. Produces the finest kind of green asparagus, both for home use or market. In appearance, when bunched for market, this asparagus can not be excelled. If you already have an asparagus bed it will pay you to plant some of this variety and note the improvement over the kind you are now growing. Our roots are the best we ever grew. While our stock is large, the demand has been very great, so advise ordering early.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 60 cts.; ½ pound $1.00; pound $1.75; 5 pounds $7.50, postpaid**

### *1* Palmetto **Produces large, always green Asparagus**

One of the most profitable asparagus on the market; mammoth in size, dark green, heavy yielding and early producing. A standard variety for all purposes. Always commands a high price in all markets.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 85 cts.; 5 pounds $3.75, postpaid**

## ASPARAGUS ROOTS

**Cultural directions are sent with every order of Asparagus Roots**

For a home garden, Asparagus Roots may be planted 18 inches apart in rows 2½ feet apart, thereby requiring about 100 roots for a patch 20x20 feet. 5,000 to 7,000 roots will plant an acre. If your garden is smaller or larger, order accordingly. Asparagus can be cut the following spring. Not less than 50 roots of the one kind supplied at the 100 rate. 250 roots or over at the 1,000 rate. 2,000 roots or over at the 5,000 rate.

**Asparagus Roots are out of season during June to October**

**69B50 PALMETTO. One-year-old roots. 25 for 50 cts.; 100 for $1.65, postpaid. By express, 1,000 roots $11.00; 5,000 for $50.00.**
**69B52 PALMETTO. Two-year-old roots. 25 for 65 cts.; 100 for $2.00, postpaid. By express, 1,000 roots $12.00; 5,000 for $55.00.**
**69B56 WASHINGTON. One-year-old roots. 25 for 70 cts.; 100 for $2.25, postpaid. By express, 1,000 roots $13.00; 5,000 for $60.00.**
**69B58 WASHINGTON. Two-year-old roots. 25 for 85 cts.; 100 for $2.75, postpaid. By express, 1,000 roots $14.00; 5,000 for $65.00.**

## Broccoli

**Somewhat Similar but Hardier than Cauliflower**



103 Early Angiers Broccoli

CULTURE.—Sow seed early in May. Set plants out in June or early July in rows two to three feet apart each way. Cultivate same as Cauliflower which it resembles. A packet will produce about 250 plants, about 3,000 plants to an ounce. Ready to use in 150 days.

### ✻ *103* Early Angiers

**150 days. Large White Heads**

The large white heads are handsome; of delicate flavor. More hardy than Cauliflower. Grown extensively in the northwest for shipping to our eastern markets. The most popular home or market sort. Matures its heads in 150 days.

**Packet 10 cts.; ½ ounce 40 cts.; ounce 75 cts.; ¼ pound $2.00; ½ pound $3.85; pound $7.50, postpaid**

## Brussels Sprouts "Miniature Cabbages"

CULTURE.—Excessive stem growth should be avoided by planting in good but not extra rich soil. Sow seed in April or June in the open ground, set plants in rows 3 feet apart, 18 inches apart in row. Break leaves from stem to aid formation of heads. A packet yields about 300 plants, an ounce 3,000 plants. Ready for use in about 125 days.

108 Brussels Sprouts

### ✻ *108* Danish Prize

**125 days. Large, Solid Sprouts**

This large headed variety has proven to be a decided advance on anything yet offered; being of half-dwarf, sturdy growth and producing abundantly large, solid, dark green sprouts of fine quality in 125 days.

**Packet 10 cts.; ounce 30 cts.; ¼ pound 75 cts.; ½ pound $1.35; pound $2.50; 5 pounds $11.25, postpaid**

INOCULATE THIS SEED WITH MULFORD CULTURE

# Green-Pod Bush Beans

INOCULATE THIS SEED WITH MULFORD CULTURE

CULTURE.—Succeed best in warm, sandy loam, enriched with well rotted stable or poultry manure. Must not be sown until the ground is warm and dry. Sow in drills 18 to 30 inches apart, 1 to 2 inches deep, placing the beans 2 to 3 inches apart in the drills; for a succession sow every 2 weeks until September. A packet will sow about 25 feet of row; use 1 pound to 100 feet of drill, 60 pounds to the acre. Bush beans are ready for use in 30 to 50 days. Cultivate frequently but shallow and never when the foliage is wet.

## * 14 Burpee's Stringless Green Pod Bush Bean

**31 days. One of the Earliest; Round Podded, Always Stringless, Tender and Crisp**

The Stringless Green Pod is now one of the most popular bush beans in America. In point of earliness it ranks among the first, in quality it is excelled by none, and in bearing ability it stands without a rival. The pods are round, fleshy and nearly straight; are borne in abundance through a long season, being ready for the table in about 31 days. They are five inches in length, rich green in color, very tender, and of highest and best flavor. They remain long in edible condition. Unexcelled for home use, or for market. Seed of medium size, yellowish brown color.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**



12 Bountiful

14 Burpee's Stringless Green Pod

## * 12 Bountiful Bush Bean

**35 days. A Continuous Bearer, Tender and Stringless**

An improved "Long Yellow Six Weeks," producing many more, better and larger green pods. It is very hardy, extremely early, very prolific and bears continuously for several weeks. The green pods are of large size, flat, solid, meaty, stringless and of delicious flavor. Excellent home garden or market sort. Ready for the table in 35 days. Seed a light yellow color.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**

## * 16 Fordhook Favorite Bush Bean

**32 days. A White Seeded, Stringless and Tender, Green Podded Sort**

A green podded bean, perfectly stringless, with white seeds, which can be used for soup or baked beans all winter. The bush grows from 18 to 20 inches high, with dark green foliage, producing an enormous yield of beautiful, meaty, almost round, green pods, averaging 5½ to 6½ inches long. Very brittle and juicy, and above all positively stringless at all stages of its growth; pods ready for use in 32 days. This variety will be found to be one of the best for either the home garden or market.

**Packet 10 cts.; ½ pound 30 cts.; pound 50 cts.;**
**5 pounds $2.00, postpaid**
**Not prepaid, 5 lbs. or over at 30 cts. per lb.; 100 lbs. $24.00**

## * 19 Maule's King of the Earlies

**30 days. The Earliest and Hardiest of the Green Podded Sorts**

An excellent variety producing round, green, long pods in 30 days. The plants are hardy and productive.

Owing to its enormous yielding qualities, large and handsome appearance and ability to withstand light frosts it should be extensively planted in all sections, early or late. Excellent home garden or market sort. A long distance shipper. Seed black.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.;**
**5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**

## 7 Round Pod Refugee

**48 days. Excellent Main Crop, Producing Round Green Pods**

Very popular in many sections; enormous yielder. The large plants are exceedingly hardy, with an abundance of foliage. Pods are perfectly round and straight, tender and of excellent table qualities; good for both the main crop and late planting. Very popular for the home garden, market and canners. Pods ready for use in 48 days.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.;**
**5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 24 cts. per lb.; 100 lbs. $21.00**

## 11 Black Valentine

**31 days. The Black Seeded Valentine Bean, Matures Early**

This bean withstands early and late frosts that kill other varieties. It yields enormously and the pods are one-third longer than most other green podded sorts; they are perfectly round and straight; ready for picking in 31 days. Owing to its handsome appearance it is a splendid sort for the market. Very popular in the South on account of its blight resisting qualities; a long distance shipper. Seed black, of medium size.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.;**
**5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 23 cts. per lb.; 100 lbs. $20.00**

## 18 Longfellow or French Stringless

**35 days. Long Green Round Pods of Excellent Quality**

This perfectly round, green podded bean is tender and prolific, and is one of the best varieties for the home garden. The pods are of fine quality, nearly stringless and exceedingly handsome. In production, very prolific; exhibits a profusion of highly beautiful, rich green pods 7 to 8 inches long, straight and round. When cooked the flavor is exquisitely delicious. The plant grows 14 to 16 inches high, bearing edible pods in 35 days. Seed purplish pink, mottled pale ochre red.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.;**
**5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 23 cts. per lb.; 100 lbs. $20.00**



16 Fordhook Favorite Bush Bean

# GREEN POD BUSH BEANS



10 Mammoth Stringless Green Pod

## ✻ 10 Mammoth Stringless Green Pod

**32 days. An Absolutely Stringless Round Podded Sort**

The handsome round pods are 6 to 7 inches long, dark green in color, very brittle and of superior quality. The plant grows large and erect, producing its pods very early, in about 32 days. It is one of the most productive varieties for the market or home garden. Seed dark yellow.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**

## ✻ 9 Full Measure

**35 days. Attractive, Long, Straight Pods**

This magnificent round podded bush bean bears long, round, dark green pods in 35 days; always solid, stringless and exceedingly prolific. The pods are of an attractive green color, 5 inches long, firm and tender, remaining fit for use many days after maturing. The plant is of a handsome, stiffly erect growth, very prolific and practically blight proof. Seed medium size, brown mottled with light yellowish drab.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**

## ✻ 20 Keeney's Stringless Refugee

**45 days. Perfectly Stringless, Brittle Pods**

The handsome, round, green pods average about 5 inches long and are brittle, tender, fleshy and perfectly stringless at all stages of their growth. Fit for the table in about 45 days. Its quality is superfine; for canning it is unequalled, and is very desirable for home or market garden. Seed light drab, thickly mottled purple.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**

## 5 Tennessee Green Pod

**32 days. The Earliest and Largest Podded Dwarf Sort**

This early snap bean is very popular in some sections of the south and where known in other parts of the country is considered of exceptional merit. The plants are large, somewhat spreading and prolific. The pods are very long, often six to seven inches, flat, irregular in shape, dark green and of exceptionally fine flavor. It is a hardy, vigorous mid-season sort, very productive. Fit to pick in 32 days. Seed of medium size, oval, flat, yellowish brown in color.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $23.00**

## 6 Dwarf Horticultural

**35 days. Excellent Either as a Snap or Shell Bean**

Also called Cranberry and Italian bean. A bush bean with large green pods, splashed with carmine. Pods ready for the table in about 35 days. Excellent either as snaps in the green state, shelled green or dry. They become fit for use as green shelled beans about 10 days later, and in this condition the beans are very large, easily shelled and about equal to the lima in quality. Seed pale buff mottled pink.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 24 cts. per lb.; 100 lbs. $21.00**

## ✻ 13 Earliest Improved Valentine Bush Bean

**32 days. An Early Standard Variety that Is Hard to Beat**

Our improved strain of this famous old reliable green podded bush bean is ready for the table in 32 to 35 days. As now perfected it has full, meaty round pods, which possess beauty, tenderness and superior flavor. It is an ideal snap short bean, and one that always sells well in the market. Plants grow uniformly about fifteen inches in height. Our Earliest Improved is a great improvement over the original Red Valentine and is now the most prolific and profitable bean of its kind. Seed is purplish pink splashed with pale buff.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 23 cts. per lb.; 100 lbs. $20.00**

13 Earliest Improved Valentine Bush Bean

## 8 Extra Early Refugee

**35 days. Sure Cropper, Very Early and Productive**

A green podded bush bean that is very widely known. It is an early form of the famous old Late Refugee or Thousand-to-One, maturing its pods in about 35 days. Almost certain to produce a crop even in unfavorable seasons; enormously productive. Suitable for early or late planting. A standard bush bean for home and market. Seed drab color, nearly covered with dark purple blotches.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**



9 Full Measure



20 Keeney's Stringless Refugee

INOCULATE THIS SEED WITH MULFORD CULTURE

# WAX POD BUSH BEANS

INOCULATE THIS SEED WITH MULFORD CULTURE

CULTURE.—Succeed best in warm, sandy loam, enriched with well rotted stable or poultry manure. Must not be sown until the ground is warm and dry. Sow in drills 18 to 30 inches apart, 1 to 2 inches deep, placing the beans 2 to 3 inches apart in the drills; for a succession sow every 2 weeks until September. A packet will sow about 25 feet of row; use 1 pound to 100 feet of drill, 60 pounds to the acre. Bush beans are ready for use in 30 to 50 days. Cultivate frequently but shallow and never when the foliage is wet.

## ✻ 27 Maule's Improved Butter Wax Bush Bean

27 Maule's Improved Butter Wax Bush Bean

**40 days. The Best Yellow Podded Bean for the Home Garden**

This bean was first offered by us as "Nameless Wax" in 1906, later known as Maule's Wingold Wax, and now Maule's Improved Butter Wax; at present, considered one of the best and handsomest general purpose wax beans. Its pods are straighter, more uniform in color and size, more attractive than any other wax sort and fully as productive. Snap pods very uniform in size, long to medium, very straight, round medium yellow, extremely brittle, absolutely stringless, without fibre and of excellent quality. The yellow pods are ready for use in about 40 days and are borne equally above and below foliage, never colored or splashed. Seeds are white with a little brown around the eye.

In addition to the above this bean is one of the earliest wax sorts, and is rust-proof and free from disease attacks, and all in all is unsurpassed.

**Packet 15 cts.; ½ pound 30 cts.; pound 50 cts.;**
**5 pounds $2.00, postpaid**
**Not prepaid, 5 lbs. or over at 33 cts. per lb.; 100 lbs. $30.00**

## ✻ 32 Maule's Profusion Wax

**48 days. A Distinct and Profuse Bearer of Handsome Round Yellow Pods**

The plants are literally covered with handsome pods which are round, of good size, full of meat, brittle and stringless. Producing its pods in 48 days, and continues in bearing a long time. Seed yellowish drab, mottled purple, a home garden sort.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.;**
**5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**

## ✻ 33 Unrivaled Wax

**33 days. Extremely Early with Creamy Yellow Wax Pods**

This handsome, attractive, wax podded bean is the earliest maturing sort. The dwarf plant is strong, well branched, and produces in about 33 days an enormous crop of beautiful, semi-transparent pale yellow pods. These pods average six inches in length, almost straight and remain tender for a long period. The flavor is excellent, seed small, flat, slightly kidney-shaped, color ochre brown.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.;**
**5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 27 cts. per lb.; 100 lbs. $24.00**

32 Maule's Profusion Wax

## 29 Maule's Cracker Jack Wax

**40 days. Exceedingly Productive and of Excellent Quality**

The plants are of strong, upright growth, which holds the pods well off the ground, protecting them from discoloration. The long bright yellow pods resemble Wardwell's Kidney Wax in shape, but are rounder and more meaty, of excellent flavor, very prolific. The attractive pods are fit for use in 40 days, making it a valuable sort for home garden and market. Seed light yellow in color.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.;**
**5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 24 cts. per lb.; 100 lbs. $21.00**

## 31 Round Pod Kidney Wax

**42 days. Round, Yellow Pods, Known as Brittle Wax**

This desirable round podded wax bean has attained the top notch among beans of this class. Producing unusually large round pods 5 to 6 inches in length, in about 42 days, which are very solid, meaty and tender, free from string, breaking brittle; the flavor is unsurpassed. Seed nearly all white with a little dark marking about the eye.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.;**
**5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 28 cts. per lb.; 100 lbs. $25.00**

## 30 Currie's Rust Proof Wax

**40 days. Best Variety Adapted to Early and Late Planting**

A very early beautiful wax bean, bearing an abundance of crisp, tender straight pods in 40 days. It is of excellent quality and delicious flavor. The handsome yellow pods are 5 to 6 inches long, oval shape, and absolutely rust proof. Vine very vigorous and productive, and is the hardiest of the wax sorts. Seed purplish black.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.;**
**5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**

33 Unrivaled Wax

# WAX-POD BUSH BEANS

## ✱ 17 Maule's Golden Carmine Wax Bush Bean

37 Pencil Pod Black Wax

**50 days. Large Yellow Stringless Pods, Tender and Prolific**

A bush bean of the Dwarf Horticultural type. The strong growing plants grow upright, very productive, producing very large flat pods of golden yellow color, splashed with carmine. Ready for the table as a snap bean in 50 days, as a shell bean about 10 days later. The pods are entirely stringless and tender at all stages of growth, making it very desirable as a snap bean. Seed is large, kidney shaped, color buff mottled, excellent for baking, one of the most desirable varieties for the home garden.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 27 cts. per lb.; 100 lbs. $24.00**

## ✱ 37 Pencil Pod Black Wax

**40 days. An Improved Prolific Black Wax, Very Productive**

The beautiful yellow, straight pods are from 6 to 7 inches long, well rounded, meaty and deeply saddle-backed. They are always solid, brittle and entirely stringless and of excellent quality, and are produced through a long season. The plants grow about 15 inches high, producing pods in 40 days, hardy and very prolific. Seed jet black.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 23 cts. per lb.; 100 lbs. $21.00**

## ✱ 26 Davis Kidney Wax

**35 days. Yellow Podded, White Seeded, Prolific and Early**

Large oval-shaped pods, ready to use in 35 days, of high table quality, and is adapted to home use or market and is not excelled for canning, having white seeds, which are very attractive in jars. The dry white kidney-shaped beans are good for winter use, either for soup or baking.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**

## 35 Improved Rust-Proof Golden Wax

**35 days. Strong Grower, Remarkably Productive**

This is one of the earliest and best dwarf sorts, remarkably free from spot or rust. The pods are of medium length, 4 to 5 inches, nearly straight, broad, flat and of golden yellow color, and are borne in great profusion, and we commend it to the public as a superior wax bush bean. The medium size pods are ready for the table in 35 days. Cooking quickly as snaps, shelling well when green, and of the highest quality. Seed white, marked with two shades of purple.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**

**PLAIN DIRECTIONS FOR CULTURE**
**are printed on every packet, ounce and pound, or fraction thereof, of Maule's Vegetable Seeds**

17 Golden Carmine Wax

26 Davis Wax

## 25 Wardwell's Kidney Wax

**40 days. Desirable for Every Climate. One of the Best**

The plant becomes loaded with long, broad and flat, beautiful yellow colored pods, which are fit for use in 40 days. Stringless and of a rich, luscious flavor, and exceedingly brittle. We can recommend this bean very highly to market gardeners. It always commands a ready sale. A great favorite for shipping, fine for the family garden. The white, mottled purple, dried beans are of a distinct kidney shape.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 27 cts. per lb.; 100 lbs. $24.00**

## 28 Golden Queen or Hodson Wax

**50 days. Most Productive Yellow Pods, Excellent Quality; Free from Spot or Rust**

An entirely distinct type of wax bean. Produces a healthy growing plant, resists rust and blight, and is remarkably prolific, with long, straight, attractive, light yellow, oval-shaped pods, brittle and tender, ready for use in 50 days. Of good quality and remarkable productiveness. Seed is purplish pink, mottled pale ochre red.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 23 cts. per lb.; 100 lbs. $20.00**

## Mulford Cultures
**FOR LEGUMES**

For inoculating Garden Beans, Lima Beans, Garden Peas and Sweet Peas. Be sure to specify which one you want to inoculate, as there is a different culture for each variety, otherwise we can not fill your order.

**One bushel size, 60 cts., postpaid; Two bushel size, $1.00, postpaid; Five bushel size, $2.25, postpaid**

Garden Size. This size only we can supply in a mixed culture to be used for any or all four varieties mentioned above. **35 cts. postpaid.**

## MATURITY DATES

**At the heading of all VEGETABLE SEED descriptions we are giving the maturity dates, starting from day of sowing the seed, thus: 50 days. This will tell you when you may expect vegetables ready for the table; of course the weather conditions must be favorable for producing the crop.**

23 Sure-Crop Stringless Wax

## ✻ 23 Sure-Crop Stringless Wax Bush Bean

**45 days. Early, Perfectly Stringless; a Sure Cropper**

While it resembles the well-known Currie's Rust Proof Wax in plant, pods and bean, it is in no way related to this variety, but is entirely different in quality, tenderness, and is stringless at all stages of its development. Produces pods in 45 days, which average 6 inches long, are flat, thick and meaty. The plants are very thrifty and hardy, resisting blight admirably and stand a remarkable amount of dry weather. Desirable for market or home gardeners. Seed is black.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**

**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**

## ✻ 34 Admiral Togo Wax Bush Bean

**38 days. The Greatest Rust Resisting Yellow Podded Bean**

This grand, extremely early, wax podded sort produces handsome and attractive light yellow pods 6 inches in length.

The plants are very vigorous, hardy and productive, maturing large, oval shape pods free from rust and other diseases and are ready to pick in 38 days. The table quality is delicious, having a peculiar delicate flavor. Its extreme earliness and disease-resisting power makes it a most desirable sort for the home garden or market. A good long distance shipper. Does well in all sections. Seed black.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**

**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $23.00**

## ✻ 22 Burpee's Kidney Wax Bush Bean

**42 days. Early Profuse Bearer of Handsome Lemon-Yellow Pods**

A productive yellow podded sort, producing handsome pods in 42 days, which are fleshy and flattened in form, often measuring 6 to 7 inches in length, and are entirely stringless and brittle, meaty and of fine flavor. The plant is of robust, upright growth and productive. Seed white with dark markings about eye.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**

**Not prepaid, 5 lbs. or over at 28 cts. per lb.; 100 lbs. $25.00**

34 Admiral Togo Wax

## ✻ Maule's Four Leaf Clover Mark ✻

We are using the Four Leaf Clover on all such varieties of vegetable seed that we consider the best in their class, knowing they will grow in all sections and soils, giving the best results. If you do not know what varieties to plant, we would suggest ordering such varieties as are marked with the Four Leaf Clover.

INOCULATE THIS SEED WITH MULFORD CULTURE

# Dwarf Shell or Field Beans

INOCULATE THIS SEED WITH MULFORD CULTURE

**Note:** Most of these field beans have a tendency to send out runners or trailers.

CULTURE.—Succeeds best in warm, sandy soil. Sow in drills 2 to 3 feet apart, placing the beans 2 to 3 inches apart and cover the seeds with 2 inches of soil. Can be sown any time from May until July 10, maturing the dry beans in about 60 to 65 days. A packet will sow about 25 feet of row, a pound about 200 feet; 30 to 45 pounds per acre. The following varieties are extensively grown for winter shelled beans:

## ✻ 15 Red Kidney Field Bean

**60 days. The Good Old-Fashioned Baking Bean**

This well known field bean is one of the best varieties for use as a dry bean. Producing large, flat, green pods, well filled with large, red, kidney-shaped beans, rich in flavor, and is one of the largest of all baking beans. A wonderful yielder, maturing its large, red, kidney-shaped beans, which are always in demand in every market, in about 60 days. Red Kidney is the favorite bean for baking. **Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**

**Not prepaid, 5 lbs. or over at 23 cts. per lb.; 100 lbs. $21.00**

## 21 Robust Pea or Navy Field Bean

**60 days. The Standard Sort for Winter Use**

This improved strain of white field bean, which was introduced by the Michigan Agricultural College, is such an improvement over the old standard sorts that it has taken the place of the Boston Pea and Burlingame Medium field beans. We recommend New Robust Pea Bean to our customers on account of its heavy yielding and disease-resistant qualities. The strong, upright plant carries the pods well above the ground, which keeps them from getting injured by wet weather before harvesting. Ripens its crop of medium size, dry, pearly white beans in about 60 days, and all at once, making it easy to harvest and thrash.

**Packet 10 cts.; ½ pound 25 cts.; pound 35 cts.; 5 pounds $1.35, postpaid**

**Not prepaid, 5 lbs. or over at 22 cts. per lb.; 100 lbs. $19.00**

## ✻ 24 White Marrowfat Field Bean

**65 days. The Largest White Seeded Sort**

This remarkable shell bean, grown so generally in all sections, is probably the most popular of all. Requiring only about 65 days to mature and ripen its large white beans. Plants are healthy and vigorous, absolutely free from all disease, a sure cropper, and a prodigious yielder. The dry white beans cook tender. Excellent for soup or baking.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**

**Not prepaid, 5 lbs. or over at 23 cts. per lb.; 100 lbs. $20.00**



24 White Marrowfat Field Bean

INOCULATE THIS SEED WITH MULFORD CULTURE

# Dwarf or Bush Lima Beans

INOCULATE THIS SEED WITH MULFORD CULTURE

CULTURE—Succeed best in warm, sandy loam, enriched with well rotted stable or poultry manure. Must not be sown until the ground is warm and dry. Sow in drills 3 feet apart, placing the eye down, 18 to 24 inches apart in the drills; or in hills 3 feet apart each way, allowing 1 or 2 plants to each hill. A packet will plant about 25 feet of row; use 1 pound to 100 feet, 25 to 30 pounds to the acre. Ready for use in 65 to 90 days.

## ✱ *60* Improved Fordhook Green Seeded Bush Lima Bean

**80 days. A True Bush Form, of the Famous Fordhook Bush Lima Bean, Producing Larger and Plumper Pods with Thicker, More Meaty, Always Green Beans**

58 Fordhook Bush

This decided improvement of Fordhook Bush Lima is so fixed that it will supersede that sort either for the home garden or market. Its strong, erect, true bush-form plant produces a thicker growth of dark green foliage, protecting the blossoms and pods from direct sun. The larger and plumper pods are produced in clusters of from five to eight. Each pod contains four to five thicker, more meaty, and plumper, always green beans. Improved Fordhook Bush Lima yields a very heavy crop in about 80 days, just as early as the original stock.

**Packet 15 cts.; ½ pound 30 cts.; pound 55 cts.; 5 pounds $2.25, postpaid**
**Not prepaid, 5 lbs. or over at 30 cts. per lb.; 100 lbs. $28.00**

## ✱ *64* Burpee's Improved Bush Lima

**85 days. Enormous Pods of Excellently Flavored Beans; Extremely Prolific**

This bean produces a magnificent crop of pods, which measure from 5 to 6 inches long by 1¼ inches wide. Compared with Burpee's Bush Lima, both pods and beans are much larger while the beans, either green or dry, are nearly twice as thick. The sturdy bushes are loaded with pods that are truly enormous in size. The luscious green beans, ready for use in about 85 days, are much larger than any bush lima.

**Packet 15 cts.; ½ pound 30 cts.; pound 50 cts.; 5 pounds $2.00, postpaid**
**Not prepaid, 5 lbs. or over at 28 cts. per lb.; 100 lbs. $25.00**

## ✱ *58* Fordhook Bush Lima

**80 days. The True Stiffly Erect Bush Form of the Popular "Potato" Lima. Enormous Bearer of Plump Pods Filled with Thick, Meaty, Tender Beans**

Fordhook produces a strong, erect, true bush-like growth (never prostrate or running). The foliage is of heavy texture and very dark green in color. The stalks that produce the blossoms are thrown out from the lateral and main stalks; the pods are borne in "clusters" of from four to eight. The pods measure from 4 to 5½ inches long, about 1¼ inches wide, by as much as three-fourths of an inch thick. The pods contain three to five large beans with an average of four. Maturing in about 80 days.

**Packet 10 cts.; ½ pound 30 cts.; pound 50 cts.; 5 pounds $2.00, postpaid**
**Not prepaid, 5 lbs. or over at 28 cts. per lb.; 100 lbs. $25.00**



60 Improved Fordhook Bush

## *62* Burpee's Bush Lima

**90 days. Beans as Large as Pole Limas; Luscious Quality and Productive**

A dwarf or bush form of the large climbing lima. The plant grows 18 or 20 inches high, and has an erect branching stem. The size and luscious flavor of the bean are exactly the same as with the climbing lima types, maturing in about 90 days.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**

## *61* Wood's Prolific Bush Lima

**65 days. The Earliest of all Limas; a Long and Continuous Bearer**

It is a distinct and valuable improvement over the original bush lima. Grown for its extreme earliness. Its true bush form plants are practically loaded down with pods, which are borne from early in the season and continue till frost. Pods contain 3 to 4 beans. Valuable as a shell bean for winter use. Ready for the table in 65 days.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 23 cts. per lb.; 100 lbs. $20.00**

## Mulford Cultures FOR LEGUMES

For inoculating Garden Beans, Lima Beans, Garden Peas and Sweet Peas. Be sure to specify which one you want to inoculate, as there is a different culture for each variety, otherwise we cannot fill your order.

**One bushel size, 60 cts., postpaid; Two bushel size, $1.00, postpaid; Five bushel size, $2.25, postpaid.**

**Garden Size.** This size only we can supply in a mixed culture to be used for any or all four varieties mentioned above. **35 cts. postpaid.**



64 Burpee's Improved Bush Lima Bean

INOCULATE THIS SEED WITH MULFORD CULTURE

# Pole Lima Beans

INOCULATE THIS SEED WITH MULFORD CULTURE

CULTURE.—A warm, sandy loam, enriched with well rotted stable manure is best. Must not be sown until the ground is warm and dry. When poles are used for support they should be set not less than 4 feet apart each way. Plant 4 to 6 beans to a pole, eyes down, 2 inches deep. When well started thin out to 2 plants to a pole. Cultivate frequently. Use 1 packet to 15 poles; 1 pound to 50 poles; 40 pounds to the acre. Ready to use in 75 to 90 days.





50 Giant Podded Pole

### ✱ 52 Maule's Evergreen Pole Lima

90 days. Named Because It Retains the Green Color the Best for Main Crop

Maule's Evergreen is a strong, robust, vigorous grower, very prolific, producing large green limas in 90 days. Is one of the best main crop pole lima beans, with enormous size pods. Some reaching 7 inches in length, and are produced in large clusters, with 5 to 6 large beans to a pod. The dry bean retains the green color longer than any other variety of which we know. When we add its unusual superb quality, we have a lima bean that is near perfection for the home garden or market.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**

**Not prepaid, 5 lbs. or over at 28 cts. per lb.; 100 lbs. $25.00**

### ✱ 50 Giant Podded Pole Lima

90 days. The Heaviest Cropping Mammoth Podded Sort

Pods measure 7 to 8 inches in length. The beans are of extra large size. The vines grow so rapidly that they make a tremendous growth of foliage which soon covers the poles, producing an abundant supply of tender, rich, buttery beans in about 90 days and bear until frost. No garden should be without this excellent giant podded pole lima.

**Packet 15 cts.; ½ pound 30 cts.; pound 50 cts.; 5 pounds $2.00, postpaid**

**Not prepaid, 5 lbs. or over at 30 cts. per lb.; 100 lbs. $25.00**

### ✱ 53 King of the Garden Pole Lima

90 days. A Standard Sort; the Gardener's Favorite

It is vigorous in growth and immensely productive. The vine begins to produce pods near the foot of the pole, and the bearing season continues without interruption until frost. The pods are large, numerous and well filled, and the beans are of mammoth size. The handsome pods often attain a length of five, six or even seven inches, with five or six full and perfectly formed beans in each pod. Ready for the table in 90 days.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**

**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**

### 49 Burpee's Sunnybrook

75 days. The Earliest Large Podded Pole Lima

The main feature of this fine new pole lima bean are its extreme earliness and tremendous prolificness. The combination of these two valuable characteristics is sure to win a foremost place for the variety in the home garden as well as with the market grower. The long flower-spikes are produced in great abundance from the base of the plant to the very summit of the vine, in some instances even before the vines have taken hold of the pole. The individual spikes carry from 5 to 10 pods of large size. Each pod is closely packed with 4, and often 5, large, thick, meaty, light green beans of the finest quality.

**Packet 15 cts.; ½ pound 30 cts.; pound 50 cts.; 5 pounds $2.00, postpaid**

**Not prepaid, 5 lbs. or over at 30 cts. per lb.; 100 lbs. $28.00**

### 54 Early Leviathan

80 days. Extremely Early, Large Podded Sort

Early, hardy, and prolific. It will not only give large lima beans earlier than any other strain, excepting Burpee's Sunnybrook Pole Lima, but is also extremely productive, both early and throughout the season. It is a strong grower, clinging well to the poles, and is a sure cropper. The pods differ from those of other early pole limas in being straighter and longer. They are borne in large clusters and contain 3 or 4, and sometimes 5, large beans each. An excellent home garden and market variety.

**Packet 10 cts.; ½ pound 25 cts.; pound, 45 cts.; 5 pounds $1.75, postpaid**

**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $23.00**

### 56 Dreer's Improved

90 days. The So-called Challenger or Potato Lima

Of peculiar shape, being thick and plump. It is a very "meaty" bean, of excellent flavor and high table quality. The beans are delicious. They remain green in the pod a long time after maturing. The pods, which are borne in clusters, average four or five inches in length, and each pod contains four or five thick beans., which shell out more beans than other pole limas. Fit for picking in 90 days.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**

**Not prepaid, 5 lbs. or over at 28 cts. per lb.; 100 lbs. $25.00**

### 57 Carolina or Sieva

75 days. The Baby Lima, Known as the Butterbean of the South

This very early and reliable small seeded pole lima is especially adapted for planting in the south; does equally as well planted in the north, especially in sections where early frosts will not permit other limas to mature their crop. A continuous and prolific bearer, maturing its pods in 75 days and continues until frost. Makes an excellent dried lima bean for winter use.

**Packet 10 cts.; ½ lb. 25 cts.; lb. 40 cts.; 5 lbs. $1.50, postpaid**

**Not prepaid, 5 lbs. or over at 23 cts. per lb.; 100 lbs. $20.00**



53 King of the Garden

INOCULATE THIS SEED WITH MULFORD CULTURE

# Pole or Climbing Beans

INOCULATE THIS SEED WITH MULFORD CULTURE

CULTURE—Sow when the ground is warm and dry. If poles are used for supports, set 4 feet apart each way. Plant 6 to 8 beans to a pole, 2 inches deep; when started, thin to 4 plants. Use 1 packet to 20 poles; 1 pound to 100 poles; 20 to 30 pounds to the acre. Ready to use in 55 to 80 days.

46 Maule's Noxall Pole Bean

## ✱ 46 Maule's Noxall Pole Bean

55 days. The Earliest Green Podded Pole or Corn Hill Bean

Maule's Noxall is a sure cropper, giving large crops when others are an entire failure. The green pods are long, round and tender, maturing in 55 days; excellent for planting among corn; good for either snap or shelled beans. Seed mottled putty color, with brown striping. This bean has been grown by many of our customers to the exclusion of all others.

**Packet 15 cts.; ½ pound 30 cts.; pound 55 cts.; 5 pounds $2.25, postpaid**
**Not prepaid, 5 lbs. or over at 35 cts. per lb.; 100 lbs. $30.00**

## ✱ 43 Improved Kentucky Wonder or Old Homestead

58 days. The Most Popular and Widely Planted of All Pole Beans

We believe this variety is the most practically useful of the green podded pole beans suitable for use as snaps, ready to pick in 58 days. Bears pods in large clusters, which are medium light green, very long, often reaching nine or ten inches, curved and twisted, nearly round and very crisp. Seed dun colored. One of the very best pole snap beans.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 21 cts. per lb.; 100 lbs. $19.00**

## 45 Lazy Wives

70 days. One of the Best for Snaps; Also for Dry Beans

The green pods are wonderfully broad, thick, fleshy and above all, stringless. They retain their rich, stringless and tender qualities until they are ripe. The pods are from 5 to 6 inches long, rich and fine flavored; ready for picking in 70 days. Seed nearly round and pure white.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 24 cts. per lb.; 100 lbs. $21.00**

## ✱ 42 Kentucky Wonder Wax

55 days. Large Golden Yellow Pods, Tender and Stringless

This wax podded pole bean commences to bear in 55 days, and keeps on producing until killed by frost. Vines densely laden with a solid mass of long, thick yellow pods, entirely stringless. Seed dark brown.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $23.00**

## 38 Golden Cluster

70 days. Enormous Yielder of Large Golden Yellow Pods

The finest of all the wax podded pole beans. It bears profusely very large, flat, golden yellow pods in clusters of three to six from bottom to top of pole, and continues in bearing until frost. Can commence picking pods in 70 days. Seed white. An enormous cropper of large pods.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 28 cts. per lb.; 100 lbs. $25.00**

## 39 Scotia or Striped Creaseback

**70 days. Especially Suitable for Growing on Corn for Snaps**

A hardy and very productive green podded cornfield bean. The vines are sturdy and of good climbing habit. The pods are long, about six inches, very cylindrical or completely rounded, distinctly crease-backed, very fleshy, fine grained, attractive and of excellent quality. The color when in condition for use as snaps is light silvery green. Seed medium, kidney shaped, mottled putty color with dark striping.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**

## 47 Scarlet Runner

75 days. An Ornamental Climber Also Useful for the Table

Of strong, quick growth, bearing large sprays of bright scarlet flowers. The pods are tender and tasty while young. Climbs well and is often grown for ornament.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**

## 41 McCaslan

58 days. The White Seeded Green Pod Snap or Shell Bean

Produces large, quick growing vines which soon cover the poles, bearing a very heavy crop of handsome green pods about 8 inches in length in 58 days; are very meaty, stringless and of delicious flavor. The vines produce their pods very early and continue to bear immense quantities of snap pods throughout the season. The dry beans being white, make an excellent soup or bake bean for winter use.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 24 cts. per lb.; 100 lbs. $21.00**

## 44 French Asparagus

80 days. Long, Tender Green Pods for the Home Garden

A green podded snap pole bean. Vines are rampant growers producing an enormous crop of tender and palatable snap pods in 80 days which grow 2 feet or more in length. Very productive and of excellent quality for snap-shorts. Seed light brown. **Packet 15 cts.; 2 packets 25 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.50, postpaid**



44 French Asparagus Pole Bean

43 Improved Kentucky Wonder

# MAULE'S TABLE BEETS

CULTURE—For earliest use and market, sow seed of any round sort under glass, in February or March, and transplant to open ground in March or April. Seed for main crop may be sown in the early spring as soon as ground can be worked. For table beets sow in drills 18 inches apart, and thin to stand 3 to 4 inches apart in the rows. A packet will sow a row about 25 feet long; use 1 ounce to 100 feet; 5 to 6 lbs. per acre. The round and turnip shaped beets are best for spring and summer; the half long kinds for winter. Make successional plantings and cultivate freely. They are fit for use in 35 to 65 days. Beet tops are much used for greens, being cooked like spinach.

## ✾ 66 Maule's Blood Turnip Beet

**50 days. The Best of Them All**



66 Maule's Blood Turnip Beet

Maule's Blood Turnip Beet has given such excellent satisfaction that it still retains its position at the head of our list. It is very early, nearly as early as Egyptian, ready for the table in about 50 days. The color is a rich dark red, and shape is globular. It is free from side or fibrous roots, being always smooth. It is excellent for forcing for a main spring or summer crop, or for use in winter, as it is a good keeper. It always cuts and cooks a rich, dark blood red; is tender, sweet and crisp, and is in every way the standard sort for the market or home gardener. Maule's Blood Turnip Beet has long been regarded as the standard of excellence by more than 50,000 successful gardeners, who plant it year after year in preference to any other.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 50 cts.; ½ pound 85 cts.; pound $1.50; 5 pounds $6.25, postpaid**



## ✾ 81 Maule's Dark Red Egyptian

**35 days. The Earliest of All Beets for Home or Market**

The Egyptian beet is one of the most popular varieties among market gardeners for forcing purposes. Justly or unjustly it is considered to be the earliest of all. It certainly will bear close planting in the valuable space under glass or in a warm garden in early spring. It is turnip shaped, and when young is crisp and tender. In color it is dark red. Ready for use in 35 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.00, postpaid**

## ✾ 84 Detroit Dark Red

**50 days. Excellent for the Home Garden or Canning**

This early globe-shaped beet of excellent quality is especially esteemed on account of its dark red color, which extends entirely through the beet, and without the light colored rings seen in some varieties. The medium sized beets are smooth and handsome and are now being largely used for canning as well as for the home garden or market. It retains its good quality even after it gets large, and is an excellent variety on this account for fall use as well as for spring. Maturing in about 50 days.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 25 cts.; ½ pound 40 cts.; pound 65 cts.; 5 pounds $3.00, postpaid**

## ✾ 74 Eclipse

**45 days. Desirable for Home Gardens or Bunching**

We have a strain of extra purity and merit, particularly noted for earliness. It is indeed high praise to say that our Eclipse beet is almost as early as Crosby's Egyptian, for the latter has been long accepted as one of the earliest; Eclipse has ever been recognized as superior to Egyptian in table value. Our strain has small top and is smooth, fine grained and tender, with bright red color. Maturing in 45 days. For home gardens it is one of the best.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 25 cts.; ½ pound 40 cts.; pound 65 cts.; 5 pounds $3.00, postpaid**



82 Maule's Market Gardeners Beet

## ✱ 82 Maule's Market Gardeners

**55 days. Always Good. Never Past Its Prime**

This all season table beet is one of the best for general cultivation for home use or for market gardeners. Makes a very rapid growth from the start, often larger than Egyptian, age for age. It continues to grow for a long period, making a heavy root for winter use. Only one sowing is necessary to produce early beets for the table and a main crop for winter use. It is a good keeper and may be used all winter. When cooked, it is dark red in color, and of unsurpassed table quality. Fit for use in 55 days. An all seasons table beet for all purposes.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

## 69 Early Yellow Turnip

**45 days. The Sweetest of All Beets**

An early, bright yellow turnip beet, maturing in about 45 days, excellent for table use. Both skin and flesh is of a bright yellow color, sweet and tender, a marked contrast to the deep red coloring of the other strains. The roots are round and smooth and are of good size. Should be in every home garden.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 40 cts.; ½ pound 65 cts.; pound $1.15; 5 pounds $5.00, postpaid**

## 76 Philadelphia Early Turnip

**50 days. The Favorite Beet for Main Crop**

An extra early, light-colored, turnip-shaped beet, originating in Philadelphia. The flesh is light red, zoned with white, and matures rapidly. The top is light green and small, which makes it suitable for growing under sash. It is especially rich in sugar and remains tender longer than any other variety. Our stock is pure and gives excellent satisfaction.

**Packet 5 cts.; ounce 15 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 90 cts.; 5 pounds $4.00, postpaid**

## 71 Maule's Market King

**65 days. The Best Half Long Beet for Winter Keeping**

Market King is a quick grower and soon reaches maturity; one of the best main crop beets. An excellent winter keeper. The solidity, fineness and firmness of its bright red flesh make it one of the best keeping varieties. It is always a ready seller on the market stall, where a symmetrical shaped beet is wanted.

On the points of flavor and table quality, we would lay especial emphasis, for it is an ideal beet for household use. It can be used at all stages of growth, ready for use in about 65 days, and it is almost needless to say that a sweet and succulent half long blood beet like this is sure to become a favorite. An excellent Market Gardener's basket beet.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**



70 Maule's Early Wonder Beet

## ✱ 70 Maule's Early Wonder

**40 days. Extremely Early, Deep Red, Tender and Sweet**

This wonderful early beet is the result of years' reselecting and improving, and is now so perfected that we believe it is one of the earliest and best turnip-shaped beets grown. It is much earlier than Crosby's Egyptian, maturing in about 40 days, of perfect shape and beautiful, deep red color. The tops are not quite as large as Crosby's Egyptian, which permits close planting and is excellent for bunching; a desirable early sort for the home garden as well as for market.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.00, postpaid**

89 Lucullus Swiss Chard

## ✱ 89 Lucullus Swiss Chard

**21 days. The Cut and Come Again Spinach Beet**

This handsome and distinct variety is a great acquisition. The stalks are as thick and broad as rhubarb. The plants grow to a height of from 2 to 2½ feet, and the stalks are from 10 to 12 inches long below the leaf and 1½ inches broad. These stalks are delicious when cooked and should be served in the same manner as asparagus. The leaf portion is heavily crumpled or savoyed and is very crisp and tender. It is cooked and served in the same manner as spinach. The leaves and stalks, being served as separate vegetables, afford two distinct dishes from the same plant at one time. Can start cutting in about 21 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.00, postpaid**

## 88 Large Ribbed White Swiss Chard

**25 days. Provides "Greens" from Early Spring Until Frost**

It seems American people are becoming more acquainted with the desirability of having a little Swiss Chard or Spinach Beet in their garden. This beet is grown for its leaves only. The middle of the leaf or mid rib is cooked and served like asparagus. The other portions of the leaf may be used like spinach. Ready to cut in about 25 days .

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.00, postpaid**

Form No. 6001

**Post Office Department** No. _____

THIRD ASSISTANT POSTMASTER GENERAL

DIVISION OF MONEY ORDERS

Stamp of Issuing Office

The Postmaster will insert

here _____

the office drawn on, when the office named by the remitter in the body of this application is not a Money Order Office.

Spaces above this line are for the Postmaster's record, to be filled in by him

# Application for Domestic Money Order

Spaces below to be filled in by purchaser, or, if necessary, by another person for him

Amount

_____ Dollars _____ Cents

Pay to Order of } WM. HENRY MAULE, INC.,

(Name of person or firm for whom order is intended)

Whose Address is } No. _____ Street

Post Office } PHILADELPHIA,

State Pennsylvania.

Sent by _____

(Name of Sender)

Address of sender } No. _____ Street

PURCHASER MUST SEND ORDER AND COUPON TO PAYEE

c5—

When sending us money, use this application. Take it to your Postmaster and procure a Money Order. If not a Money Order Office, he will send application to nearest Money Order Office by mail.

# Fees for Money Orders Drawn on Domestic Form

Payable in the United States, including Hawaii, Porto Rico, and the United States Virgin Islands, or in Guam and Tutuila (Samoa); also for orders payable in Antigua, Bahamas, Barbados, Bermuda, British Guiana, British Honduras, British Virgin Islands, Canada, Canal Zone, Cuba, Dominica, Grenada, Jamaica, Martinique, Montserrat, Nevis, Newfoundland, Philippine Islands, St. Kitts, St. Lucia, St. Vincent, and Trinidad and Tobago.

| | | | |
|---|---|---|---|
| **For Orders** | From $0.01 to | $2.50 | 3 cents. |
| | From $2.51 to | $5.00 | 5 cents. |
| | From $5.01 to | $10.00 | 8 cents. |
| | From $10.01 to | $20.00 | 10 cents. |
| | From $20.01 to | $30.00 | 12 cents. |
| | From $30.01 to | $40.00 | 15 cents. |
| | From $40.01 to | $50.00 | 18 cents. |
| | From $50.01 to | $60.00 | 20 cents. |
| | From $60.01 to | $75.00 | 25 cents. |
| | From $75.01 to | $100.00 | 30 cents. |

**Memoranda of Issuing Postmaster:**

---

---

If order is purchased through Rural Carrier, he will fill spaces below:

Carrier's receipt No. ----------

---------- , Carrier.

NOTE.—The maximum amount for which a single Money Order may be issued is $100. When a larger sum is to be sent additional Orders must be obtained. Any number of Orders may be drawn on any Money Order office on any one day.

Applications must be preserved at the office of issue for three years from date of issue.

C5—7155 (EDITION JUNE, 1924) GOVERNMENT PRINTING OFFICE

# ✻ 67 MAULE'S ALPHA BEET



67 Maule's Alpha Beet

**40 days. Best Extra Early Beet for Table or Market**

Maule's Alpha beet is ready for market in about 40 days. It is turnip shaped; a little deeper than Crosby's Egyptian. The flesh is of a dark crimson color, and is handsome in appearance. It has a rich, sweet flavor when cooked, and is tender and free from fibre and toughness. Undoubtedly one of the best extra early table or market beets.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.00, postpaid**

## 86 Maule's Improved Long Red

**65 days. Heavy Cropper and a Good Keeper**

Next to Market King this is the best long red beet on the market, of unexcelled quality for table and live stock. It has yielded twelve tons to the acre. In color it is rich carmine, and in quality it is sweet and tender. In rich ground it may be sown with advantage in June as a second crop. It will not be injured by the October frosts and will produce a great abundance of first-class root food for winter, either for table or stock. Matures in about 65 days.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 90 cts.; 5 pounds $3.75, postpaid**

**Order all Seeds and Collections by NUMBER or Name; if by NUMBER only, be sure to give correct number.**

## 78 Crimson Globe 41 days. Tender and Delicious

A handsome and medium size, globe shape sort, entirely free from rootlets; a grand second early sort, ready for use in 41 days. The foliage is small but just right for bunching or for forcing under glass. Of a rich bronze purple, borne on slender stems which occupy but a small portion of the root. The flesh is a rich blood red, slightly zoned or ringed in a most beautiful manner, making it very attractive in appearance; always sweet and tender.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**

### MATURITY DATES

**At the heading of all VEGETABLE SEED descriptions we are giving the maturity dates, starting from day of sowing the seed, thus: 42 DAYS. This will tell you when you may expect vegetables ready for the table; of course, the weather conditions must be favorable for producing the crops.**

## ✻ 77 Crosby's Egyptian

**42 days. The Standard Early Beet. Popular Everywhere**

A distinct improvement on the older forms of Egyptian beet, with a larger and more globular root. It is extremely early. Produces a most desirable turnip shaped beet of presentable size in about 42 days, making it a favorite with market gardeners for earliest sales.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.00, postpaid**



77 Crosby's Egyptian Beet

91 Edmand's Early Turnip Beet

## ✻ 91 Edmand's Early Turnip

**42 days. Good Main Crop Beet**

An excellent early variety, producing a desirable turnip-shaped beet, with both skin and flesh of a deep blood red. Very sweet and tender. A standard sort of well established merit; maturing in about 42 days; one of the best beets to follow the extra early varieties and for late crop; well adapted to forcing. This beet has become very popular as a home garden sort or for the market gardener wanting an ideal turnip-shaped blood red beet.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 25 cts.; ½ pound 40 cts.; pound 65 cts.; 5 pounds $3.00, postpaid**

## 75 Early Bassano

**48 days. Excellent for the Home Garden**

A very early turnip-shaped variety of beet, producing large light red colored roots, which are of high table excellence. It has rose colored flesh arranged in alternate white rings. Tender and sweet.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 90 cts.; 5 pounds $4.00, postpaid**

## 90 Mixed Table Beets

**35 to 65 days. One Planting Will Give an Ample Supply All Summer**

Contains an assortment of beets, some of which will mature in about 35 days and continue until the late sorts are ready, which is in about 65 days, so that one planting will give a supply of delicious beets all summer.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 90 cts.; 5 pounds $4.00, postpaid**

## *Beets for Stock Feeding*

# SUGAR BEETS

CULTURE.—Sow the seed in May or early June in drills 2 to 3 feet apart. Cover the seed with 1 inch of soil and thin to stand about 8 to 12 inches apart in the rows. Use a packet to 25 feet of drill; 1 ounce to 100 feet, 5 to 6 pounds per acre. A light loamy soil is best. Cultivate frequently. Matures in 60 to 65 days.

93 Klein Wanzleben Sugar

### ✻ *92* Imperial Sugar — 65 days. One of the Best for Stock Feeding

One of the best for stock feeding purposes. Of easy and cheap production, with rich sugary quality. The crop has reached 30 tons per acre, and single specimens have weighed 35½ pounds. Matures in 65 days.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 25 cts.; ½ pound 40 cts.; pound 65 cts.; 5 pounds $2.50, postpaid**

### *93* Klein Wanzleben Sugar

**60 days. Best for Sugar Making or Stock Feeding**

The roots are 7 to 8 inches long. They can be grown as close as 5 inches apart in the row and 2 feet between the rows. Smooth, with a broad shoulder gradually tapering toward the base. An enormous yielder, grown extensively in many sections for sugar. Highly recommended as a winter food for cows. Ready in 60 days.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 25 cts.; ½ pound 40 cts.; pound 65 cts.; 5 pounds $2.50, postpaid**



92 Imperial Sugar

# MANGELS For Stock Feeding

CULTURE.—Sow the seed in May or early June in drills 2 to 3 feet apart. Cover the seed with 1 inch of soil and thin to stand about 8 to 12 inches apart in the rows. Use a packet to 25 feet of drill; 1 ounce to 100 feet, 5 to 6 pounds per acre. A light loamy soil is best. Cultivate frequently. Matures in 85 to 110 days.

### ✻ *94* The Jumbo — 110 days. The Best Long Red Mangel

This mangel is the finest of its class; the best long red fleshed mangel. Heaviest cropper of all. Matures in 110 days.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 25 cts.; ½ pound 40 cts.; pound 60 cts.; 5 pounds $2.35, postpaid**

### ✻ *95* Maule's Gate Post — 90 days. A Heavy Yielder

One of the finest of yellow mangels. Flesh white. Ready in 90 days.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 25 cts.; ½ pound 40 cts.; pound 60 cts.; 5 pounds $2.35, postpaid**

### *96* Yellow Tankard — 95 days. Sweet and Productive

Flesh yellow, zoned with white. Matures in 95 days.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 25 cts.; ½ pound 40 cts.; pound 60 cts.; 5 pounds $2.35, postpaid**

### ✻ *101* Giant Half Sugar

**90 days. A Big Cropper**

This mangel is white, with a rose top; flesh white. Combines best qualities of sugar beets and mangels; fit for use in 90 days.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 25 cts.; ½ pound 40 cts.; pound 60 cts.; 5 pounds $2.50, postpaid**

### ✻ *102* Champion Yellow Globe

**85 days. For Shallow Soils**

Skin rich orange, flesh white with yellow rings. Matures in 85 days; splendid keepers. One of the best for stock feeding.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 25 cts.; ½ pound 40 cts.; pound 60 cts.; 5 pounds $2.35, postpaid**

94 The Jumbo Mangel

102 Champion Yellow Globe Mangel

95 Maule's Gate Post Mangel

# MAULE'S CABBAGE

CULTURE.—Cabbage is a very gross feeder, and well repays heavy manuring and high culture. It succeeds best on well drained soil. The plants are started in frame or seed bed, and afterward transplanted. Seed for early cabbages may be started in autumn in a cold frame, or in early spring in a hot bed. For main crop, summer and autumn cabbage, the seed should be sown in a rich border in the open air, in May or June. Sow shallow; a packet will produce about 250 plants, an ounce 3,000 plants; ¼ pound for an acre. Set plants 1½ by 3 feet apart.

## Maule's First and Second Early Cabbages

**Ready to use in about 60 to 90 days**

110 Golden Acre Cabbage

### ✱ *110* Golden Acre Cabbage

**70 days. The Earliest Large Round Headed Sort**

Golden Acre has proven to be one of the most profitable home garden or market varieties for the early crop. Plants are dwarf, allowing close planting; the solid heads are as round as a ball, measuring, when fully matured, about 9 inches in diameter, the average weight of which is 5 pounds; hard as a cannon ball, solid and very uniform. The large size heads mature in 70 days and practically all at one time, and each is exactly like one another in size and form. Our selected stock of this grand cabbage is unexcelled—grown for us in Denmark by the originator.

**Packet 15 cts.; ounce 75 cts.; ¼ pound $2.00; ½ pound $3.85; pound $7.50; 5 pounds $35.00, postpaid**

### *115* Maule's Winningstadt

**85 days. Remarkably Hard and Solid**

Maule's Winningstadt matures its solid heads in 85 days. The heads are slightly larger than Wakefield and of the proper cone-shaped form. It is a sure header, even where other sorts fail, and seems less liable to the attack of the cabbage worm than other sorts.

**Packet 5 cts.; ounce 30 cts.; ¼ pound 75 cts.; ½ pound $1.35; pound $2.50; 5 pounds $11.25, postpaid**

### *112* Maule's Earliest Express

**70 days. The Earliest of the Pointed Head Sorts**

We first introduced this cabbage in 1887. With First Early it holds the place as the earliest cabbage in cultivation, as it has produced fair sized, marketable heads in 70 days from the sowing of the seed. There are few loose leaves, and almost every plant forms a head.

**Packet 10 cts.; ounce 30 cts.; ¼ pound 75 cts.; ½ pound $1.35; pound $2.50; 5 pounds $11.25, postpaid**

### ✱ *116* All Head Early

**90 days. The All Year Round Large Flat Head Cabbage**

It has proven itself to be adaptable to a wide range of both soil and climate, and is well worthy of recognition as a standard American sort. It is a money maker for gardeners, and a very desirable sort in every garden. It is the earliest of large cabbages, being ready for the table or market in about 90 days. All Head Early in size of heads is one-third larger than Maule's First Early or Copenhagen market. The deep, flat heads are remarkably uniform in shape, size and color. Good quality and tenderness are marked features. The compact habit of growth of All Head Early cabbage renders close planting feasible. A good early spring, summer or winter sort.

**Packet 10 cts.; ounce 30 cts.; ¼ pound 85 cts.; ½ pound $1.50; pound $2.75; 5 pounds $12.50, postpaid**

113 Maule's Prize Jersey Wakefield Cabbage

### ✱ *113* Maule's Prize Jersey Wakefield

**75 days. Very Early, Solid, Pointed Head Cabbage**

Maule's Prize Jersey Wakefield is the earliest and finest strain of this variety. Grown from selected heads only, and is of the best quality. It has few outer leaves, and in compactness and regularity our strain cannot be surpassed. The thick stout leaves and uniform habit makes it the best sort for very early and close setting. It frequently matures large, hard conical-shaped heads of splendid eating quality within 75 days. We offer only Long Island grown seed.

**Packet 10 cts.; ounce 35 cts.; ¼ pound 90 cts.; ½ pound $1.60; pound $3.00; 5 pounds $12.50, postpaid**

116 All Head Early Cabbage

### ✱ *118* Charleston Wakefield

**90 days. An Improved and Larger Form of Jersey Wakefield**

The Wakefield, with its pointed heads, held the leading place among early cabbages for several decades. It is so reliably early and so genuinely good that nothing can wholly supersede it or drive it out of the markets.

The Charleston Wakefield is an improved and larger form of Maule's Prize Wakefield. It requires rather more time to reach maturity, but it yields fully twice the crop of the original Wakefield cabbage. It comes along in a close succession to the earliest cabbage crop producing its heads in about 90 days. It is a strain which cannot be profitably over-looked by any gardener, whether it is intended for a private garden or to be sent to market.

Charleston Wakefield is a good keeper and may be planted as a second crop to mature in the autumn, if desired. It is a first rate shipper, and in great favor with everybody who knows it.

**Packet 10 cts.; ounce 30 cts.; ¼ pound 75 cts.; ½ pound $1.35; pound $2.50; 5 pounds $11.25, postpaid**

**Customers may order 2 pounds or over at the 5 pound rate.**

# ✱ *111* Maule's First Early Cabbage

**70 days. This Splendid and Profitable Extra Early Flat-Headed Cabbage Is the Rival of the Famous Wakefield Produces Fine, Solid Good Sized Heads, Fit for the Table or Market in 70 Days from Sowing the Seed**

Maule's First Early is what is wanted for home or market. Its shape, habit of growth and general aspect are well shown in the illustration. It can safely be planted as close as Wakefield and is a sure header. It excels Wakefield and all other early cabbages in solidity of head; in fact, the head is as hard as a stone. It is a choice market sort on account of both shape and quality. It is a beautiful cabbage in appearance, being handsome in color and general uniformity.

No wonder the buyers of early cabbages select these attractive heads when displayed on the market stalls. Almost anybody would pick out one of these solid flat heads in preference to a round or pointed head variety.

Many of our customers have cleaned off their entire crop of Maule's First Early before they have started to cut Early Wakefield, or Early Flat Dutch. We have harvested a fairly good crop of this seed this year, and as Maule's First Early cabbage is so popular with our customers we fear we will not have enough to go around, so advise ordering early.

111 Maule's First Early Cabbage

**Packet 15 cts.; ounce 60 cts.; ¼ pound $1.75; ½ pound $3.25; pound $6.00; 5 pounds $27.50, postpaid**

130 Pe-Tsai Chinese Cabbage

## ✱ *130* Pe-Tsai

**60 days. Chinese or Celery Cabbage**

Chinese cabbage is so easily grown, that it should be in every garden. It is a dainty table vegetable either shredded as slaw, cooked as other cabbage or trimmed to be eaten as celery. It should be sown early for Spring use, or grown like late cabbage planted in July or August for Fall use. When bleached it is almost clear white, and is very crisp and tender. Grows very quickly, being ready to eat in 60 days. Full cultural directions are printed on each package.

**Packet 10 cts.; ounce 30 cts.; ¼ pound 85 cts.; ½ pound $1.50; pound $2.75; 5 pounds $12.50, postpaid**

120 Maule's Early Baby Ball Head Cabbage

## *120* Maule's Extremely Early Baby Ball Head

**68 days. An Excellent Early, Round, Solid Head Sort for the Home Garden**

Its extreme earliness makes it a desirable sort for forcing—producing firm, well-shaped, round heads in about 68 days from time of sowing of seed. Maule's Extremely Early Baby Ball Head Cabbage produces small, unusually solid white heads which are crisp and of delicious quality in about six weeks after setting out the plants. The peculiar advantage of this extremely early cabbage is that it requires very little space to grow, in comparison to other early varieties of cabbage; also its remarkable firmness and delicious taste. Originator's stock, grown in Denmark.

**Packet 10 cts.; ounce 50 cts.; ¼ pound $1.40; ½ pound $2.65; pound $5.00; 5 pounds $22.50, postpaid**

## ✱ *117* Maule's Early Flat Dutch

**90 days. Large, Solid, Flat Heads**

An excellent early maturing cabbage, producing large, solid heads of uniform shape, flattened on top as shown in the illustration. Fully developed heads frequently measure 10 to 12 inches across and weigh 12 to 15 pounds each. It also is fine grained and of dainty flavor. The large, flat heads are borne on short stems and are very solid. A sure cropper; practically every plant will form a good, solid head, which are ready to use in about 90 days. It succeeds everywhere, but seems particularly suited to the South, as it has strong heat resisting qualities. This variety has long been popular among growers, both for home or market.

**Packet 10 cts.; ounce 30 cts.; ¼ pound 75 cts.; ½ pound $1.35; pound $2.50; 5 pounds $11.25, postpaid**

**Customers may order 2 pounds or over at the 5 pound rate.**



117 Maule's Early Flat Dutch Cabbage

# MAULE'S THREE DESIRABLE CABBAGES

119 Copenhagen Market Cabbage

## Early, Medium and Late
## ✱ *119* Copenhagen Market

**75 days. The Best Early Round Headed Cabbage. Stands Longest Without Bursting**

Copenhagen Market is certainly a valuable early maturing cabbage, producing round hard heads of the finest quality for the table or market in seventy-five days. It is the most popular early cabbage in the markets of Copenhagen, and has become very popular in America. Market gardeners here who tried it are strong in its praise on account of its extreme earliness and solid ten pound heads, with a small core and always of excellent quality, making it a good seller. The plants are short stemmed, producing heads almost on the ground. The light green colored leaves are medium in size, saucer shaped, and are always tightly folded; the plants may therefore be set closer than most other early varieties. It is a vigorous grower and yielder, as are all cabbages from Denmark, and an excellent keeper. A most excellent round headed sort for the home garden, as well as for the market gardener whose trade requires a large solid head early in the season. Our stock of Copenhagen Market comes to us direct from the originator in Copenhagen, Denmark, which we can highly recommend.

**Packet 10 cts.; ounce 40 cts.; ¼ pound $1.00; ½ lb. $1.85; lb. $3.50; 5 lbs. $16.25, postpaid**

## ✱ *126* Maule's Midsummer

**95 days. Controls the Garden or Market from June to October. The Best of all Cabbage for Warm Weather**

This intermediate sort matures in about 95 days, soon after All Head Early, producing much larger heads, of unsurpassed beauty and solidity. It has noteworthy compactness of growth, which permits close planting. Midsummer is a remarkably sure and uniform header, and is one of the most profitable market varieties. It's a truly fine summer cabbage in all respects, producing from June until October.

Maule's Midsummer cabbage has already met with wide appreciation and hearty endorsement, and we do not know of a sort of more commercial importance to market gardeners for warm weather culture.

**Packet 10 cts.; ounce 30 cts.; ¼ pound 75 cts.; ½ pound $1.35; pound $2.50; 5 pounds $11.25, postpaid**

### YOUR GARDENING FRIENDS

**Kindly send us on back of order sheet the names and addresses of your neighbors or friends who plant a garden. Send us as many of these names as you wish. We will be mighty glad to mail all of them a Catalog free. Thank you.**

126 Maule's Midsummer Cabbage

# Maule's All Seasons Cabbage Collection

**We have selected the three varieties on this page to insure a full supply of Cabbage for the table throughout the season, as well as to have enough for Kraut making or winter storing.**

***3112* Collection. One Packet each of the three cabbages mentioned on this page for 25 cents, postpaid;**

***3116* Collection. One ounce each of the 3 named sorts for 75 cents, postpaid**

134 Maule's Prize Flat Dutch Cabbage

## ✱ *134* Maule's Prize Flat Dutch

**110 days. Well Known and Widely Grown**

**The Sauer Kraut Maker**

This cabbage is as widely grown as any other in the whole country. Continued care and critical selection have secured a perfectly true stock of seed. The heads of our Prize Flat Dutch are very large, heavy, solid, flat on top, and of a bluish green color. Our strain is a low growing variety with short stem and comparatively few outer leaves. The quality is fine and the flavor excellent, the heads being white when cut and the inside leaves crisp and tender. Our seed has always been American grown, coming from the celebrated Long Island districts, and whoever purchases Maule's Prize Flat Dutch may be assured of getting the best. It is everywhere a favorite market or kraut variety. It matures slightly earlier than Prize Drumhead, producing heads in about 110 days. Prize Flat Dutch is comparatively free from a disposition to burst, and is one of the most reliable winter keepers.

**Packet 10 cts.; ounce 30 cts.; ¼ pound 75 cts.; ½ pound $1.35; pound $2.50; 5 pounds $11.25, postpaid**

# Late Summer and Winter Cabbage

Ready to use or store in about 90 to 120 days

## ✻ *124* Danish Round Head Cabbage

**110 days. Heaviest Yielding Strain, Often Producing 22 Tons Per Acre. Excellent Basket Cabbage or for Making Slaws and Sauer Kraut**

In this strain we have very large, solid heads on short stems, produced in 110 days, having the same keeping quality as the original strain of Danish Ball Head, so widely known. It is 10 days to 2 weeks earlier and produces a larger yield than any of the so-called Danish cabbages. It is especially valuable for high, dry land, producing good sized heads where other strains would be too small. For shipping in the late fall or winter there is no finer cabbage than this strain. Danish Round Head is exceedingly hardy in resisting cold and stands dry weather well. Our stock comes direct from the originator in Denmark, and is so well bred that practically every plant will produce a good solid head.

**Packet 10 cts.; ounce 30 cts.; ¼ pound 85 cts.; ½ pound $1.50; pound $2.75; 5 pounds $12.50, postpaid**

124 Danish Round Head Cabbage

## *143* Mammoth Red Rock

**120 days. The Best, Largest Heading Red Cabbage**

The hardiest and largest heading red cabbage. Produces heads in 120 days, round, very solid and of a deep red color, often weighing 12 pounds each. Used principally for pickling. A sure cropper.

**Packet 10 cts.; ounce 35 cts.; ¼ pound 90 cts.; ½ pound $1.65; pound $3.00; 5 pounds $13.50, postpaid**

138 Volga or Stonehead Cabbage

## *127* Glory of Enkhousen

**90 days. Round, Solid Heads of Superior Merit**

This desirable cabbage, Glory of Enkhousen, originated in Holland; in season it is medium early, maturing its heads in 90 days, with heads frequently weighing 8 to 10 pounds each. The large sized, ball shaped heads are very firm and solid, leaves being fine ribbed and exceedingly tender. It is a dwarf and compact grower, allowing close planting; in fact some of its enthusiastic admirers claim it will yield more tons per acre than any other variety on account of close planting.

**Packet 10 cts.; ounce 30 cts.; ¼ pound 85 cts.; ½ pound $1.50; pound $2.75; 5 pounds $12.50, postpaid**

## ✻ *138* Volga or Stonehead

**100 days. A Splendid Drought Resister and a Good Keeper**

This grand cabbage is a great acquisition. In a field of several acres frequently not a single plant shows any variation from a true and valuable type, the large heads are of about equal size and shape, round as a ball, hard and solid, and stand a long time before bursting, producing heads in about 100 days. This sort is very desirable where large uniformly round heads with short stem and plants of compact growth are wanted.

**Packet 10 cts.; ounce 30 cts.; ¼ pound 85 cts.; ½ pound $1.50; pound $2.75; 5 pounds $12.50, postpaid**

# ✻ *131* Maule's Genuine Surehead

**110 days. All Head and Always Sure to Head. Excellent for Slaws or Sauer Kraut**

We watch with great care all the new cabbages, and test them at our trial grounds, but we still think that Maule's Surehead for main crop will do the most good for the most people. No other cabbage in America today has all the merits of Maule's Genuine Surehead.

People who have never sown Maule's Surehead do not know how good this cabbage is. The Surehead is the greatest and most profitable cabbage ever introduced, that has, for such a long term of years, maintained so wide a popularity. This is proven by the testimony of over 100,000 planters, in all sections of the country, representing all conditions of soil, elevation, climate and cultural treatment.

Maule's Surehead is a late variety with head as large as Maule's Prize Flat Dutch. Ready to cut in 110 days. The heads are firm and hard, elegant for kraut; the cabbage keeps well, is a splendid shipper, giving satisfaction everywhere, also an excellent home garden sort.

**Packet 10 cts.; ounce 35 cts.; ¼ pound 90 cts.; ½ pound $1.65; pound $3.00; 5 pounds $13.00, postpaid**

131 Maule's Genuine Surehead Cabbage

## *132* Succession

**100 days. Does Well in All Seasons; a Sure Cropper**

Nearly as early as Early Flat Dutch, but considerably larger in size and one of the largest and most desirable of the second early varieties. The heads are large, nearly round or somewhat flattened, extremely hard and solid, with finely ribbed leaves; the eating quality is not excelled by any other Cabbage. It is suited to all growing seasons, is a sure header under most adverse conditions, and keeps well even if planted very late. Remarkable for its ability to stand the hot sun and dry weather. Matures in 100 days.

**Packet 10 cts.; ounce 30 cts.; ¼ pound 85 cts.; ½ pound $1.50; pound $2.75; 5 pounds $12.50, postpaid**

# ✻ *125* Danish Ball Head Cabbage

**120 days. The Cabbage that is Swelling the Bank Account of Thousands of our Customers Every Year**
**Our Strain of this Seed is Simply Unsurpassed for Home Use, Market or for Making Sauer Kraut**

125 Danish Ball Head Cabbage

If you want the highest price per ton in car lots, you must plant Maule's Seed of this cabbage.

In describing our Danish Ball Head we can do no better than refer to the illustration, from a photograph sent us by our grower of this famous cabbage in Denmark.

The wide and unfailing popularity of Danish Ball Head cabbage is simply wonderful. It seems to adapt itself to all soils and conditions. The leading characteristics of Danish Ball Head cabbage are: First, that it is a sure header; second, that it is of unapproachable solidity and weight; third, that it is an extra good keeper; and fourth, that it is a good seller.

Danish Ball Head cabbage produces its crop in about 120 days. It is sure to head, the heads being round, hard and extremely heavy, though not extra large. It can be grown in close quarters, on account of its compact habit. As to its keeping qualities, it comes out of the pit in March or April as fresh as when put in, and with no waste. It is popular in the markets of all the large cities. Our seed of this popular cabbage comes to us direct from the best growers in Denmark.

**Packet 10 cts.; ounce 30 cts.; ¼ pound 85 cts.; ½ pound $1.50; pound $2.75; 5 pounds $12.50, postpaid**

## *140* Red Danish Round Head

**110 days. Round, Solid, Dark Red Heads**

This is the newest and most superior variety of red cabbage. It originated in Denmark and is considered one of the best strains introduced. The plants are strong and compact in growth, producing dark red, round, solid heads of medium size, equally as hard and handsome in appearance as our famous Danish Ball Head. The red color extends to the centre of each head, making it a valuable sort for the home garden, market or pickling. Its beautiful solid heads are ready for the table in 110 days. Originator's stock.

**Packet 10 cts.; ounce 35 cts.; ¼ pound 90 cts.; ½ pound $1.75; pound $3.25; 5 pounds $15.00, postpaid**

## ✻ *141* Improved Drumhead Savoy

**110 days. The Best Crumpled Leaf Cabbage**

The Savoy cabbages are noted for their fine and delicate flavor. The leaves are wrinkled or densely crumpled. Matures fine large heads in 110 days. A good winter keeper and one of the best for home or market.

**Packet 10 cts.; ounce 35 cts.; ¼ pound 90 cts.; ½ pound $1.65; pound $3.00; 5 pounds $13.50, postpaid**

141 Improved Drumhead Savoy Cabbage



135 The Houser Cabbage

## ✻ *135* The Houser

**130 days. The Latest Cabbage of Them All**

This excellent cabbage is in very wide favor, and thousands of our friends testify to its value. It is at least two weeks later than any strain of the Late Flat Dutch type. In solidity it is almost as hard as the renowned Danish Ball Head. It is very compact in habit of growth, the leaves closely surrounding and overlapping the head.

In size the Houser cabbage will average about 12 pounds at maturity, and the heads are uniformly handsome. The shape is round and deep, as indicated, and when a head cracks or bursts it is always at the stem end, which does not destroy its use for market.

In quality the Houser cabbage equals the best, being very free from the coarse ribs found in most late sorts. In fact, we would say that the Houser cabbage is very well bred. It is a strong, vigorous grower, with ability to withstand drought better than most varieties.

Its true merit is shown by the demand for it. It behaves well on the field and sells well in the market, and adapts itself to various conditions of soil and climate.

In respect to its keeping qualities in winter storage, we have only to say that it is perfect. Indeed, it is because the Houser is so extremely late, maturing in about 130 days, and is such an excellent keeper that it has attained such wide popularity.

**Packet 15 cts.; ounce 60 cts.; ¼ pound $1.75; ½ pound $3.25; pound $6.00; 5 pounds $27.50, postpaid**

# ✻ *123* Maule's Disease-Resistant Wisconsin Hollander Cabbage

**120 days. The "Yellows" or "Yellow Rot" Disease-Resistant Sort. Introduced by the University of Wisconsin**

This new strain of Hollander cabbage we recommend for locations where cabbage plants are affected by the "yellows," causing fields to be abandoned. The disease-resistant qualities of this cabbage enable growers to produce a crop of medium size round or somewhat flattened heads of remarkable solidity and excellent keeping quality. Matures in about 120 days. The plants show considerable variation of types, resemble Hollander, but longer and more leafy and spreading. Owing to a very short seed crop, our stock is limited.

**Packet 10 cts.; ounce 45 cts.; ¼ pound $1.25; ½ pound $2.35; pound $4.50; 5 pounds $20.00, postpaid**

**Customers may order 2 pounds or over at the 5 pound rate.**

123 Maule's Disease-Resistant Wisconsin Hollander Cabbage



133 Maule's Prize Drumhead Cabbage

## ✻ *133* Maule's Prize Drumhead

**120 days. Large, Solid Flat Heads on Short Stems. A Good Keeper**

Sureness in heading and regularity in growth have placed this variety high in the list, and we have no fear of using words of praise too high for its merits. It forms very large, hard, solid, flattened heads, uniform in shape and color, and of handsome appearance. It has a very short stem, and is a compact grower. Shortness of stem is so characteristic as to be associated with the very best strains of this cabbage, and the stock which we offer is thoroughbred in this and all other respects. This cabbage, like Prize Flat Dutch, has so long been an established standard that certain peculiarities have been bred into it, and have become so firmly fixed as to be necessary features of growth. It is as natural for this cabbage to form a head as to form leaves, and reports of 99 marketable heads from 100 plants are of frequent occurrence. Nobody will be disappointed in our strain of Short Stemmed Drumhead, for it far surpasses the old-fashioned strains of the same name, with heads of deeper and better shape maturing in 120 days. It is a standard sort for winter keeping or kraut making, and sells readily in the winter and spring markets.

**Packet 10 cts.; ounce 30 cts.; ¼ pound 75 cts.; ½ pound $1.35; pound $2.50; 5 pounds $11.25, postpaid**

## *136* Marblehead Mammoth

**120 days. The Longest Keeper. Best for Kraut**

A variety with dark green or bluish-green leaves that are attractive on the market. Heads are extra large, flat, rounded at top, firm and very solid. Good keeper. The absence of many large outer leaves permits more plants to the acre than most large late varieties, and this feature makes it nice for home gardens also. Eating quality is very good, the heads being fine grained, tender and deliciously flavored.

**Packet 5 cts.; ounce 30 cts.; ¼ pound 75 cts.; ½ pound $1.35; pound $2.50; 5 pounds $11.25, postpaid**

201 True Georgia Collards

## Collards

Of particular value in the South.

CULTURE.—Sow like cabbage. Set a foot apart in rows 2 to 3 feet apart. Can also sow seed in June, July and August. A packet will give about 300 plants, an ounce 2,500. Matures in about 45 days.

## *201* True Georgia

**45 days. Used Exclusively for Greens**

Forms a loose head of cabbage-like leaves, which are largely used for greens; ready for use in 45 days.

**Packet 5 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.00, postpaid**

## Chicory

CULTURE.—Sow in Spring, in drills 18 inches apart, one-half inch deep and thin plants to 4 inches. Use a packet to 20 feet of drill; an ounce to 200 feet; 4 pounds to an acre.

## *193* Large Rooted

**120 days. Substitute for Coffee**

Take up roots in the fall, cut in small pieces and let dry; when wanted for use it is roasted and ground like coffee.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 50 cts.; ½ pound 85 cts.; pound $1.50; 5 pounds $6.25, postpaid**

## ✻ *194* Witloof Chicory

**150 days. Known as French Endive**

The famous winter salad so popular in first-class restaurants. Forms leaves like Cos lettuce and can be eaten raw as salad or boiled.

**Packet 10 cts.; ounce 25 cts.; ¼ pound 65 cts.; ½ pound $1.15; pound $2.00; 5 pounds $8.75, postpaid**

194 Witloof Chicory

# Maule's Cauliflower

CULTURE—A gross feeder, and well repays heavy manuring and high culture. It succeeds best on well drained soil. Start plants in frame or seed bed, and transplant. Seed for early cauliflower may be started in Autumn in a cold frame, or in early Spring in a hot bed. For main crop, Summer and Autumn, the seed should be sown in May or June. A packet will produce about 150 plants, an ounce about 3000 plants; ¼ pound for an acre. Set the plants 2 to 3 feet apart each way. Ready for use in 90 to 130 days.

## ✻ *164* Maule's Prize Earliest Cauliflower

**90 days. The Earliest, Largest and Surest White Header Grown**

Heads the list as the earliest, finest and handsomest cauliflower. Whether for forcing under glass or growing in the open ground, and whether planted early or late, it is the surest header of all, maturing its heads in about 90 days. It is very dwarf and compact in habit of growth, like the Snowball, and can be planted as close as 18 inches each way for forcing or where space is limited. Maule's Prize Earliest is particularly desirable for forcing under glass, while in our open air trials every plant has produced a head, excelling all other varieties in earliness, size and quality; undoubtedly the finest and most popular early cauliflower grown, either for the home garden or market.

**Packet 25 cts.; ¼ ounce 90 cts.; ounce $3.00; ¼ pound $8.00; ½ pound $15.50; pound $30.00, postpaid**

164 Maule's Prize Earliest Cauliflower

## *166* Maule's Always Heads

**100 days. The Popular and Perfect Header**

The name well illustrates the strongest characteristic of this Cauliflower, that in season and out of season it can always be depended upon to make a head. Produces solid pure white heads in 100 days. It is an absolutely unsurpassed strain. Excellent home garden or market sort.

**Packet 10 cts.; ¼ ounce 75 cts.; ounce $2.75; ¼ lb. $7.50; ½ lb. $14.50; lb. $28.00, postpaid**



165 Dry Weather Cauliflower

## ✻ *165* Dry Weather Cauliflower

**105 days. Reaches Perfection When Ordinary Sorts Fail**

This desirable strain originated in Denmark, but has been fully tested in America with the most favorable results. It produces a large, solid, pure white head, maturing in about 105 days, a little later than Maule's Prize Earliest. It is in all respects a first-class Cauliflower, but is especially and peculiarly adapted to dry situations and to resisting the effects of drought. It will also do well in moist or wet seasons, making heads equal to any. Excellent home or market sort.

**Packet 20 cts.; ¼ ounce 75 cts.; ounce $2.75; ¼ pound $7.50; ½ pound $14.50; pound $28.00, postpaid**

## ✻ *168* Early Snowball

**95 days. Large Solid White Heads. A Sure Cropper**

This standard variety is known everywhere, either in the home garden or with the market gardeners. Produces large solid white heads when conditions are ordinarily favorable in about 95 days. Averages about 9 inches and often attains a size of 12 inches in diameter.

Being one of the earliest strains of cauliflower it becomes one of the most popular sorts, either for forcing under glass during winter and spring, or for planting in the open ground. The plants are of compact habit, which enables close planting.

**Packet 15 cts.; ¼ ounce 75 cts.; ounce $2.75; ¼ pound $7.50; ½ pound $14.00; pound $27.50, postpaid**

168 Early Snowball Cauliflower

**Lend this Catalog to your neighbor**

## *173* Autumn Giant

**130 days. An Extra Fine Late Sort**

This is a late variety, maturing its heads in 130 days. The heads are large, very white and of the best quality. The heads are protected by the foliage and remain fit for use a long time.

**Packet 10 cts.; ¼ ounce 20 cts.; ounce 60 cts.; ¼ pound $1.75; ½ pound $3.25; pound $6.00, postpaid**

## *172* Early Favorite

**115 days. Sure Heading, Second Early Sort**

Will stand heat and drought exceptionally well, which is a great point in its favor and makes it most highly desirable in regions where other varieties have failed. Producing large white heads in 115 days.

**Packet 10 cts.; ¼ ounce 35 cts.; ounce $1.00; ¼ pound $2.75; ½ pound $5.25; pound $10.00, postpaid**



172 Early Favorite Cauliflower

**Never allow your Cauliflower plants to become dry. Keep plants well watered during a dry spell**

# Garden Carrots

CULTURE.—Sow in drills in early spring until July. Cover ½ to 1 inch deep, and press soil about seed; afterward thin plants to 2 to 6 inches. Make rows 12 to 30 inches apart. Use a packet to 60 feet of drill, an ounce to 400 feet, 2 to 3 pounds to the acre. Ready to use in 45 to 75 days.

152 Maule's Danvers Half Long

## ✻ *152* Maule's Danvers Half Long

**70 days. The Popular Carrot for the Home Garden or Market**

This variety is well adapted to all soils and sections, and some years it leads our whole list as the best seller. It is half long in shape, almost cylindrical, somewhat stump rooted, and of rich, dark orange color. We claim that it will yield greater bulk and weight for a given length of root than any other carrot now grown. Over 40 tons per acre of Maule's Danvers have been grown, and a yield of 25 to 30 tons per acre is not uncommon. Matures its crop of beautiful shaped roots in 70 days. Grown extensively by market gardeners for bunching and makes a handsome appearance on the market stalls; of the finest quality and one of the most popular sorts for home use.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 85 cts.; 5 pounds $3.75, postpaid**

## *153* Maule's Improved Long Orange

**75 days. The Heaviest Cropper and the Best Winter Keeper**

Maule's Improved Long Orange is the strongest and purest strain of that well known carrot on the market. The roots are of large size, and are smooth, fine grained and in all respects superior. This beautiful carrot is always well formed. The color is deep orange, as indicated by the name. Enormous crops can be grown under good culture, being fit to pull in 75 days. The heaviest yielding table carrot and one of the most profitable to grow for stock feeding. An excellent long dark orange color carrot for bunching.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 25 cts.; ½ pound 45 cts.; pound 80 cts.; 5 pounds $3.50, postpaid**

## *150* Rubicon Half Long Stump Rooted

**65 days. An Ideal Carrot for the Home Garden**

This excellent stump rooted carrot is broad shouldered, of cylindrical form, about 5 to 6 inches in length by 3 inches in diameter. The roots are uniformly thick at the shoulder. Color deep rich orange-red, skin smooth. The flesh is fine grained, sweet, crisp, tender and free from core. Ready for the table or market in 65 days. A ready seller on the market stall, also a desirable home garden sort.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 40 cts.; ½ pound 65 cts.; pound $1.15; 5 pounds $5.00, postpaid**

## *144* Extra Early Parisian Forcing

**45 days. The Earliest or First of All Carrot**

This carrot is one of such quick growth that we think a good name for it is the radish carrot. Matures quickly; in about 45 days. It has a very fine neck and a rather hollow crown. Good for forcing under glass or outdoor planting.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 85 cts.; 5 pounds $3.75, postpaid**

148 Early Scarlet Horn

## *146* Oxheart or Guerande

**65 days. A Great Producer, a Good Keeper**

This carrot is a splendid second early sort. In length it comes between Early Scarlet Horn and Half Long Scarlet. It runs fully 3 to 4 inches in diameter, and specimens have been raised measuring over 7 inches in diameter, being ready to pull in 65 days. In quality it is extra good. This carrot will prove satisfactory for the market gardener or for home use.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 85 cts.; 5 pounds $3.75, postpaid**

## ✻ *148* Early Scarlet Horn

**55 days. The Gardener's Favorite Carrot**

A variety of carrot long and favorably known to all growers. It is not large, but is often used for early crop. It is sometimes used for forcing. The flesh is fine grained and the color a deep orange. It has small tops, and grows well in shallow soil. It matures in about 55 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 85 cts.; 5 pounds $3.75, postpaid**

## *163* Mixed Table Carrots

**45 to 75 days. One Sowing to Produce Carrots All Season**

A most desirable mixture for planting in the home garden where a few carrots are wanted for the table. One planting is all that is necessary, producing tender carrots in 45 to 75 days, giving a supply of carrots all season.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00, postpaid**

**Order All Seeds and Collections**
**by Number or Name; if by Number only, be sure to give Correct Number**

153 Maule's Long Orange

146 Oxheart or Guerande

## ✻ *145* Maule's Golden Rod Carrot

**68 days. The Handsomest and Best Carrot for Both Home and Market**

This handsome carrot is a half long, stump-rooted sort, somewhat deeper in color than Danvers and a heavier cropper. The root is smooth, uniform and handsome, entirely free from core, with sweet and tender flesh. It never becomes stringy nor shows rings, producing its crop of desirable size and shape carrots in about 68 days. Highly recommended both for table use and stock feeding and especially desirable for market gardeners and amateurs who wish to grow something choice in quality. With ordinary good treatment Golden Rod will yield close to 40 tons to the acre.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.50, postpaid**



151 Chantenay or Model

## ✻ *149* Nantes Half Long Stump Rooted

**65 days. One of the Best Table Carrots; Tender and Delicious**

The medium-sized roots are a beautiful, bright orange color, perfectly cylindrical in form. The flesh is orange and tender all the way through. It is very early, ready to pull in 65 days. Very popular as a bunch carrot; has small tops.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 85 cts.; 5 pounds $3.75, postpaid**

## ✻ *151* Chantenay or Model

**60 days. Unexcelled in Quality and Productiveness**

This variety is a very productive one. It has an extra large shoulder, is easily dug, and is desirable in all respects. It is a stump-rooted sort, very smooth, fine in texture and of a beautiful, rich, orange color. For table use it is considered by many to be the best of all; matures its beautiful shaped roots in 60 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 85 cts.; 5 pounds $3.75, postpaid**

149 Nantes Half Long

# Carrots for Stock Feeding

Carrots will pay you well if sown for a feeding crop for cows, horses or sheep.

CULTURE.—Sow any time before July 1, half an inch below the surface, in rows 24 to 30 inches apart. Thin to 6 inches in the row. Sow a packet to 60 feet of drill, an ounce to 400 feet, two pounds to the acre. Ready to use in 80 to 90 days.

## ✻ *156* Long Lemon Stump-Rooted

**80 days. Also Known as Lobberichs Agricultural**

Considered the best yellow carrot ever offered to American farmers. It is of a rich yellow color, stump-rooted, and grows to a very large size. Matures in about 80 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 85 cts.; 5 pounds $3.75, postpaid**

## ✻ *158* Improved Short White

**85 days. A Heavy Cropper, Easy to Harvest**

One of the very best. Roots are half long, 7 to 9 inches in length, smooth, very heavy at the shoulder but tapering regularly to the point, maturing its crop of roots in about 85 days. The color is creamy white with light green crown. The flesh is white, solid, crisp and of excellent quality for stock feeding.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 20 cts.; ½ pound 35 cts.; pound 65 cts.; 5 pounds $3.00, postpaid**

## ✻ *162* Large Yellow Belgian

**90 days. Enormous Yielder**

This is the giant among carrots and produces an immense quality of roots in 90 days. The skin is of a pale orange color. The flesh is light orange. The roots are produced entirely under ground. Many farmers prefer the orange fleshed carrots to those with white flesh and they are said to be most nutritious. A very productive variety, doing best on deep and fertile soil.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 20 cts.; ½ pound 35 cts.; pound 65 cts.; 5 pounds $3.00, postpaid**



158 Short White

## *157* Mastodon

**85 days. Highly Relished by Stock**

This carrot is extremely heavy at the shoulder, producing a short, heavy root, suited for shallow soil, and is fit to pull in 85 days; an enormous cropper. The crown is light green in color, but below ground the root is pure white, both skin and flesh. Root smooth, flesh rich and solid; best for stock feeding.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 20 cts.; ½ pound 35 cts.; pound 65 cts.; 5 pounds $3.00, postpaid**

## *161* Large White Belgian

**90 days. A Great Producer**

Our strain of this variety forms its roots entirely under ground. The roots will average 2 inches in diameter at the shoulder and a foot or more in length. The diameter is almost even throughout the entire length, the roots tapering gradually toward the base. Flesh and skin pure white, tinged with green on the upper portion, near the shoulder of the root. It does best in rich, deep soils.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 20 cts.; ½ pound 35 cts.; pound 65 cts.; 5 pounds $3.00, postpaid**



162 Large Yellow Belgian Carrot



156 Long Lemon

**Sow seed of Carrots, for winter storing, in June. Carrots from earlier sowings are too old for winter use**

# MAULE'S CELERY

CULTURE—Celery seed is slow to germinate, and ample time must be given. Sow thinly in early spring and cover lightly. Keep constantly moist. Count on about 400 plants to a packet of seed, about 7,500 plants per ounce or quarter pound per acre. When the seedling plants are 3 inches high they should be clipped at the top, to favor stocky growth, or else transplanted. Celery is mostly grown under flat culture, without trenches, in rows 4 feet apart, 6 inches apart in row. For home use celery is often grown in double rows, 10 inches apart, and plants 6 inches apart in each row, allowing 4 feet of space before setting out another double row. This will permit soil for banking for winter storage without lifting. Ready for use in 100 to 140 days.

## ✱ *176* Golden Plume or Wonderful Celery

**105 days. Blight Resistant and Free from Strings or Hollow Stalks**

A new type of the famous Golden Self-Blanching Celery. The plants are semi-dwarf with thicker stalks, very full heart and wider leaves, bleaches to a beautiful golden yellow color, ready for the table or market in 105 days. Its attractive appearance, superior quality, fine nutty flavor and resistance to attacks of blight and rust make it a very profitable variety for the market gardener or long distant shipper as well as the home garden.

**Packet 20 cts.; ½ ounce $1.10; ounce $2.00; ¼ pound $5.50; ½ pound $10.50; pound $20.00, postpaid**

## ✱ *189* Maule's American Yellow

**110 days. The Favorite Self-Blanching Sort for Home and Market**

Maule's American Yellow Celery is an early, self-blanching sort very similar in many ways to XX French grown Golden Self-Blanching, except that it grows a larger stalk, with the additional advantage that it fills a standard celery crate more evenly, maturing its beautiful golden yellow stalk in 110 days.

**Packet 10 cts.; ½ ounce 35 cts.; ounce 60 cts.; ¼ pound $1.65; ½ pound $3.25; pound $6.00; 5 pounds $27.50, postpaid**

## ✱ *181* Perfected White Plume

**100 days. The Earliest Celery in Cultivation**

This magnificent celery is a truly beautiful type. Not only does the stem whiten, but the leaf itself, especially every inner leaf, assumes the attractive white color. This makes the White Plume celery one of the most showy ornaments that can be put upon the Thanksgiving or Christmas dinner table. As to succulence, crispness and quality, the Perfected White Plume is all that can be desired. Fit to eat in 100 days. It is easily and quickly blanched.

**Packet 10 cts.; ½ ounce 20 cts.; ounce 30 cts.; ¼ pound 85 cts.; ½ pound $1.50; pound $2.75; 5 pounds $11.25, postpaid**

## *177* Emperor

**135 days. The Largest Hearted and Best Nut Flavored Celery**

A well known true dwarf type with very large heart, solid and finest nut flavored. It is a true dwarf sort and, therefore, much easier to blanch than the taller growing varieties. Ready for the market or table in 135 days. The plants grow 15 to 18 inches in height. The stalks are smooth and very thick, the heart tinged with yellow, crisp and of decidedly nutty flavor. An excellent late keeping sort for the home garden or for market. It is worthy of a place in every garden.

**Packet 10 cts.; ½ ounce 35 cts.; ounce 60 cts.; ¼ pound $1.65; ½ pound $3.25; pound $6.00; 5 pounds $27.50, postpaid**

## *180* Columbia

**115 days. Valuable for Fall or Early Winter Use**

This is a valuable celery to follow Golden Self-Blanching. Stored at the same time, it will be ready just as soon as the Golden Self-Blanching is gone. The stalks are broad and thick, almost round, solid and of the highest quality, and very attractive in appearance. The foliage is of a distinct light shade of green with a tinge of yellow. The plant is of medium height which matures in 115 days, blanches easily and is a good winter keeper for home or market.

**Packet 5 cts.; ½ ounce 20 cts.; ounce 30 cts.; ¼ pound 75 cts.; ½ pound $1.35; pound $2.50; 5 pounds $11.25, postpaid**

189 Maule's American Yellow Celery

## *182* Giant Pascal or Winter King

**140 days. The Largest Ribbed Celery**

This celery has the sweet, nutty flavor of Golden Self-Blanching, of which it is an offspring. The stalks are about two feet high; thick, solid and stringless, and as brittle as glass. Matures in 140 days. It is an elegant winter keeper for home or market.

**Packet 10 cts.; ½ ounce 20 cts.; ounce 30 cts.; ¼ pound 85 cts.; ½ pound $1.50; pound $2.75; 5 pounds $12.50, postpaid**

## *185* Winter Queen

**140 days. Best Winter Sort. A Money Maker**

Probably the most desirable winter keeping celery. It is short, stout, thick and heavy, with double the amount of heart of any other celery, a habit of growth which gives it truly remarkable value. The flavor is sweet, nutty and delicious, leaving nothing to be desired. It bunches up handsomely. The leaves are light green, and blanch to a cream white. Matures its crop in 140 days. It is a money maker for the market gardener.

**Packet 10 cts.; ½ ounce 20 cts.; ounce 30 cts.; ¼ pound 70 cts.; ½ pound $1.25; pound $2.25; 5 pounds $10.50, postpaid**

## *188* Celeriac

**120 days. Or Turnip-Rooted Celery**

Culture is the same as celery; as the roots are the edible portion, it requires no hilling. The large roots are smooth, without any side roots, globular in shape. Flesh is pure white, tender and of excellent flavor and quality. Celeriac deserves to be grown much more than it is, as the roots are used for flavoring soups and salads, or are boiled like turnips, having the pleasant celery taste. Fit for the table in 120 days.

**Packet 10 cts.; ½ ounce 20 cts.; ounce 30 cts.; ¼ pound 70 cts.; ½ pound $1.25; pound $2.25; 5 pounds $10.00, postpaid**

176 Golden Plume or Wonderful Celery

181 White Plume Celery

## ✱ *175* Maule's Golden Self-Blanching

**110 days. XX Selected French Grown Original Dwarf Strain**

Our XX Selected French Grown Golden Self-Blanching celery is absolutely the best strain of this variety that we know. It is as true to type as any variety on the market. In quality it ranks with the highest. It is the favorite sort with both the market gardener and the amateur.

It is dwarf to half dwarf, growing 18 to 20 inches in height, wonderfully stocky, very heavy, perfectly solid, of delicate flavor and a very good keeper, ready for the table or market in 110 days. Added to these points is its great distinctive feature of being literally self-blanching.

All the largest and most experienced celery growers plant Maule's Golden Self-Blanching XX Selected French Grown seed. The top notch prices which they receive from their commission merchant produces an enormous profit annually.

Maule's Golden Self-Blanching XX Selected French Grown produces a bumper crop of excellent celery which stands shipping better than most other sorts, and brings the highest market prices. In the home garden the golden yellow stalks, which are crisp, and nutty in flavor, keep in good condition until Christmas or New Year.

We have had this seed grown for us in France by the same grower for a number of years, so we know our stock is right.

**Packet 15 cts.; ½ ounce 55 cts.; ounce $1.00; ¼ pound $3.00; ½ pound $5.75; pound $11.00; 5 pounds $50.00, postpaid**

## ✱ *186* Easy Blanching

**115 days. Easiest and Quickest to Blanch; Long Keeping**

The heavy stalks are stocky in growth and of medium height and are the easiest and quickest to blanch and keep better in the trench than other sorts. The tender, brittle, sweet, nutty flavored stalks are attractive in appearance. Ready for the table or market in about 115 days.

**Packet 10 cts.; ½ ounce 40 cts.; ounce 75 cts.; ¼ pound $2.00; ½ pound $3.85; pound $7.50; 5 pounds $35.00, postpaid**

175 Maule's Golden Self-Blanching Celery

## Corn Salad

CULTURE.—Sow thinly in drills half an inch deep in the early Spring and thin to two inches in the row. Matures in about 42 days. For winter or early spring use sow in drills in August or September.

### *203* Large Round-Leaved

**42 days. Lamb's Lettuce**

Well known garden sort.

**Pkt. 10 cts.; oz. 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

203 Corn Salad

## Cress, or Peppergrass

CULTURE—Can be sown in the early spring, out-doors in rows 1 foot apart, covering seed about one-quarter inch and sow thickly. A packet will sow about 40 feet of drill, an ounce about 200 feet. Ready to use in 20 to 40 days.

### *238* Extra Curled 20 days. For Garnishing

The leaves while young have a warm, pungent taste; used as a salad with lettuce. The most popular variety for market; of excellent flavor.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 80 cts.; 5 pounds $3.50, postpaid**

### *242* Water Cress 40 days. Esteemed for Salads

Grows luxuriantly in shallow water or in cool, moist soil. Highly prized and popular as a salad.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 45 cts.; ¼ pound $1.25; ½ pound $2.35; pound $4.50, postpaid**



284 Green Curled Endive

## Dandelion

A hardy perennial. Sow in early spring, in drills half an inch deep, and thin to 2 or 4 inches in the row. Will be ready to cut in about 55 days. A packet will sow about 25 feet of drill, an ounce about 300 feet.

### ✱ *275* Large Leaved 55 days. Leaves Thicker and Double in Size

Very early; produces large leaves which make wholesome greens.

**Packet 10 cts.; ½ ounce 40 cts.; ounce 75 cts.; ¼ pound $2.00; ½ pound $3.85; pound $7.50, postpaid**

## Endive

CULTURE.—Sow in the open ground in April, or for main crop in June or July, about one inch deep. In autumn the endive is blanched by tying the leaves together, or laying a board upon the plant. Use a packet to 25 feet of drill; an ounce to 150 feet; 4 to 5 pounds per acre. Ready to use in 35 to 45 days.

### ✱ *284* Green Curled 40 days. Moss Curled or Giant Fringed Oyster

Beautiful dark green curly leaves are finely cut or laciniated, giving the plant a feathery effect. Rich green in color, but blanching to creamy white. Chiefly grown for summer and fall use.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 50 cts.; ½ pound 85 cts.; pound $1.50; 5 pounds $6.25, postpaid**

### *285* Ever White Curled 35 days. Self-blanching

A beautiful variety, with leaves as finely curled or mossed as the preceding, but of an attractive light green color. Blanches easily and has a most delicious crisp flavor.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 50 cts.; ½ pound 85 cts.; pound $1.50; 5 pounds $6.25, postpaid**

### *287* Broad Leaved Batavian 45 days. Also Known as Escarolle

The leaves are large and broad. Well-rounded heads often measuring 16 inches across. It can be blanched, but is more generally used cooked like spinach or as flavoring for soups, stews, etc.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 50 cts.; ½ pound 85 cts.; pound $1.50; 5 pounds $6.25, postpaid**

**Blanch early celery with boards, paper or tiles; from 10 to 20 days will be required for blanching**

# MAULE'S SWEET or SUGAR CORN

CULTURE—Plant when danger of frost is over, in drills 2x3 feet or 3x4 feet apart, about an inch deep and the seed 8 inches apart in the rows, or 4 seeds may be dropped in hills 3 to 4 feet each way, allowing 2 or 3 plants to remain in a hill. Make successional plantings until July 10th to insure plenty of corn during the summer, and to have enough to dry or can for winter use. A packet will plant about 100 feet of drill, half pound for 200 hills; 12½ pounds per acre. Ready to eat in 50 to 90 days.

## Extra Early and Second Early Varieties

### Ready to Use in 50 to 70 Days



### * 214 Maule's First of All Sweet Corn

**55 days. Extra Early, Large Eared Sort for Early Market or the Home Garden**

Matures in about 55 days, and we can confidently recommend it. It produces larger ears and more to the stalk than any other corn listed, and will prove a boon to gardeners who desire to be first in the market. It is one of the earliest sugar corns for the home garden, and in the market brings double the price that other corns command later.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.65, postpaid**
**Not prepaid, 5 lbs. or over at 23 cts. per lb.; 100 lbs. $20.00**

### * 217 Burpee's Sunnybrook Sweet Corn

**60 days. A Luscious Sweet Buttery, Golden Yellow Corn Resembling Golden Bantam**

Burpee's Sunnybrook Sweet Corn originated from the same plant as Burpee's Delicious and consequently it resembles it in many ways. However, the ears are a trifle smaller and the kernels are even broader, and it matures a few days earlier. The ears of Burpee's Sunnybrook are of attractive appearance and of handy size for corn on the cob. The kernels are a bright golden yellow. They are broad and deep, and therefore extremely meaty. The rows and kernels are set closely together around a small cob. Of a luscious sweet and buttery flavor, greatly resembling that of Golden Bantam. The thick and tightly folded husk is an important feature with the variety because the corn ear worm seems to find it difficult to work its way into the ears.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 22 cts. per lb.; 100 lbs. $19.00**

### Maule's Collection of "The Big 4" Leading Early Sweet Corns

Ready to Use in 62 to 90 Days

*211* **Golden Giant .....62 days**
*212* **Maule's XX .....65 days**
*216* **Country Gentleman .....70 days**
*225* **Maule's Improved Giant .....90 days**

*3145* **Collection. One packet each of the four sweet corns listed above for only 35 cts., postpaid**
*3147* **Collection. Half pound of each (4—½ lbs. in all), for 90 cts., postpaid**
*3149* **Collection. One pound of each (4 lbs. in all), for $1.50, postpaid**
*3147* **Collection. Half pound of each (4—½ lbs. in all), for 60 cts., not prepaid**
*3149* **Collection. One pound of each (4 lbs. in all), for $1.10, not prepaid**



### * 212 Maule's XX SWEET CORN

**65 days. Famous for its Delicious, Sweet, Sugary Flavor. Excellent Home Garden or Market Sort**

All who plant Maule's XX want it again and again. It has won a national name and fame. It is fit for the table in 65 days from planting, and of most delicious, sweet and sugary flavor. It remains long in edible condition. The stalk grows 5 to 6 feet in height. It produces 12 rowed to 16 rowed ears as large as Stowell's Evergreen (9 to 10 inches). It grows well in midsummer, and may be sown as late as July 5 to 15. In flavor it has no superior, and in productiveness it is simply remarkable. The market gardeners' favorite also the home gardeners' pride.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**

# ✱ 205 Maule's Colossal Early Sugar Corn

**70 days. For the Home Garden or Market**



205 Maule's Colossal Early Sugar Corn

## The Finest Large Eared Sugar Corn in Existence

The first real rival of the Shoe Peg or Country Gentleman, as large as Stowell's Evergreen, and of delicious flavor.

**Frequently matures fine large ears ten weeks from planting**

Maule's Colossal has four principal points that especially recommend it:

**First**—Earliness. It has matured a crop in 60 to 65 days under extraordinary circumstances, but can generally be depended upon to produce ears of marketable size within 70 days.

**Second**—Flavor. It is the most delicious sugary corn you have ever eaten.

**Third**—Size. It is undoubtedly the largest eared early sugar corn in existence, as the ears average from 7 to 9 inches in length, and frequently 2½ to 3 inches in diameter, with 12 to 14 rows of large sweet kernels that fairly melt in your mouth.

Two or three ears are generally found on every stalk; it grows from 6 to 7 feet tall, which furnishes a most desirable fodder.

**Fourth**—A Money Maker. Every market gardener should grow Maule's Colossal Early sugar corn. It will prove profitable, as it is a money maker.

This is also a desirable variety for the home garden, as the quality of this corn is extra fine, being tender, sweet and delicious.

**Packet 15 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 28 cts. per lb.; 100 lbs. $25.00**

## ✱ 213 Barden's Wonder Bantam Sweet Corn

**60 days. Ears Larger Than Golden Bantam. Just as Early and Sweet**

A new yellow grain variety of the same type, season and quality as Golden Bantam. Going one better by having larger ears produced higher up on the stalks. The stalks grow from 5 to 6 feet in height and have ears 8 to 10 inches in length filled with 8 rows of rich golden yellow kernels. It is a variety that will appeal to the critical market or home gardener as well as the canner who has been looking for a Bantam Corn that will produce more tonnage per acre and yet have the sugar sweet Bantam quality. All growers of corn should give Barden's Wonder Bantam a trial this season.

**Packet 15 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 28 cts. per lb.; 100 lbs. $25.00**



213 Barden's Wonder Bantam

## 208 Kendel's Early Giant

**60 days. Extra Early, with Ears of Remarkable Size**

The ears measure 8 to 10 inches long and have 10 to 14 rows of grains. The kernels are pure white, and are very sweet, tender and palatable. Kendel's Early Giant is a prolific variety, and matures its large ears in about 60 days. Valuable for the home garden or market.

**Packet 10 cts.; ½ pound 25 cts.; pound 35 cts.; 5 pounds $1.35, postpaid**
**Not prepaid, 5 lbs. or over at 18 cts. per lb.; 100 lbs. $16.00**

## 209 Extra Early Dighton

**50 days. Extremely Early, with Large Ears**

An extra early sweet corn. Stalks 4 feet high; ears, usually two to a stalk, 6 to 7 inches long, 8 to 10 rowed; grain white, cob pink. Very good quality for so early a corn. A valuable acquisition in Northern states where the season is short. Matures in 50 days.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.65, postpaid**
**Not prepaid, 5 lbs. or over at 23 cts. per lb.; 100 lbs. $20.00**

## 219 Howling Mob

**65 days. Early with Large Thick Ears. A Basket Filler**

A large eared early sweet corn, ready for use in about sixty-five days, generally producing two good large size ears to a stalk, averaging 7 to 9 inches long, with 12 to 14 rows of pearly-white grains. Stalks, 5 feet.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.60, postpaid**
**Not prepaid, 5 lbs. or over at 20 cts. per lb.; 100 lbs. $18.00**

## 226 Mammoth White Cory

**65 days. The Favorite Large Eared Early Sort**

Stalks grow four feet high, each generally bearing two large, finely shaped ears, fit for use in about 65 days. Ears are twelve rowed, 6 to 7 inches long, very symmetrical and handsome.

**Packet 10 cts.; ½ pound 25 cts.; pound 35 cts.; 5 pounds $1.35, postpaid**
**Not prepaid, 5 lbs. or over at 18 cts. per lb.; 100 lbs. $16.00**

## ✱ 206 Maule's Ideal Early Corn

**55 days. Do you want delicious corn on your table the 4th of July? If so, plant this extremely hardy, early maturing, large eared sort**

We have produced in this early corn a variety which stands alone as a money maker. It is in the same class as the Earliest of All sugar corns, considerably larger, and, best of all, contains a sweetness equal to most true sugar varieties.

It has the power of germination under conditions where all others have failed, and can safely be planted much earlier than any true sugar corn on account of its extreme hardiness. It adapts itself to any kind of soil, either sand or heavy clay.

It is as large as Stowell's Evergreen. The fodder grows 6 feet high; no small item to a gardener; and as a proof of its quality and sweetness, we have a continuous call for "Ideal" from our customers year after year. In earliness, any one growing this pearly white corn will have the crop marketed and the money in his pocket before any of the early sugar corns are ready. Matures in 55 days. No gardener should fail to plant Maule's Ideal Early.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $20.00**



206 Maule's Ideal Early Corn

## ✱ 207 Golden Bantam

**60 days. The Earliest and Sweetest Yellow Grained Variety**

This is a very early sweet corn, deep yellow in color. The delicious yellow kernels are so tender that they do not need scoring or cutting across the grain; the flavor is also distinct, being almost as sweet as honey. Can be planted thickly, each and every stalk has from 2 to 3 perfect ears about 6 inches long. Matures in 60 days. Most popular sort for the home garden.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 20 cts. per lb.; 100 lbs. $17.00**

## ✱ 210 Burpee's Delicious

**63 days. Named Delicious on Account of Its Sweet Sugary Flavor**

Burpee's Delicious is so named because the most outstanding characteristic is its delicious flavor. Being a chance sport from the famous Golden Bantam, it has inherited the delicious buttery taste which heretofore was not present in any other variety.

Burpee's Delicious makes a strong and vigorous growth, 5 to 7 feet tall, and each stalk carries two fine ears measuring close to 8 inches. The kernels are broad and deep. They are pearly white, with fine thin skin enclosing the rich delicious pulp.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 22 cts. per lb.; 100 lbs. $19.00**

## ✱ 211 Golden Giant

**62 days. Extremely Early and Sweet Large Eared Yellow Grain Sort**

Golden Giant is a cross between Golden Bantam and Howling Mob, combining the distinct buttery flavor of its most delicious yellow parent with the size of its white parent, making it the sweetest, most tender and juicy of all sweet corns. The stalks grow 4½ to 6 feet high, producing in 62 days two to three good ears 7 to 9 inches long with 12 to 16 rows of long, deep kernels of deep orange color. The husk is very heavy, affording the end protection from worm and bird. It is an excellent yellow grained corn for the home or market garden.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.60, postpaid**
**Not prepaid, 5 lbs. or over at 20 cts. per lb.; 100 lbs. $18.00**



207 Golden Bantam

## 215 Maule's Nonesuch

**70 days. Always Sweet, Best Large Eared Sort**

It almost always yields two perfect ears to the stalk, the ears being 9 to 12 inches long, compactly filled with grains from end to end. Kernels large, tender and deliciously sweet. Ears are 12-rowed, and the tips are always filled out. Stalks about 6 feet high. Matures in 70 days.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.60, postpaid**
**Not prepaid, 5 lbs. or over at 20 cts. per lb.; 100 lbs. $18.00**

## 218 Black Mexican

**70 days. Considered the Sweetest of All**

Grains when first perfected are pure white, and are then at their best for table use. Very tender and sweet; bluish black when ripe, but when cooked grains are white with a bluish tinge. Fit to eat in 70 days. One of the best for home use.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 22 cts. per lb.; 100 lbs. $19.00**

## 220 Early Evergreen

**70 days. Ten Days Earlier than Stowell's**

This variety resembles Stowell's Evergreen, maturing its crop in 70 days. Producing very large ears with deep, narrow grains, which are tender and sweet; very desirable sort for the home garden, and is grown extensively for market.

**Packet 10 cts.; ½ pound 25 cts.; pound 35 cts.; 5 pounds $1.35, postpaid**
**Not prepaid, 5 lbs. or over at 18 cts. per lb.; 100 lbs. $16.00**

## 224 Premo

**60 days. A Good Early Sweet Corn**

Produces ears right after First of All, reaching maturity in about 60 days. It combines all the merits of the leading early varieties, and is superior to many of them in size, quality and yield. Stalks grow 5 feet high.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 20 cts. per lb.; 100 lbs. $17.00**

# Main Crop and Late Varieties

**Ready for Use in 70 to 90 Days**



## ✻ *225* Maule's Improved Giant Sweet Corn

**90 days. The Best and Largest Eared Sweet Corn for the Home Garden or Market**

Maule's Improved Giant is the largest and best sweet corn grown, and any one desiring sugar corn, producing ears of immense size, which are at the same time of delicious flavor, will do well by planting Maule's Improved Giant. Matures in 90 days. The stalks are comparatively short, and so thick and strong they stand up well against storms and rains. The ears are frequently 12 inches or more in length, well formed and exceedingly handsome. In sweetness, succulence, depth of grain and fine table quality Maule's Improved Giant will be found hard to beat. We recommend it to private or market gardeners as well as canners.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 23 cts. per lb.; 100 lbs. $20.00**

## ✻ *216* Country Gentleman or Improved Shoe Peg Sweet Corn

**70 days. The Best Known and Most Largely Planted Sweet Corn**

The ears are quite large, and frequently three are on a stalk. The grains are irregularly set on the cob, which is remarkably small, giving great depth to the compressed grains. The ears average eight to nine inches in length. Ready for the table or market in 70 days. For delicious flavor and sweetness none surpass this popular variety. Excellent home garden or canning sort.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 20 cts. per lb.; 100 lbs. $17.00**



## ✻ *221* Stowell's Evergreen Sweet Corn

**80 days. The Standard Main Crop, Long Eared, Late Sort**

Stowell's Evergreen produces a strong and vigorous stalk, seven to eight feet high; ears eight inches long with 16 or more rows of the finest sugary grains. This variety has gained and maintained a reputation with the home gardener or market grower for productiveness, fine rich flavor, sweetness and deep set tender white grains.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.60, postpaid**
**Not prepaid, 5 lbs. or over at 20 cts. per lb.; 100 lbs. $17.00**

## ✱ 222 Maule's Lead All Evergreen Sugar Corn

**85 days. Sweetest and Most Delicious Sugar Corn for a Main Crop**

A distinct new sugar corn of the evergreen type. Produces handsome ears which are sweeter and larger than either Country Gentleman or Stowell's Evergreen. The stalk grows 8 to 9 feet high, usually producing 2 large, well developed ears 8 to 10 inches long to each stalk. The large, white grains, of great tenderness and sweetness, are deep set with 14 to 18 rows on the cob. It is usually ready for the table or market in 85 days. It withstands drought unusually well and holds its edible qualities better than most other varieties. We highly recommend this delicious sugar corn for the home garden, market gardener or canner.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**

222 Maule's Lead All Evergreen

## ✱ 229 BANTAM EVERGREEN

**70 days. Larger Ear Than Golden Bantam, but Later**

Just the right sized ear for eating off the cob. Stalks grow 6 to 7 feet high, bearing two ears of 12 to 14 rows of light yellow grains. Matures in 70 days. Sweeter than Golden Bantam.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 20 cts. per lb.; 100 lbs. $17.00**

## 228 Maule's Late Mammoth

**90 days. Late Maturing with Enormous Ears**

This tall growing sugar corn is one of the very sweetest known. It matures its crop in about 90 days, and is large in both stalk and ear. In quality it is delicious, being sweet and tender. The ears remain long in the green state. The large, broad grains are particularly good for canning.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.60, postpaid**
**Not prepaid, 5 lbs. or over at 20 cts. per lb.; 100 lbs. $18.00**

**Customers may order 2 pounds or over at the 5 pound rate, 10 pounds or over at the 100 pound rate**

# POP CORN

CULTURE.—Plant when danger of frost is over in hills 3 to 4 feet apart each way, leaving 3 to 4 stalks to the hill. May also be sown in drills 3 to 4 feet apart, dropping the seed a foot apart in the drills. A packet will sow about 150 feet of drill; use 4 pounds to the acre. Matures in 130 to 140 days.

## 234 Queen's Golden 130 days. The Largest of All Grains

This surpasses all others in size and color. It pops perfectly white, expanding nearly one inch. Matures in about 130 days.

**Packet 10 cts.; ½ pound 25 cts.; pound 35 cts.; 5 pounds $1.25, postpaid**
**Not prepaid, 5 lbs. or over at 18 cts. per lb.; 100 lbs. $15.00**



## ✱ 235 Tom Thumb 130 days. Known as Japanese Hulless and Dwarf Baby Rice

Tom Thumb is a heavy yielder of attractive ears, peculiar in form, being nearly as thick as long. The kernels are similar to the best strains of White Rice, only longer and slimmer and pearly white in color, but its crowning merit lies in its popping quality, fine flavor and absence of hull or shell. Most tender and delicious flavor, without any hard particles. The stalks grow about 5 feet high, and bear two or three perfect ears each, which are matured in about 130 days.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 21 cts. per lb.; 100 lbs. $18.00**



## ✱ 237 Monarch White Rice 140 days. The Popular Variety for Popping

Everybody knows this old favorite sort. Three ears on a stalk is not a rare occurrence, maturing its long, slender ears in 140 days. The white grains are sharply pointed, but when popped are very full; very popular.

**Packet 10 cts.; ½ pound 25 cts.; pound 35 cts.; 5 pounds $1.25, postpaid**
**Not prepaid, 5 lbs. or over at 18 cts. per lb.; 100 lbs. $15.00**

# Maule's Cucumbers

CULTURE.—Flourish best in a rich, warm, sandy loam. Sow when danger of frost is over, in hills 4 or 5 feet each way. As the young plant has many enemies sow thickly half an inch deep, and thin out finally to three or four plants to the hill. For pickles plant during June and July. Use a packet of seed to 15 hills; an ounce to 75 hills; two to three pounds to the acre. Ready to use in 45 to 80 days. Gather cucumbers by cutting, not tearing. Leave none to ripen on the vines if you want a full crop.



## ✱ *244* Maule's Extra Early Cucumber

**55 days. First for the Table, Market and Pickling**

This widely popular cucumber is as early as Green Cluster. Although early, the fruits are of fine quality and the color an attractive dark green. When suitable for pickling, the cucumbers are straight, square ended and very firm. When ready for slicing they are 6 to 7 inches long, crisp and of a most delicious flavor. The vines are of extra vigorous growth and produce an abundance of fruits, which are fit for the table or market in 55 days.

Its extreme earliness is, however, its greatest recommendation, making it invaluable. Its earliness and its very high quality make it a good variety for both home and market gardens, or for planting in June or July for late pickles.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

## ✱ *254* Maule's Earliest Black Diamond Cucumber

**50 days. The Earliest of the White Spine Type. It "Stays Green." Holds Its Dark Green Color a Long While**

Maule's Earliest Black Diamond is the cucumber all growers are looking for. It is adapted to all sections and soils. We especially recommend it to all growers that grow cucumbers either in small or large quantities, for the home garden, market or long distance shipping. The fruit grows seven to eight inches in length, cylindrical in shape, smooth and handsome. The color is a dark green from end to end, with little white rays at the blossom end. Maule's Earliest Black Diamond retains this dark green color longer than any kind we know of. On this account it will always command the highest market price. The flesh is white, firm, crisp, and of the very best quality for slicing. The vine makes a vigorous growth and is an enormous yielder of dark, always green, cucumbers, maturing in about 50 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

254 Maule's Black Diamond

## *258* Nichol's Medium Green

**50 days. Straight and Smooth**

A handsome variety, in shape between Early White Spine and Long Green. Worthy of a high place in the list of pickling sorts, and second to none for slicing when mature. Ready to pick in 50 days. Color dark green. Flesh crisp and tender. Size medium. Always straight and smooth.

**Packet 5 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 65 cts.; pound $1.10; 5 pounds $5.00, postpaid**

261 Chicago Pickling

## ✱ *261* Westerfield's Chicago Pickling

**53 days. Green, with Prominent Spines**

This variety is preferred above all others by some of the largest pickling establishments in Chicago and elsewhere. It is one of the best for the purpose, combining almost every good quality, and being satisfactory alike to grower and pickle maker. Matures its crop in 53 days.

**Packet 5 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.50, postpaid**

## *268* Maule's Early Fortune

**60 days. A Great Favorite with Southern Shippers. Excellent Table Sort**

An attractive variety, and has become very popular. Early Fortune is now being largely grown by market gardeners and shippers both north and south. In color it is an attractive deep green, which it retains much longer than most other sorts. Being fine grained, its white flesh is exceedingly crisp and brittle, excellent for slicing. Matures in 60 days. Is one of the earliest, dark green white spine cucumbers.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

## *259* Snow Pickling

**50 days. The Right Size for Bottling or Slicing**

A beautiful dark green cucumber which is the right size for bottling. Matures in 50 days. It is cylindrical in shape with square ends. The flesh is firm, crisp and tender. Very popular.

**Packet 5 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 65 cts.; pound $1.10; 5 pounds $5.00, postpaid**

## *290* Garden Lemon

**60 days. Also Called Lemon Cucumber**

CULTURE.—Sow seed one-half inch deep in hills 4 to 6 feet apart each way, allowing four plants to remain in each hill. Use a packet to 20 hills, one ounce to two hundred hills, two pounds per acre. Cooking recipe sent with each order.

Fruits short, nearly round, with yellow and green markings. Ripe when turning yellow. Matures in 60 days.

**Packet 10 cts.; ounce 25 cts.; ¼ pound 65 cts.; ½ pound $1.10; pound $2.00, postpaid**

**Pick all Cucumbers when fit for use; if left on the vine to ripen, they destroy its productiveness**

## ✱ 252 Maule's Early White Spine Cucumber

**58 days. The Finest for Slicing, Home Garden or Market**

An extra fine improved type of the best and most widely grown variety in America. It is unsurpassed as a table and market sort, and is also used for pickling. No other kind exceeds it in productiveness, and it is equally good for forcing under glass or growth in the open air. The fruit is from 5 to 7 inches long and 2 to 3 inches in diameter. Color, a beautiful dark green throughout. Matures in 58 days.

**Packet 10 cts.; ounce 15 cts.; ¼ lb. 45 cts.; ½ lb. 75 cts.; lb. $1.25; 5 lbs. $5.50, postpaid**



252 Maule's Early White Spine

## ✱ 245 FORDHOOK FAMOUS

**70 days. The Largest of the White Spines**

A handsome extra long white Spine cucumber; produces perfectly smooth, very dark green, straight fruit, often measuring 12 to 17 inches long. They are always solid, flesh being a greenish white, firm, crisp and of most delicious flavor. It is a great cropper and fruit is full of flesh with but few seeds. Matures in about 70 days.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 50 cts.; ½ pound 85 cts.; pound $1.50; 5 lbs. $6.25, postpaid**

## 250 Improved Arlington White Spine

**62 days. Attractive, Long, Dark Green in Color**

A productive white spine variety of average size, seven to eight inches in length, with broad and showy foliage, habit of growth rather rampant. Fruit long and slim and very dark green throughout the entire length with only a very slight white marking at the blossom end. Matures in 62 days. The flesh is white, crisp and solid with comparatively few seeds. Improved Arlington is a superior strain and is recognized as a standard by all growers. Very desirable for the home garden, and an ideal truckers variety.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 40 cts.; ½ pound 65 cts.; pound $1.10; 5 lbs. $4.75, postpaid**

## 263 Early Green Cluster

**50 days. Bears in Twos and Threes**

This is a short, pale green variety, maturing in 50 days. It is rather prickly and contains few seeds. The fruit is borne in clusters; it is a favorite for pickling on account of its great productiveness.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 lbs. $4.50, postpaid**

## 266 Everbearing

**45 days. A Continuous Bearer Throughout the Season**

This is a unique and highly meritorious pickling variety; meritorious because of its quality, and unique in its ability to go right on bearing throughout the entire season. It is enormously productive and a general favorite. Fruits of every age may be found on a single vine. Fit to eat in 45 days. Especially desirable for pickles and excellent for home gardens.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 85 cts.; 5 lbs. $3.75, postpaid**

## 273 Small Gherkin

**80 days. Used for Pickles Only**

A novel little cucumber grown for show and pickles. The fruit is oval, 2 to 3 inches in length, and closely covered with spines. Used exclusively for pickling, for which purpose it is in high favor. Matures in 80 days.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 50 cts.; ½ pound 85 cts.; pound $1.50; 5 lbs. $6.75, postpaid**

## ✱ 257 Maule's Improved Long Green

**70 days. Very Popular Variety**

This fine cucumber grows from 12 to 16 inches or more in length, and is of superior quality. The young fruits are very largely used for pickling, and it is a standard sort for that purpose. Full sized cucumbers are in high favor for making the so-called sweet pickles. Vines are strong growers and the fruit is always produced in great abundance. Produces large pickles in 70 days.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 50 cts.; ½ pound 85 cts.; pound $1.50; 5 lbs. $6.25, postpaid**



245 Fordhook Famous

257 Maule's Improved Long Green Cucumber

## ✱ 246 DAVIS PERFECT CUCUMBER

**60 days. Davis Perfect Planted Outdoors Will Equal in Flavor and Resemble the High Priced Hot House Forcing Sorts**

The Davis Perfect has become the most popular cucumber both for forcing under glass and growing outside, for the following reasons:

**First.** It has an ideal shape, and the handsomest dark green color of all cucumbers. Ready to pull in 60 days.

**Second.** It is a type of the most perfect size; just what is wanted either for the table or market.

**Third.** Eating qualities surpass any other cucumber.

**Fourth.** It is almost seedless one-third of its length from the stem end, and the seeds when it is in slicing condition are so small and tender that they are unnoticed.

**Fifth.** It is enormously productive, in fact, beats anything we have ever tried.

**Sixth.** It does not change its dark, rich color when grown outdoors; in fact, it resembles a hothouse cucumber so closely that dealers cannot tell the difference, and are willing to pay as much for it as the hothouse production. We believe this is the greatest cucumber ever introduced, and it is bound to become popular everywhere when it is known. It will be a big money maker for anyone engaged in growing cucumbers in the open ground. The Davis Perfect has had the greatest sale any cucumber novelty has ever had and every grower, whether for home consumption or for market, to be abreast of the times, should plant this variety.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 40 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.00, postpaid**

## ✱ 247 MAULE'S SHAMROCK

**60 days. A Desirable Dark Green, White Spine Sort**

Our special strain of this desirable cucumber grows regular in shape, size and color, and will be sure to please you. The vines are very hardy, prolific and a sure cropper, producing cucumbers 7 to 8 inches long which are very attractive, dark green in color, and remain green for days after being picked and shipped. Very crisp and unsurpassed for slicing or pickling. Matures in 60 days. It is a good table cucumber and is one of the best market sorts.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

247 Maule's Shamrock

## ✱ 256 Green Prolific or Boston Pickling

**50 days. Early and Valuable for Pickles**

This is one of the most popular pickling cucumbers, of the very best form and quality, and has yielded at the rate of over 200,000 pickles per acre. Its enormous productive ability makes this variety a favorite one. Ready to pick in 50 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 85 cts.; 5 pounds $3.75, postpaid**

## 251 Maule's Earliest Klondike

**60 days. Holds Its Dark Green Color for Many Days After Picking**

Excellent strain of White Spine, remarkable for the uniformly dark green skin of its shapely fruits. Its good qualities are its extreme earliness and prolificness. Very hardy, resisting unfavorable weather conditions and is a good size for slicing. It is also quite firm when small and is excellent for pickling. Matures in 60 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 40 cts.; ½ pound 70 cts.; pound $1.15; 5 pounds $5.25, postpaid**

## 264 Cool and Crisp

**65 days. Bears the Whole Season. Tender, Table Sort**

An exceedingly prolific and handsome variety. At the pickling age the fruit is straight, long, even and slim, and until it reaches full size it is of a very dark green or almost black color. The knobs bearing the spines are prominent at all stages of growth, giving the cucumber a characteristic appearance. Matures its crop in about 65 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 40 cts.; ½ pound 65 cts.; pound $1.10; 5 pounds $5.00, postpaid**

## 267 Danish Pickling

**65 days. Medium Size, Thickly Set with Small Spines**

This variety has shown itself to be a remarkable grower, producing in 65 days handsome cucumbers which remain green through all the growing stages. The flesh is firm and solid, crisp and has an excellent flavor. It is a shy seeder and is just what is wanted for slicing for the table as well as for pickling. In Denmark this variety is used exclusively for making dill and mustard pickles.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 55 cts.; ½ pound 95 cts.; pound $1.65; 5 pounds $7.25, postpaid**

## 272 Japanese Climbing

**60 days. Can Be Grown on Pole or Trellis**

All cucumbers are of trailing or creeping habit, but this one is a real climber and does best on pole or trellis. It can be picked in 60 days. The fruit is of excellent quality, of dark green color. The flesh is pure white and never bitter. Fine for slicing and pickling.

**Packet 10 cts.; ounce 25 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

## 274 Mixed Cucumbers

**45 to 80 days. One Planting for the Season**

This mixture contains early, medium and late sorts. Customers can have an abundant supply of Cucumbers, either for pickling or slicing. This mixture prolongs the picking season from 45 to 80 days. A mixture suitable for the home garden.

**Packet 5 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00, postpaid**

256 Green Prolific

# Maule's Egg Plants

CULTURE—Sow the seed in hotbed or greenhouse in March or April, and transplant in small pots or shallow boxes. Plant in the open ground when danger of frost is past, in rows 3 feet apart each way. A packet will produce about 150 plants, an ounce about 2000 plants; ¼ pound for an acre. Ready for use in 120 to 140 days.

## ✱ 277 Maule's Excelsior Egg Plant

**140 days. The Largest of All; Blight Proof**

It is of large size and extremely good shape, being particularly adapted to slicing, and for flavor it cannot be surpassed. It resists drought, blight and bad weather to a wonderful degree, on account of its strong, upright growth. The fruit often measures 18 to 24 inches in circumference (6 to 8 inches in diameter) and is borne well above the ground. Matures in 140 days.

**Packet 15 cts.; ½ ounce 30 cts.; ounce 50 cts.; ¼ pound $1.40; ½ pound $2.65; pound $5.00, postpaid**

## 281 New York Improved Purple

**130 days. Leading Sort for Home and Market**

This is an entirely spineless strain of the large purple-fruited type. Our strain of this variety is especially fine. The plants are most productive, bearing oblong fruits in 130 days which are a beautiful rich purple. The large plants bear 4 to 6 full-size fruits. It is an excellent market and home garden sort.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 45 cts.; ¼ pound $1.25; ½ pound $2.40; pound $4.50, postpaid**

## ✱ 282 Black Beauty

**120 days. The Earliest Large Egg Plant**

Originated in South Jersey. It combines in itself many characteristics which are very valuable. It is very early, maturing in 120 days. By this we mean it is the earliest variety that grows to a good size suitable for market. It is very desirable in color, being a jet black. Shape is nearly round, average weight 2 to 3 pounds. It is dwarf growing and bears its fruit close to the main stem.

**Packet 10 cts.; ½ ounce 30 cts.; ounce 50 cts.; ¼ pound $1.40; ½ pound $2.65; pound $5.00, postpaid**

277 Maule's Excelsior Egg Plant

# Gourds

CULTURE—Gourds are tender annuals. The seed should not be planted until the ground is warm. Plant in hills and cultivate as squash. Leave only three or four plants in a hill, and allow the vines to ramble over the ground, or train on fence, trellis or arbor. A packet will sow about 10 hills, 2 ounces about 100 hills. Matures in 65 to 90 days.

## 299 Calabash or Pipe

**80 days. Useful for Making Pipes**

An ornamental gourd from which are made the African calabash pipes now so popular on account of their lightness, grace and meerschaum coloring qualities. When grown for the production of pipe gourds, the vines are usually allowed to grow on the ground like cucumbers, pumpkins, etc., so that the fruits in place of hanging down and growing straight, will take their natural pipe curve. Matures in 80 days. Directions for growing, curing and how to make pipes sent with all packages.

**Packet 10 cts.; ½ ounce 20 cts.; ounce 35 cts., postpaid**

## 295 Nest Egg

**65 days. Useful for Darning or Nest Eggs**

This interesting gourd produces white fruit exactly the size and shape of a hen's egg. The matured fruit does not crack, and will serve for years as a nest egg, or for darning stockings. Matures in 65 days.

**Packet 10 cts.; ½ ounce 20 cts.; ounce 35 cts., postpaid**



## 297 Mixed Gourds

**65 to 90 days. Ornamental as Well as Useful**

In this mixture we offer all the varieties listed and some other varieties we grow, so that you may enjoy a number of curious novelties. Matures in 65 to 90 days.

**Packet 10 cts.; ½ ounce 20 cts.; ounce 35 cts., postpaid**

## 291 Dish Cloth or Luffa

**90 days. Useful as a Sponge or Dish Cloth**

The peculiar lining of this gourd gives it its name. The fruit grows about two feet long. The interior membrane is serviceable for a variety of household purposes, being used as a dish cloth, or sponge. Matures in 90 days.

**Packet 10 cts.; ½ ounce 20 cts.; ounce 35 cts., postpaid**

## 292 Orange or True Mock Orange

**70 days. Useful for Darning**

A good old sort, the fruit often finding its way into the family sewing basket. A beautiful and rapid climber. Fruit the size and shape of an orange. Matures in 70 days.

**Packet 10 cts.; ½ ounce 20 cts.; ounce 35 cts., postpaid**

## 293 Dipper

**75 days. Useful for Dipping**

A well known and useful gourd. When grown on the ground the stem is much curved; but on a trellis the weight of the fruit makes the stem straight. Matures in 75 days.

**Packet 10 cts.; ½ ounce 20 cts.; ounce 35 cts., postpaid**

# Ground Cherry

**Used Only for Preserving or Pies**

CULTURE—Grow and cultivate the same as tomatoes. Full cooking recipes sent with every order. A packet will produce about 400 plants; an ounce, about 5000 plants.

## 300 Mammoth Purple Fruited Ground Cherry

**120 days. The Green Gage Purple Husk Tomato**

A prolific bearer of enormous size fruit, which measures 1½ to 2½ inches in diameter. The flesh is green while the color of the skin is green changing to a purple. This fruit when made into preserves has the appearance of green gages. Forms a plant 2½ feet high. Ready for use in 120 days.

**Packet 10 cts.; ½ ounce 35 cts.; ounce 60 cts., postpaid**



## 301 Improved Ground Cherry

**120 days. Known as Strawberry or Yellow Husk Tomato**

The small, yellow fruit is very sweet, of mild flavor, used for preserving. Matures in 120 days. Vines low and spreading.

**Packet 10 cts.; ½ ounce 35 cts.; ounce 60 cts., postpaid**

# Kohl Rabi

CULTURE—Sow in drills 12 to 18 inches apart and thin out to 6 inches apart in the row. A packet will sow about 40 feet of drill, an ounce about 300 feet, 2 pounds to an acre.

## ✱ 310 Improved Imperial

**50 days. Known as Early White Vienna**

A select extra early, short topped strain.

**Pkt. 10c.; oz. 25c.; ¼ lb. 70c.; ½ lb. $1.25; lb. 2.25; 5 lbs. $10.50, postpaid**

## 311 Large White

**60 days. Late and Quite Hardy**

Extra large bulbs. Sweet and tender.

**Pkt. 5c.; oz. 20c.; ¼ lb. 60c.; ½ lb. $1.00; lb. $1.75; 5 lbs. $7.50, postpaid**

Kohl Rabi

## 312 Early Purple Vienna

**50 days. Earliest and Best for Home Garden**

Purple skin, flesh white, tender and of fine quality; matures in 50 days.

**Packet 10 cts.; ounce 25 cts.; ¼ pound 70 cts.; ½ pound $1.25; pound $2.25; 5 pounds $10.50, postpaid**

## For Flavoring Soups, Meats, etc. Herb Seeds For Potherbs, Sweet and Medicinal Purposes

CULTURE—Sow in early spring, at the time when the trees begin to leaf, in ordinarily good and well drained garden soil, in rows 12 to 24 inches apart. Cover seed lightly. Thin or transplant to stand 6 to 12 inches apart in the rows. Cultivate frequently and keep free from weeds. Packet will sow about 25 feet of drill; an ounce about 200 feet. Ready to use in 30 to 50 days.

### * 758 Marjoram, Sweet

The leaves and the ends of the shoots are highly esteemed for seasoning.
**Packet 10 cts.; ½ ounce 20 cts.; oz. 35 cts.; ¼ lb. 90 cts.; ½ lb. $1.70; lb. $3.25, postpaid**

### † 742 Caraway

Seeds are used for flavoring bread, pastry, meats, etc. The oil relieves gas on the stomach and prevents griping.
**Packet 10 cts.; ½ ounce 15 cts.; ounce 25 cts., postpaid**

### † 770 Sage

The most extensively used of all herbs for seasoning and dressing.
**Packet 10 cts.; ½ ounce 20 cts.; oz. 35 cts.; ¼ lb. 90 cts.; ½ lb. $1.70; lb. $3.25, postpaid**

### † 744 Catnip

Grown for bee pasture. Leaves and young shoots are used for seasoning.
**Packet 15 cts.; ½ ounce 40 cts.; ounce 75 cts., postpaid**

**NOTE.** — We can also supply the following varieties of Herb Seeds.

| | | Pkt. | ½ Oz. | Oz. |
|---|---|---|---|---|
| 732 | *Anise | .10 | 20 | 30 |
| 736 | *Basil Sweet | .10 | 20 | 35 |
| 740 | *Borage | 10 | 20 | 30 |
| 746 | *Coriander | .10 | 15 | 25 |
| 754 | †Horehound | .10 | 20 | 35 |
| 756 | †Lavender | .10 | 25 | 40 |
| 764 | †Rosemary | .10 | 25 | 45 |
| 780 | †Winter Savory | 10 | 25 | 45 |
| 782 | †Wormwood | .10 | 20 | 30 |

(Herbs marked * are annual; marked † are perennial.)
**All postpaid**

### † 752 Fennel, Sweet

The leaves are ornamental. When boiled, are used in fish sauces, also make a splendid tea for colic.
**Packet 10 cts.; ½ ounce 15 cts.; ounce 25 cts., postpaid**



### † 745 Chives

Also called Schnittlauch. Chives resembles small onions. The tops are used for flavoring. More delicate than onions. Perfectly hardy.
**Packet 10 cts.; ½ ounce 30 cts.; ounce 50 cts., postpaid**

### * 750 Dill

Fruit is warming, stimulating and quiets nervousness. The tea is good for colic and prevents hiccough. The plants are used largely for pickling cucumbers.
**Packet 5 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00, postpaid**

### † 778 Thyme

The leaves and shoots are used for seasoning; a tea is also made of the leaves, a remedy for headaches.
**Packet 10 cts.; ½ oz., 25 cts.; ounce 45 cts.; ¼ lb. $1.25; ½ lb. $2.40; lb. $4.50, postpaid**

### * 772 Summer Savory

The leaves and flowers are used for flavoring soups, dressings, etc.
**Packet 10 cts.; ½ ounce 15 cts.; ounce 25 cts., postpaid**

## ✱ 303 Maule's Emerald Isle Kale

**55 days. Quite Hardy, Half Dwarf, Finely Curled Sort**

A distinct and hardy variety of medium height. The leaves are very large, deeply curled and fringed and of that desirable rich, deep green color. The plants are hardy above zero; frost improves the quality.

Maule's Emerald Isle is one of the handsomest and hardiest Kales ever developed, yielding a tremendous crop of fine, large, curly leaves for greens. Ready to use in 55 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ lb., 75 cts.; pound $1.25; 5 pounds $5.25, postpaid**

# Kale or Borecole

CULTURE—For late Fall or early Winter use, sow early in June and transplant about the middle of July in rows 18 to 24 inches, setting the plants 8 to 10 inches apart in the rows. For Spring use, sow in August or September. A packet will produce about 300 plants, an ounce about 3000 plants; ¼ pound enough for an acre. Protect during winter with a covering of hay or coarse litter. All Kales are improved when touched by frost. Ready to use in 50 to 60 days.

## ✱ 306 Dwarf Green Curled Scotch

**50 days. Very Hardy; Sometimes Called Norfolk**

The plant is low and compact. Remarkably tender and delicate in flavor. Leaves rich green and very curly. Hardy. Matures in 50 days.
**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $3.75, postpaid**

## 304 Hardy Dwarf Siberian

**60 days. In Some Sections Called Sprouts; Extremely Hardy**

One of the best known and most largely used varieties. A large plain leaved variety of a low or spreading habit, with grayish green leaves which are only slightly curled at the edge. Matures in 60 days.
**Packet 5 cts.; ounce 10 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 85 cts.; 5 pounds $3.75, postpaid**

## 307 Tall Green Curled Scotch

**60 days. Quite Hardy, Plume-Like Foliage**

Grows about two feet high, with an abundance of dark green leaves, which are very curly and wrinkled. Quite hardy. Matures in 60 days.
**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $3.75, postpaid**

# Leek

CULTURE—Sow in frames or border in early spring, in drills 12 to 18 inches apart and 1 inch deep. When plants are 6 to 8 inches high transplant to permanent quarters in rows a foot apart and plants 4 to 6 inches apart in rows. Set the young plants deeply in the soil, so that the neck, being covered, will easily blanch. A packet will sow about 25 feet of drill, an ounce to 150 feet, 4 to 5 pounds to the acre. Ready to use in about 80 days.

313 Giant Italian

## ✱ 313 Giant Italian Leek

**80 days. The Favorite Home or Market Sort**

The largest variety, stems very thick with broad leaves. When well grown often produces stalks three inches in diameter; white and tender, mild in flavor. It is an exceptionally hardy garden or market sort; matures in 80 days.
**Packet 10 cts.; ounce 25 cts.; ¼ pound 70 cts.; ½ pound $1.25; pound $2.25; 5 pounds $10.00, postpaid**

## MATURITY DATES

**At the heading of all VEGETABLE SEED descriptions we are giving the maturity dates, starting from day of sowing the seed, thus (50 days). This will tell you when you may expect vegetables ready for the table; of course the weather conditions must be favorable for producing the crops.**

# Maule's Lettuce

CULTURE—Seed may be started indoors or in frames during February or early March and plants set outdoors as early in the Spring as the ground can be worked, in rows 1 foot apart and 8 to 12 inches apart in the row. Seed may be sown in the open ground as soon as it can be worked, in rows 1 foot apart, covering seed about 1 inch; thin plants out to stand 6 to 8 inches apart in the row. Make successional sowings every two weeks until June; for Fall use sow seed in August and September. A packet will sow about 30 feet of drill, an ounce about 300 feet, use 4 to 5 pounds for an acre. Ready to use in 38 to 55 days.

316 Maule's Immensity Lettuce

## ✱ 316 Maule's Immensity

**50 days. The Largest Grown, the Best Heat Resister**

This grand lettuce is claimed to be without exception the very largest lettuce in cultivation. Notwithstanding its great size it is tender, sweet and crisp. It produces in 50 days a fine, large, solid head. It has great heat resisting qualities, being slow to run to seed, so that it is very reliable for a late crop when many other sorts are unfit for use.

**Packet 10 cts.; ounce 25 cts.; ¼ pound 65 cts.; ½ pound $1.10; pound $2.00; 5 pounds $8.75, postpaid**

## 318 May King

**45 days. A Quick Grower, Extremely Hardy**

Very early, and a quick grower. Matures in 45 days. Leaves are a light green, slightly tinged with brown, inner leaves a bright yellow. In flavor it is particularly rich, buttery and tender. Excellent for early outdoor planting or for forcing. Popular both in home or market gardens.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.35; 5 pounds $6.25, postpaid**

**SOW MAULE'S SEEDS**
"There are none better"

331 Crisp-as-Ice Lettuce

## 330 California Cream Butter

**50 days. Round, Crisp, Solid Heads of Buttery Flavor**

Forms a very large head in 50 days, which is very buttery. The bright leaves are slightly spotted with brown. Withstands extreme heat or cold.

**Packet 5 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.35; 5 pounds $6.25, postpaid**

## 326 Early Prize Head

**45 days. Crisp and Tender Loose Head Sort**

This lettuce forms a large tender, crisp, loose head of bright green crimped leaves tinged with brownish red, of superior flavor, long remaining sweet and slow to run to seed. Matures in 45 days.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 50 cts.; ½ pound 85 cts.; pound $1.50; 5 pounds $6.25, postpaid**

## ✱ 331 Crisp-as-Ice

**50 days. Medium Size, Compact, Solid Heads**

A beautiful cabbage head lettuce for home use. The solid heads are of medium size, and the leaves are so tender and brittle as to have suggested the name bestowed upon it. The heads, when cut open, have a rich, creamy yellow heart. The green leaves, variegated with bronze, are thick and glossy, somewhat curled. Matures in 50 days.

**Packet 10 cts.; ounce 25 cts.; ¼ pound 65 cts.; ½ pound $1.15; pound $2.00; 5 pounds $8.75, postpaid**



344 Black-Seeded Simpson Lettuce

## ✱ 342 Grand Rapids

**38 days. A Home Garden or Market Favorite**

Bright green savoyed leaves, finely crumpled at edges; of crisp, sweet, delicious flavor. Matures in 38 days. Best for outdoor or forcing.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 50 cts.; ½ pound 85 cts.; pound $1.50; 5 pounds $6.75; postpaid**

**Customers may order 2 pounds or over at the 5 pound rate**

## ✱ 344 Black-Seeded Simpson

**40 days. The Best Cut and Come Again Sort**

The best of the non-heading lettuces. It is light green colored, with inner leaves almost white; good for spring and early summer culture. Matures in 40 days and remains long in edible condition.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.35; 5 pounds $6.25, postpaid**

## 346 All the Year Round

**50 days. An Improved Salamander; a Solid Butter Head Sort**

One of the most popular varieties for withstanding heat. Grows large size, solid heads in 50 days of a light green color, which bleach white, of the finest quality. Good for spring or fall planting or forcing.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.35; 5 pounds $6.25, postpaid**

342 Grand Rapids Lettuce

## ✱ *334* Big Boston Lettuce

**45 days. A Great Favorite for Forcing and Equally Desirable for Out-door Planting**

334 Big Boston Lettuce

A popular sort whether grown in the open ground for summer and fall use or in frames for use in early spring, as well as for forcing in the greenhouse during the winter. Its large, compact, bright green, crisp and tender heads have few outer leaves, the heart is a light golden yellow color. An excellent long distance shipper. Matures in 45 days.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 50 cts.; ½ pound 85 cts.; pound $1.50; 5 pounds $6.50, postpaid**

## *341* Chicken Lettuce

**45 days. All kinds of Poultry Eat It Greedily**

Your poultry needs green food. Chicken lettuce is just the thing you want to grow for them. This lettuce will yield more food for your poultry or rabbits than any plant that you may have used for greens. Grows 4 feet high when running to seed. Ready to cut in 45 days, after which it starts to grow again and makes a successive crop.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.35; 5 pounds $6.25, postpaid**

## *323* Iceberg

**50 days. Known as Ice Head Lettuce, Extremely Hard Heading**

Large, handsome head, of fine flavor. The light green, curly outside leaves have slightly reddish edges. The inside leaves are strongly arched, making a solid, well blanched head. Matures in 50 days.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 60 cts.; ½ pound $1.00; pound $1.75; 5 pounds $7.50, postpaid**

## *336* Maule's All Seasons

**50 days. Large Butter Head Sort. A Great Heat Resister**

An excellent variety; does exceedingly well in hot, dry weather. It s medium large in size, having large, broad leaves of a light green color, xtremely solid, tender and mild. Matures in 50 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.35; 5 pounds $6.25, postpaid**

## *337* Early Curled Simpson or Silesia

**40 days. Very Early Loose-Head Cutting Variety**

This is the old favorite popular loose head variety, of dwarf, compact abit. Matures in 40 days. The curly leaves are large, yellowish green vith finely curled edges. Crisp and tender, hardy and withstands heat nd drought. Sure to make good leaves, under unfavorable conditions.

**Packet 5 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

## *343* Romaine or White Cos

**55 days. Crisp, Tender and Sweet**

Grows about 10 inches high. Leaves being well folded toward the enter, bleaches almost pure white, crisp and tender. Matures in 55 days.

**Packet 10 cts.; ounce 25 cts.; ¼ pound 65 cts.; ½ pound $1.15; pound $2.00; 5 pounds $8.75, postpaid**

328 Maule's Improved Hanson Lettuce

## ✱ *328* Maule's Improved Hanson

**50 days. Withstands Extremes of Weather Better than Others**

In table quality this lettuce is perfection itself. It is wholly free from bitter taste, having a sweet and rich flavor, even to the outer leaves. Matures in 50 days. It remains long in good table condition, and resists heat and drought well. It is a perfect open air lettuce in all respects. It is hardy and may be set out in earliest spring or grown late in the fall.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.00, postpaid**

## *339* Mixed Lettuce

**38 to 55 days. One Sowing for the Season**

Twelve to fifteen sorts—early, medium and late. One sowing produces salad for the entire season; a grand assortment of decidedly distinct and excellent lettuces; all are crisp and tender. Matures in 38 to 55 days.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 50 cts.; ½ pound 85 cts.; pound $1.50, postpaid**

340 Burpee's Earliest Wayahead Lettuce

SHOP BY MAIL

## ✱ *340* Burpee's Earliest Wayahead

**40 days. The Earliest of the Head Lettuces**

An extra early heading lettuce, producing good size heads in 40 days, vhich are tightly folded; the inner leaves bleach to a rich buttery yellow. uality excellent, very sweet, crisp and of firm texture, an excellent let- uce for sowing in cold frames in the early spring, as well as in the open round in spring and fall. A desirable home or market sort.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 50 cts.; ½ pound 85 cts.; pound $1.50; 5 pounds $6.50, postpaid**

## ✱ *345* New York or Wonderful

**55 days. Known as Los Angeles. The Heat Resister**

A popular variety for summer planting. The best heat resister with arge white heads. Resemble cabbage in their solidity, frequently weigh and 3 pounds each. The quality is superb, being crisp, rich and tender. Matures in 55 days. Does remarkably well in all sections.

**Packet 10 cts.; ounce 25 cts.; ¼ pound 70 cts.; ½ pound $1.25; pound $2.25; 5 pounds $10.00, postpaid**



345 New York or Wonderful Lettuce

# Maule's Muskmelons

CULTURE—Plant seed in hills 4 to 6 feet apart each way, after danger of frost is over. Use well rotted manure in t hills. Insert seeds just under surface of soil; use a packet to 15 hills, 1 ounce to 60 hills; 2 to 3 pounds to an acre. Thin o leaving only 4 plants to a hill. A light, warm soil is best suited to all melons. Ready to use in 57 to 85 days. Casabas a Honey Dews in 120 days.

## ✱ *351* Maule's Model The Famous Muskmelon

**70 days. Spicy Green Flesh. Small Seed Cavity. A Prodigious Cropper. A Melon of Distinguished Pedigree. High Bred at Every Point.**

(Green flesh.) A paragon of merit—in size, shape, netting, appearance, aroma, flavor, depth of flesh, smallness of seed cavity, cropping ability and shipping quality. It is by far the finest, most delicious muskmelon ever grown.

**Maule's Model** is an early large melon, maturing its crop of fine, luscious, green flesh melons in 70 days. It is larger than Rocky Ford, the average weight being somewhat above two pounds. It has an ideal shape for a fashionable market. The interior seed cavity is small, and of triangular or prismatic shape, the seeds being few.

**Maule's Model** as a table melon cannot be surpassed. In delicacy and quality of flavor it is unexcelled by any variety in our list. The flesh is deep and firm, extending from the rind almost to center of the melon. Rich and highly flavored.

**Maule's Model** bears transportation well, and can be carried to distant cities without injury, where it will bring the highest prices. The right size for hotel or table use. One of the best for home or market gardeners.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**



351 Maule's Model Muskmelon

## ✱ *364* Improved Watter's Solid Net Rocky Ford

**65 Days—the Earliest of All Solid Netted Rocky Fords For the Home Garden or Shipper**

364 Improved Watter's Rocky Ford

(Green flesh.) Watter's Solid Net sets a very heavy first crop, so that in few days after the first ripe melons, heavy pickings are in order for the next tw or three weeks. It is a most valuable sort to plant where first melons on th market are of great importance, and has made the best record for money return on account of its early maturity. Furthermore, Watter's produces melons of eve size and shape. The well developed gray and green netting is very closely lace The thick flesh is light green, spicy and sweet. It germinates a very vigorou plant that sets fruit early and matures its crop in about 65 days. The large yiel of early cantaloupes, when prices average high, is the strong point in favor c this strain. Excellent early shipping sort or for the home garden.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**

## ✱ *366* Tip Top

**80 days. The Largest and Sweetest Can't-Be-Beat Melon**

(Orange flesh.) This is a fine melon, nearly round in shape. It is sweet, juic and delicious. The flesh is firm but not hard, and is edible almost to the rind. Th melon is of medium to large size, evenly ribbed and moderately netted; a stron grower, heavy yielder and of handsome appearance. Matures in 80 days. Thi melon has been grown for a number of years by market gardeners near Rochester N. Y., also Columbus, Ohio, and has proven so superior in every way that there i practically no other variety grown for this market.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

## ✱ *363* New Honey Ball Muskmelon

**100 days. A Cross Between a Cantaloupe and a Honey Dew Melon**

(Green flesh.) This distinct new melon has become a great favorite where Honey Dew Melons are known. Honey Ball produces good size vines which are blight resistant and hardier than Honey Dew and are more prolific, sure cropper and earlier, maturing melons in about 100 days. The melons are as round as a ball, little larger than Rocky Fords. The delicious thick green flesh is sweet to the rind and has very small seed cavities. The color of rind is greenish white until it is fully ripe when it turns to a creamy white and are slightly netted. Honey Ball possesses that sweet, sugary flavor found in the Honey Dew and will keep in perfect condition for several weeks after they are pulled from the vines. A prime favorite as a shipping melon or for the home garden.

**Packet 10 cts.; ounce 25 cts.; ¼ pound 65 cts.; ½ pound $1.15; pound $2.00; 5 pounds $8.75, postpaid**



363 New Honey Ball Muskmelon

# ✱ 367 Bender's Surprise Muskmelon

367 Bender's Surprise Muskmelon

**80 days. A very popular variety. Large size, deliciously sweet, with long keeping qualities**

(Salmon flesh.) A very popular, large muskmelon, known in the East, particularly around Albany, N. Y., where it has a wide reputation for high quality in the best hotels and markets. It grows, in all sections, to a very large size, often producing melons weighing 10 to 15 pounds. The melons are oval in shape, light green, with coarse netting. When ripe, turns to a golden tint, which gives the fruit an attractive appearance.

The very thick, deep orange colored flesh is deliciously sweet and of high flavor. The vines are productive, producing melons in about 80 days that will keep in good condition 5 to 6 days after picking. For the home garden, market or shipping, this is an important consideration.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 60 cts.; ½ pound $1.00; pound $1.75; 5 pounds $7.50, postpaid**

## 365 Extra Early Grand Rapids

**60 days. Delicious Home Garden Melon**

(Orange flesh.) This extremely early muskmelon matures extra large melons in 60 days. Oblong shape, pale green, turning to yellow when ripe. The flesh is orange, sweet and luscious.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

## 382 Maule's Prize Jenny Lind

**58 days. Though Small, the Sweetest of All**

(Green flesh.) This is the earliest of all green fleshed sorts and one of the sweetest, of small to medium size, 4 to 5 inches in diameter. The flesh is deep and thick, light green in color. The flavor is exceedingly fine. The skin is green, ribbed and netted. A heavy cropper. Matures in 58 days. Excellent home garden sort.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 40 cts.; ½ pound 65 cts.; pound $1.15; 5 pounds $5.00, postpaid**

## ✱ 353 Edward's Perfecto Salmon Flesh Rocky Ford

**70 days. The Best of the Rocky Fords for Shipping or the Home Garden or for Market**

(Salmon flesh.) A new type developed from Eden Gem. The uniform size fruit is nearly round and densely covered with a hard gray netting. Flesh very thick and of a beautiful salmon color. Matures in 70 days. Edward's Perfecto has the deepest flesh, smallest seed-cells and more salmon-colored flesh than any other type of the Rocky Ford shipping melons. Recommended for their hardiness, prolificness and deep flesh and excellent eating and shipping qualities.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

## 349 Solid Netted Burrell's Gem

**75 days. Equal to the Rocky Ford but Larger**

(Orange flesh.) This large muskmelon may be called an orange fleshed Rocky Ford with solid netting. Producing oval shaped melons which are very thick fleshed, fine grained, rich orange colored, sweet and spicy. For a shipping melon, they pack ideal, both for size and shape, and for either market or home use where a pink or orange fleshed melon is wanted. Matures in 75 days.

**Packet 5 cts.; ounce 15 cts.; ¼ pound 40 cts.; ½ pound 65 cts.; pound $1.15; 5 pounds $5.00, postpaid**

## 355 Maule's Honey

**75 days. Noted for Its Very Rich, Sweet and Sugary Flavor**

(Green flesh.) Maule's Honey muskmelon is of medium size, weighing 3 to 4 pounds on an average. It is distinctly and evenly ribbed and moderately netted; globe shape and somewhat flattened at the stem and blossom end. Its exterior color is a peculiar shade of green, quite unlike any other muskmelon. The flesh is green, inclining to yellow. The spicy flavor is as distinct and characteristic as it is sweet and pleasing. The flesh is both deep and firm, the edible portion almost touching the rind. Matures in 75 days. Excellent home garden or market sort.

**Packet 10 cts.; ounce 15 cts.; ¼ ounce 45 cts.; ½ pound 75 cts.; pound $1.35; 5 pounds $6.25, postpaid**



383 Banana Muskmelon

## ✱ 357 Hearts of Gold

**70 days. Extremely Thick, Sweet Orange Flesh**

(Orange flesh.) An ideal basket and crate melon of medium size, round, heavily netted, flesh very thick, of rich orange color, handsome appearance and of the sweetest flavor. Average size of melon 6 to 8 inches in diameter. Matures in 70 days. The seed cavity is small and the rind is very tough, making it a good shipper; its vine is a vigorous grower and a heavy cropper. A very convenient sized melon for the table and for packing in shipment. Does well in all sections.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

## 384 Mixed Muskmelons

**57 to 120 days. Excellent for the Home Garden**

(Green and orange flesh.) By planting this mixture one is sure to produce melons in 57 to 120 days of luscious flavor that are suited to your climate. Excellent assortment for the home garden.

**Packet 5 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25, postpaid**

## 383 Banana

**85 days. So Called on Account of Its Banana-Like Shape and Flavor**

(Orange flesh.) This curious melon attains a length of 18 to 24 inches and a diameter of 2 to 4 inches. The flesh is deep, and of exquisite flavor. This sort is not a mere curiosity, but commands good prices in city markets, 50 cents to $1.00 each. A good melon for home use.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25, postpaid**

## ✻ 347 Maule's Select Rocky Ford or Netted Gem

**70 days. The Popular Melon for Market or Home Garden**

(Green flesh.) In this Rocky Ford melon we offer our customers a strain of seed grown for us by one of the very best, if not the best, growers of melons in Rocky Ford, Colo. Melons are slightly oval in shape, finely netted. Flesh is light green in color, very thick and firm, ripening close to the rind; in flavor it is luscious and sweet, the vines are vigorous and productive. Matures in 70 days. A desirable early sort.

**Packet 5 cts.; ounce 15 cts.; ¼ pound 40 cts.; ½ pound 65 cts.; pound $1.15; 5 pounds $5.00, postpaid**

## ✻ 369 Pollock's Solid Rock

**70 days. The Handsomest, Best Netted Early Melon in Existence**

(Green flesh.) It gives us much pleasure to be able to offer to our customers this grand early solid net strain of Rocky Ford. It has the heaviest, thickest flesh and the smallest seed cavity. Its oval shape is the same as the Rocky Ford with a solid gray netting. The average yield is over 250 crates per acre of A No. 1 shipping melons, fully a third more than other sorts. The extra thick green flesh has a beautiful pinkish hue of the most delicious quality, and is one of the best rust resisting melons ever produced.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 40 cts.; ½ pound 65 cts.; pound $1.15; 5 pounds $5.00, postpaid**

## 370 Delicious Gold Lined Rocky Ford

**70 days. One of the Sweetest and Most Delicious Melons**

(Green flesh.) The melons are covered with a heavy grayish netting. Its shape is ideal, very slightly oval, no ribs and is heavily netted over the entire melon. A wonderfully prolific yielder, producing its luscious medium size melons in 70 days. It is the right shape to pack to best advantage in crates. The seed cavity is very small, flesh thick and firm; a good melon for market as well as the home garden.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 90 cts.; 5 pounds $3.75, postpaid**

## ✻ 375 Montreal

**80 days. The Famous Canadian Large Melon**

(Green flesh.) This celebrated melon is in universal esteem. It is of large size and delicious, melting flavor. The skin is green and the flesh is light green in color. The shape and markings are shown in the engraving. A weight of 20 to 25 pounds is not rare, and a weight of 39½ pounds is on record. The vine is prolific; fruit matures in 80 days. This is the melon that commands such high prices on the Eastern market in the late fall months; is a good shipper. The best seed comes from the neighborhood of Montreal, and our stock is the true Canadian.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

## 358 Fordhook

**70 days. An Orange Fleshed Large Jenny Lind**

(Orange flesh.) This melon resembles the Prize Jenny Lind in shape. The vine is a strong, vigorous grower, branching freely and frequently setting five to nine melons close to the hill. The melons grow very even and regular in size and attractive in appearance, slightly flattened at both stem and blossom ends. They are roughly netted. The flesh is very thick, color an attractive deep orange and of a delicious flavor. Matures in 70 days medium sized melons which are excellent for both home and market.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

## 377 Large Hackensack

**75 days. The Famous and Noted Turk's Cap Melon**

(Green flesh.) Fruits very large, weighing from 5 to 6 pounds each, flattened at the ends and well ribbed. The skin is deeply netted. The flesh is green, inclining toward yellow at the center, and of delicious flavor. Maturing large, luscious melons in 75 days. Excellent for the home garden.

**Packet 5 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**



## ✻ 361 Salmon Tinted Eden Gem

**70 days. Also known as Pollock's 10-25 Salmon Pink**

(Salmon tinted.) This muskmelon is considered one of the best of the Rocky Fords. Is the most reliable and best cropper, thriving on most any soil, producing ripe melons in about 70 days. The fruits are of great uniformity in size and shape, with gray netting, closely laced and covering the entire surface. The rich salmon tinted flesh is very deep, solid, of a luscious, sweet flavor and ripens clear to the rind.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 40 cts.; ½ pound 65 cts.; pound $1.15; 5 pounds $5.00, postpaid**

## 378 Honey Dew Melon Orange Flesh

**120 days. The Famous Long Keeping Melon; Sweetest Melon Grown**

(Orange flesh.) New type of melon, cross between cantaloupe and a Casaba. The fruit is oval-shaped, about 6 inches in diameter and 7 to 8 inches long, weighing from 8 to 10 pounds each. It ripens in about 120 days. The skin is smooth, dull white when ripe. The rind is thin but tough. The honey flavored flesh is thick, of rich, orange color.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 50 cts.; ½ pound 85 cts.; pound $1.50; 5 pounds $6.50, postpaid**



## ✻ 380 Honey Dew Melon Green Flesh

**120 days. Melons Sell at Fabulous Prices in All Markets**

(Green flesh.) Honey Dew is a new type of muskmelon, which grows uniform in size, about 6 inches in diameter from top to bottom and 7 or 8 inches long. The color is a dull white when ripe, having no netting, The rind, though thin, is very tough and so close that the excellent flesh is practically sealed up where it keeps in fine condition for several weeks after they are ripe. The flesh is a rich green color, very sweet and possesses a delightful flavor.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 50 cts.; ½ pound 85 cts.; pound $1.50; 5 pounds $6.50, postpaid**

## 385 Melon Peach or Mango Melon 80 Days. For Preserves or Pickles

Cultivate the same as muskmelon, but used only for mangoes, preserving, pies or pickling. The fruit has the size, shape and golden yellow color of an orange. The flesh is snow white, and makes excellent preserves.

Receipes for cooking are sent with every order.

**Packet 10 cts.; ounce 25 cts.; ¼ pound 65 cts.; ½ pound $1.10; pound $2.00, postpaid**

# ✱ 371 Maule's Perfection Muskmelon

371 Maule's Perfection Muskmelon

**75 days. The most delicious of all large melons. Weigh 8 to 10 pounds each, and attracts attention anywhere. Flesh from 2 to 3 inches in thickness, and in shape and general appearance it resembles the large French melons sold on the fruit stands at 50 cts. to $1.00 each.**

(Salmon flesh.) The shape of this melon is well shown in the illustration herewith; color of skin is a deep rich green, well ribbed and thickly netted, while the flesh is a rich salmon. The melon is nearly all flesh, the interior being very small, hardly large enough to accommodate the seed. In flavor it is simply unexcelled, and it certainly justifies its name, given by us in 1884, by its past experience and real merit. It is so thick fleshed that one melon is enough for two or three people under ordinary circumstances, and in a patch of an acre or more you can find hundreds of melons that very closely resemble the large French melons sold on fruit stands. Matures in 75 days. For the home garden or near market trade it is unsurpassed.

**Packet 10 cts.; ounce 25 cts.; ¼ pound 65 cts.; ½ pound $1.10; pound $2.00; 5 pounds $8.75, postpaid**



350 Lake Champlain Muskmelon

# ✱ 350 Lake Champlain Muskmelon

**57 days. The Earliest Orange Flesh Melon to Ripen**

(Orange flesh.) This new, very early maturing Muskmelon is of the Emerald Gem type but ripens much earlier, producing almost round, medium size melons, well netted, moderately ribbed, thick fleshed, sweet and melting of golden yellow color. The plants are very hardy and vigorous, setting and ripening melons in any of the Northern States. It is a sure cropper, producing nice size melons in 57 days and does well in all sections. An excellent home garden and market sort. Seed we offer is grown for us from the originator's stock.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 60 cts.; ½ pound $1.00; pound $1.75; 5 pounds $7.50, postpaid**

# ✱ 348 Maule's Gold Coin

**70 days. The Sweetest of the Salmon-Fleshed Sorts**

(Salmon flesh.) Maule's Gold Coin is larger, and a great deal more netted, of lighter skin, wider ribbed, of deeper flesh and better quality than Osage. It also yields twice as many melons to the acre. The specimens run from round to oblong, often both on the same vine. Maule's Gold Coin equals the Emerald Gem in quality, but a better shipper. Excellent for both the home garden and for market.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

## 372 Extra Early Hackensack

**65 days. The Earliest Large Melon**

(Green flesh.) In shape and color it is similar to Hackensack. Matures earlier, in about 65 days. It is a round melon, flattened on the ends and well ribbed. The skin is netted, and the green flesh is rich and sugary.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 40 cts.; ½ pound 65 cts.; pound $1.15; 5 pounds $5.00, postpaid**

## 373 Emerald Gem

**70 days. Splendid Size, Color and Flavor. A Melon That Can Be Grown in Any Garden**

(Salmon flesh.) This beautiful melon matures in 70 days. It is truly a gem. The ribs are marked, but the skin is smooth, of a deep emerald green color. The flesh is thick and firm, ripening almost to the rind.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 40 cts.; ½ pound 65 cts.; pound $1.15; 5 pounds $5.00, postpaid**

## 374 Osage or Miller's Cream

**75 days. Does Well on Heavy Soils**

(Salmon flesh.) Of medium size, nearly round, with skin ribbed and somewhat netted. Flesh salmon colored, of luscious flavor. Prolific bearer. Seed cavity very small. Matures its handsome distinct melons in 75 days. A good keeper and an excellent shipper.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**

# ✱ 362 Extra Early Knight or Maryland

**70 days. A Splendid Melon for All Purposes**

(Green flesh.) An extremely early melon and is especially valued on that account. The melons are oval in shape, regular in size and form, well covered with a close gray netting and distinctly ribbed. The skin is of light golden hue when fully ripened, flesh fairly thick and very sweet and ripens close to the skin. Color medium green blending to light pink near the center. Matures in 70 days. An excellent high quality melon for the home garden, nearby market or for long, distant shipping.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 90 cts.; 5 pounds $3.75, postpaid**

## 360 Golden Beauty Casaba

**120 days. The Great Christmas Melon, Often Called Water Muskmelon**

(White flesh.) It is extensively grown throughout the Southwest for shipping to our Eastern markets, and sold at very high prices during the fall. Matures in 120 days. The melons are nearly globular in shape, bright yellow with golden tint and wrinkled skin. Measures 6 to 8 inches in diameter. Flesh is white, thick, and of delicious flavor.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 60 cts.; ½ pound 85 cts.; pound $1.50; 5 pounds $6.25, postpaid**

362 Extra Early Knight or Maryland Muskmelon

# MAULE'S SUPERIOR WATERMELONS

CULTURE.—Watermelons do best on light, well drained soils, but there are varieties adapted to heavy loams. The hills should be 8 feet apart each way, with some well rotted manure in each hill, thoroughly incorporated with the soil. Plant the seed as soon as the weather is really warm and settled. A packet will plant about 10 hills, an ounce about 30 hills; 3 or 4 pounds of seed to the acre. Allow two or three plants to remain in each hill. Watermelons are ready to use in 60 to 90 days. Citron Melons are ready in about 100 days.

## ✻ 387 Maule's Panmure All-Heart Watermelon

**80 days. The Sweetest of All. Exceedingly Productive**

Here we have an entirely distinct variety that is sure to excite the admiration of all lovers of fine Watermelons. It is not only of superb flavor, but is all its name implies. Solid as a cannon ball, and while it has a thin rind, the skin is firm, consequently making it a good shipper. Seeds are about the same size as apple seeds, but notwithstanding this fact, the average weight of the melon is 30 to 40 pounds, maturing in 80 days. The uniform shape is well shown in illustration. All of our customers should plant some Maule's Panmure All-Heart this season.

**Packet 10 cts.; ounce 25 cts.; ¼ pound 70 cts.; ½ pound $1.10; Pound $2.00; 5 pounds $8.75, postpaid**

387 Maule's Panmure All-Heart Watermelon

## 396 Maule's Improved Georgia Rattlesnake

**80 days. A Good, Sweet, Juicy, Old Time Melon**

The old Rattlesnake has always been regarded as a fine melon. Our improved strain is the result of careful selection. In quality and flavor it is not surpassed. It has a thin, tough rind, which makes it a good shipper. Flesh deep scarlet, sweet and delicious; shape oblong, striped and mottled with various shades of green, maturing in 80 days. Improved Georgia Rattlesnake is largely grown in all sections.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 20 cts.; ½ pound 35 cts.; pound 60 cts.; 5 pounds $2.50, postpaid**

## 412 Phinney's Early

**70 days. Extremely Early. A Melon Anyone Can Grow**

The finest of all the early maturing melons of medium size and oblong shape, marked with two shades of green. The rind is thin. The red flesh is very sweet and tender. The vine is productive and a sure cropper, maturing in 70 days. Adapted to all sections and soils, and does exceptionally well in the Northern States.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 25 cts.; ½ pound 45 cts.; pound 75 cts.; 5 pounds $3.00, postpaid**



392 Thurmond Gray Watermelon

## ✻ 392 Thurmond Gray Watermelon

**85 days. A Distinct New Wilt-Resistant and Sunproof Melon. The Newest Long Distance Shipper**

This new Watermelon has made its appearance on the Northern markets this past year and is sure to become very popular. The strong healthy vines stand wet weather well and is a good producer. Its quality and attractiveness have made it an excellent market melon. In shape it is long and thick. The rind is of a rich, greenish gray color, making it hard to sunburn. Melons grow to a very large size. The flesh is bright red, finely flavored, solid and sweet. Matures in 85 days. An excellent home garden, market or long distance shipper.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**

## ✻ 393 Kleckley Sweet or Monte Cristo Watermelon

**80 days. Sweetest Flavored Large Melon**

One of the most popular, early, large watermelons grown. It is a high bred delicious melon originated in the South, and is especially celebrated for its fine flavor. It is a long, oblong shaped watermelon, averaging 18 to 20 inches in length by 10 to 12 inches in diameter, with a dark green rind. Of handsome appearance; ripens early. The flesh is scarlet, very firm, and of luscious quality and crisp texture. It is widely popular, and is one of the best family garden melons, or for nearby market it is a ready seller, but the rind is rather too tender for distant shipping. It gives satisfaction almost everywhere, and we can recommend it for use both North and South; matures in 80 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 90 cts.; 5 pounds $4.00, postpaid**



393 Kleckley Sweet or Monte Cristo Watermelon

# ✻ 397 Harris' Earliest Watermelon

**60 days. Sweetest Early Melon. Largest Early Melon. Best Early Melon for the Home Garden**

397 Harris' Earliest Watermelon

The general shape and appearance of the Harris are shown in the illustration. The skin is mottled with green and white. The flesh is red, sweet, juicy and crisp. The seeds are black. The weight varies all the way from 12 to 40 pounds, the average being 15 to 20 pounds. They average about 20 inches long and 12 inches thick, which is exceptionally large for so early a variety, maturing in 60 days. Its table quality is first class.

Owing to its extreme earliness, and adaptability to growing in heavy soils, it is extensively planted in the Northern States, where it is the undisputed favorite. We have known this melon to mature in latitudes as far north as Canada, and in places where watermelons never grew before.

The Harris is the earliest watermelon on the market; the sweetest early melon, the largest early melon and the best early melon for the home garden. These are sweeping statements, but they are true. Moreover, the Harris will out-yield any other early melon.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**

## ✻ 407 Irish Gray

**5 days. Also Called General Pershing. A Super Melon Equal to Kleckley Sweet**

This combination melon is equally as good for shipping as or home use and has attained great popularity on its merits. t is a melon you will like. The flesh is red, sweet, crisp and ree from stringiness. The thin but tough rind is a mottled reenish gray, entirely distinct. Vines are very vigorous, ealthy, and produce fine melons through a long season. Maures in 85 days. The melon worthy of a trial.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 90 cts.; 5 pounds $4.00, postpaid**

## 401 Angel's Kiss

**80 days. A Delicious Watermelon Novel and Attractive**

Angel's Kiss originated with one of the largest Southern elon growers. It is a handsome melon of large oblong shape. he flesh is bright red, solid, firm and of melting flavor. The ine is a remarkably strong, vigorous grower and a heavy earer of large mottled, silver gray melons with very tough hin rind. The melons measure from 20 to 30 inches in length, vith an average weight of from 30 to 40 pounds each, ripening hrough and through and is one of the best melons in culti- ation, maturing in 80 days. The seed is pure white.

**acket 10 cts.; ounce 15 cts.; ¼ pound 25 cts.; ½ pound 45 cts.; pound 75 cts.; 5 pounds $3.00, postpaid**

## 408 Peerless or Ice Cream

**85 days. Always Good; Excellent for the Home Garden**

A watermelon which we strongly recommend for home arket or garden culture. Of good size. Color mottled green. lesh rich scarlet and sweet; rind thin. Vine is very pro- uctive. Matures in 85 days. Being thin in the rind, it is ot so well adapted for shipping.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 25 cts.; ½ pound 45 cts.; pound 75 cts.; 5 pounds $3.00, postpaid**



## ✻ 388 Wonderful Sugar or McIver

**85 days. Always Sweet and Delicious**

This widely famous watermelon is, we believe, the sweetest ever put before the people of this country. It is of medium size, with striped or variegated exterior, beautiful red flesh, and light colored or white seeds. The flesh is entirely stringless, and of perfect quality as to texture. The vines are strong, thrifty and prolific, and well adapted to withstand either wet weather or drought. **We introduced it to the American public** in our 1894 catalog. Since that time it has been tried by many thousands of our customers, both North and South, and unlimited praise is given to it. Matures in 85 days. It is well adapted to nearby markets. An excellent home garden melon.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 20 cts.; ½ pound 35 cts.; pound 60 cts.; 5 pounds $2.50, postpaid**

391 Burpee's Fordhook Early Watermelon

## ✻ 391 Burpee's Fordhook Early

**60 days. An Extra Early Large Melon; Does Well Anywhere**

One of the largest of the extra early varieties, maturing in about 60 days. Shape nearly round. Color a medium shade of green. Flesh bright red, and of deliciously sweet flavor. The rind is sufficiently hard to make it a good shipper. Does well if grown in heavy soils. A sure cropper on light soils.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**

## ✻ 398 Maule's National

**80 days. The Melon for Everybody. Always Sweet**

Maule's National is a watermelon of medium to large size and of high table quality. In shape it is oblong. The outside color is pale green, with darker green markings. The flesh is brilliant red in color, and remarkably solid. The flavor is delicious, and the flesh entirely stringless. The rind, though thin, is tough, insuring good shipping qualities. National produces large melons, often weighing 40 pounds and over in 80 days. Its handsome appearance makes it a rapid seller, and for the home garden it has no equal.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 25 cts.; ½ pound 45 cts.; pound 75 cts.; 5 pounds $3.00, postpaid**

## ✻ 409 Golden Sweet Watermelon

409 Golden Sweet Watermelon

**85 days. Yellow Fleshed, Sweet, Cris and Delicious**

A large melon with yellow flesh tha fairly melts in the mouth, and which fc its fine sugary, juicy and delicious flavc cannot be surpassed by any red flesh sor The outside skin is dark green, stripe darker green, grows oblong in shape, ma turing its large size melons in 85 day The rind is thin but hard, and the color c flesh a golden yellow, solid, crisp, smoot of delicious sweetness. For table use it equally as good as any of the red fles varieties, and is extensively planted. It tempting, melting flavor, has made it on of the most popular watermelons of ou list for the home gardener.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**

## ✻ 389 Excel

**85 days. Of Enormous Size and Excels All Others for Home Use or Shipping**

The large oblong melons are of a dark green color with faint stripes. The tough rind permits handling in transit, making it a good long distance shipper. The red flesh is very solid, crisp and of excellent flavor. The vines produce an enormous crop in about 85 days. This melon has black seeds, also white with a black border.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 40 cts.; ½ pound 65 cts.; pound $1.10; 5 pounds $5.00, postpaid**

## 410 Shaker Blue

**90 days. One of the Best Large Round Melons for Home and Marke**

This is a large melon of handsome appearance. The rind i dark green striped with narrow bands of lighter green, bu when ready for shipping has a solid dark green appearance It grows to huge size, averaging when well grown from 40 t 50 pounds each. In addition to this it is a melon of deliciou flavor, and frequently produces melons in 90 days as large a 60 pounds each, its bright red flesh being of tempting appear ance. Excellent home or market sort.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 20 cts.; ½ pound 35 cts. pound 60 cts.; 5 pounds $2.50, postpaid**

## 414 Alabama Sweet

**80 days. The Favorite Melon Everywhere**

This splendid large melon, grown extensively in the South, is oblong in shape. The tough skin is very dark green with still darker stripes; flesh is dark red in color, fine grained, sweet and luscious, entirely free of stringiness. A first class shipper; under good cultivation they grow to a very large size, frequently weighing from 30 to 60 pounds, and commanding the very highest prices in the market. Makes a strong, healthy vine and is very productive; matures in 80 days. It is a favorite above all others in sections where it has been grown and has met with universal favor everywhere.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 25 cts.; ½ pound 45 cts.; pound 75 cts.; 5 pounds $3.00, postpaid**

## ✻ 411 Winter Watermelon

**95 days. The Luxury Christmas Melon. Will Keep Four Months After Storing**

This new melon, known as the King and Queen watermelon is adapted to all sections of the country. It matures its melons late, usually in about 95 days. Producing melons very light in color with a suspicion of a stripe. Size 10 inches in diameter. Seed small shiny black. Flesh pink. Solid and stringless. The flavor is sweet, crisp and surprisingly delicious. This melon should not be eaten right off the vine but be allowed to ripen slowly after being picked. They will keep until wanted or as late as Christmas. Melons stored four months remain in excellent condition.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts. pound $1.00; 5 pounds $4.25, postpaid**

## 418 Mixed Watermelons

**60 to 95 days. A Great Assortment for the Home Garden**

All different sorts in a grand mixture, producing melons of different shapes maturing in 60 to 95 days, and all of a delicious flavor. Everyone is sure to get a melon to suit their taste.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00, postpaid**

## 420 Colorado Preserving Citron

**100 days. For Preserving or Sweet Pickles**

A productive citron melon producing medium sized round fruit, with white flesh, which is very solid; used exclusively for preserving or pickling. The rind is dark green, distinctly striped with light green. Seed red; matures in 100 days. The fruit will keep in good condition for some time after picking and can be used when wanted.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 90 cts.; 5 pounds $4.00, postpaid**

## ✻ 413 Halbert Honey

**85 days. Most Deliciously Flavored Large Melon**

413 Halbert Honey Watermelon

This melon is as handsome in color as the Kleckley Sweets, but more regular in form and much more productive. The melons, blunt both at stem and blosson end, are generally free from any appear ance of neck. They average 18 to 20 inches in length; 6 to 8 inches in diameter. Color of rind a clear, glossy, deep green. The flesh is a beautiful crimson extending to within less than half an inch of the rind, maturing in 85 days. Excellent melon for the home garden and for local markets.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 25 cts.; ½ pound 45 cts.; pound 75 cts.; 5 pounds $3.00, postpaid**

# * 404 Maule's Improved Kleckley Sweet Watermelon

404 Maule's Improved Kleckley Sweet Watermelon

**80 days. A New and Improved Type, a Reliable Long Distance Shipper**

This Improved Strain of Kleckley Sweet Watermelon is now so thoroughly fixed as to perfect a new type of this favorite sort. Producing uniformly large melons in 80 days, retaining all of the fine qualities as a table sort, with an important added feature of having much harder rind, which assures its satisfactory carrying quality. While the old type will not stand even short distance shipping in carloads. The seeds are all creamy white. Flesh, scarlet, very firm, of superb flavor and crisp texture. Color of rind remains the same dark bluish green and grows to a much larger size than the old type. A desirable home garden, market or shipping sort. We offer the genuine Improved Kleckley Sweet Watermelon, Originators stock.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

## 403 Florida Favorite

**80 days. A Reliable Keeper. An Excellent Shipper**

This variety originated with one of the most extensive melon growers of Florida. A beautiful melon, with dark and light green exterior; shape oblong; flesh bright crimson, crisp and deliciously sweet. Ripens large, handsome melons in about 80 days. A good shipper. Sample specimens of this melon sent us from Florida always reach Philadelphia in prime condition. A great favorite with our customers.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 85 cts.; 5 pounds $3.50, postpaid**

## 399 Sugar Stick 80 days. Sweet and Delicious

A long, grayish or light green melon of handsome appearance. The strong vines are of vigorous growth, producing numerous large melons often measuring 2 feet in length and weighing 30 pounds each. This melon has a thin rind which is very tough, making it a good keeper and an excellent shipper. The luscious flesh, which is a deep, rich red, is very crisp and sugary, maturing in 80 days. Sugar Stick is desirable either for the home garden or market.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 85 cts.; 5 pounds $3.50, postpaid**

## 419 Apple Pie Citron Melon

**100 days. Excellent for Pies, Preserving, Etc.**

This citron melon has fruit very similar to the watermelon, but the flesh is used exclusively for sauces, pies, preserving, etc., having a most delicious flavor, resembling somewhat the flavor of apples. The flesh is white and solid. Each vine produces 5 to 15 large size melons in 100 days. One will make as many pies as a half bushel of apples. They keep fresh and solid all winter, so can be used when wanted.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**

**Our 50 Years in the Seed Business Is Your Guarantee of Satisfaction**

**You Absolutely Run No Risk When You Order of Maule**

## 394 Gray Monarch or Long White Icing

**80 days. Known for Its Fine Shape, Large Size and Sweetness**

The exterior color of this fine melon is a light green, though its mottled markings make it appear gray. The flesh is deep red in color, and of fine quality. Matures in 80 days. Specimens of Gray Monarch weighing 60 to 70 pounds have been produced. It has become widely popular in the home garden and nearby market.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 25 cts.; ½ pound 45 cts.; pound 75 cts.; 5 pounds $3.00, postpaid**

## * 416 New Perfection

**A Great and Important New Watermelon**

This wonderful new watermelon combines the qualities of a good shipper with lusciousness.

Perfection grows to enormous size, the fruits weighing from 50 to 75 pounds. The rind is a glossy dark green, thin, but unusually tough, so that it makes a good shipping variety. The flesh is of a dark red color. It is sweet and free from fiber or strings, yet of firm texture.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 40 cts.; ½ pound 65 cts.; pound $1.15; 5 pounds $5.00, postpaid**

## * 395 Tom Watson 85 days. The Most Popular of All Melons for Shipping

395 Tom Watson Watermelon

This melon was an instantaneous success in some of the very best watermelon growing sections of the country. The illustration was taken from a large melon sent into our office. It is an average specimen of the stock from which our seed is saved; it weighed 36 pounds. Tom Watson is a long, dark, mottled green melon, which at times grows exceptionally large, often weighing from 60 to 70 pounds, but at the same time one of the most prolific melons in cultivation. Although the rind is thin it is very tough, making it a most excellent shipper for long distances. The flesh is of most superb quality and intense red in color; matures in 85 days. A desirable melon for both market and home use.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 85 cts.; 5 pounds $3.50, postpaid**

## 69B64 Garlic Sets

69B64 Garlic Sets

150 days. Used for Flavoring

A bulbous root of the onion type, having a strong, penetrating odor and flavor, esteemed for flavoring soups, stews, etc. Ready to use in 150 days.

CULTURE—The bulbs (sets) are composed of several parts, which should be divided and planted in rows 1 to 3 feet apart, 6 inches apart in the rows and one inch deep. When the tops turn yellow take up and dry in the shade.

**½ lb. 25 cts.; lb. 40 cts.; 5 lbs. $1.50, postpaid**
**Not prepaid, 5 lbs. $1.00; 100 lbs. $15.00**

## Mustard Used as a Salad

CULTURE—Sow broadcast or in drills, 1 to 1½ feet apart, ½ inch deep. Thin out plants to 1 or 2 inches apart in the row. A packet will sow about 50 feet of drill; an ounce about 200 feet, 3 to 5 pounds in drills, or 25 pounds broadcast to the acre. Ready to use as salads in about 30 days.

### ✻ 421 Southern Giant Curled

**30 days. Very Curly; the Popular Sort**

Produces in 30 days large, dark green leaves with extra curled edges. Extensively grown in all sections.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 30 cts.; ½ pound 45 cts.; pound 75 cts.; 5 pounds $3.00, postpaid**

### 423 Burpee's Fordhook Fancy

**30 days. Finest of All, Curled Like an Ostrich Plume**

Dark green leaves, used as a salad. Matures in 30 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**



### ✻ 422 Elephant Ear or Large Smooth Leaf

**30 days. Very Quick Grower; Plain Leaf Sort**

This variety produces in 30 days large leaves of a light green color. A single plant will produce sufficient leaves for a mess of greens. Very popular in the South.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 85 cts.; 5 pounds $3.50, postpaid**

## 69B68 Mushroom Spawn

CULTURE—One brick of spawn is sufficient for 8 square feet of prepared bed. Special cultural hints sent with every order.

**Pure Culture Brand.** By a newly discovered process of selection and grafting, the spawn is scientifically propagated so that large, vigorous and finely flavored mushrooms are reproduced. The sort we offer is the earliest strain.



69B68 Mushroom Spawn

**Brick** (about 1¼ lbs.) **50 cts.; 5 bricks $2.25, postpaid**
**Not prepaid, 5 bricks $1.25; 10 bricks $2.25; 25 bricks $5.50**

### Order by Number or Name

**When ordering all Seeds and Collections order by Number or Name, if by Number only be sure to give Correct Number.**

## Okra or Gumbo

**Green Pods Impart a Rich Flavor When Used in Soups, Stews, Etc**

A fashionable Southern vegetable of easy growth in the North. The pods are used when young and tender as a separate dish or in soups and stews.

CULTURE—Sow in May and June, after the ground is warm, in drills three feet apart, cover the seed with about 1 inch of soil, and thin to 12 to 18 inches apart in the rows. Use a packet to about 25 feet of drill; an ounce to about 100 feet; 8 pounds to an acre. Ready to use in 50 to 60 days.

### 431 Perkin's Perfected Long Pod

**60 days. Long, Dark Green Giant Pods**

Large okra, esteemed by canners and market gardeners. It is a great improvement on the old green podded sorts. Large, handsome green pods. Fine quality, very productive, 4 to 5 feet tall. Matures its giant green pods in 60 days.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 25 cts.; ½ pound 40 cts.; pound 75 cts.; 5 pounds $3.25, postpaid**

### 434 White Velvet

**55 Days. Early and Productive, Light Green Pods**

Pods are round and smooth, while in other sorts the pods are ridged or square edged. Superior flavor and tenderness. It is very productive, producing its smooth light green pods in 55 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 25 cts.; ½ pound 40 cts.; pound 75 cts.; 5 pounds $3.25, postpaid**

### ✻ 433 Dwarf Georgia Favorite

**50 days. Low Growing with Giant Dark Green Pods**

A giant podded dwarf okra, producing in 50 days an abundant crop of long, dark green pods, which are twice the length of the common varieties. Grows about 2 feet high, and produces pods a few inches from the ground to the top of the plant. The pods last long in prime condition, and are borne in great profusion all summer.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**

Sow MAULE'S SEEDS—There are NONE BETTER

# Maule's Select Onion Seeds

CULTURE—Onions do best on a rich loam, previously cultivated for two years. The land should be highly fertilized with well-rotted manure, complete fertilizers, etc. Fresh stable manure has a tendency to produce soft onions. For dry (or fall) onions a packet will sow about 50 feet of drill, an ounce about 300 feet, 4 to 5 lbs. of seed per acre. Sow in drills 2 to 18 inches apart as early in spring as possible and cover one-half inch deep. When large enough thin to 3 inches apart. If sets are wanted, sow seed thickly and don't thin out; use 60 to 80 lbs. of seed per acre. Fine marketable size onions (according to variety planted) are easily produced the first year from early spring sown seed, maturing in from 65 to 120 days.

## ✻ 441 MAULE'S PRIZETAKER ONION

441 Maule's Prizetaker Onion

**100 days. A Large, Productive, Sweet, Attractive, Mild Flavored Yellow Globe Onion**

We named and introduced this great onion in 1888, and ever since have given it special prominence in every catalog we have issued. Today, thirty-nine years after it was named by us, it will be found in almost every seedsman's catalog.

Prizetaker is by far the handsomest, most productive, most popular and best of all large yellow globe onions. It is a bright, clear straw color, and always grows to a uniform shape, which is a perfect globe. It has a very small neck and ripens up firm and solid. In market it never fails to attract attention on account of its beauty, and is sure to bring a better price than any other onion. Maule's Prizetaker has attracted more attention and awakened wider and more cordial enthusiasm than any other onion ever introduced to the American public. It is one of the largest, finest flavored yellow globe onions for either the home garden or market. Matures in 100 days.

**Packet 10 cts.; ounce 30 cts.; ¼ pound 75 cts.; ½ lb. $1.35; lb. $2.50; 5 lbs. $11.25, postpaid**

**ORDER YOUR SEEDS**
**now or as soon as possible after receiving this book**

## ✻ 451 Ebenezer or Japanese

**100 days. An Enormous Cropper, Mild Flavored, and a Good Keeper**

This desirable yellow skin, early maturing onion has created a tremendous demand by growers of large onions, as well as onion set growers in all sections. The flesh is white, firm, and of a very delicious flavor; in fact it is the mildest flavored onion grown. The handsome onions are large, somewhat flattened in shape, yellow skinned, with very small tops, maturing in 100 days. Keeps in good, hard and sound condition all winter. Anyone wanting a nice mild onion for their table, should plant Ebenezer.

**Packet 10 cts.; ounce 40 cts.; ¼ pound $1.10; ½ pound $2.15; pound $4.00; 5 pounds $18.50, postpaid**

## 470 Mixed Onions

**65 to 120 days** *All Shapes and Colors*

This mixture contains a grand assortment of the different colored and various shaped onions, maturing at intervals in 60 to 120 days, so as to give a supply of onions fit for the table when wanted, or for saving for winter use.

**Packet 5 cts.; ounce 25 cts.; ¼ pound 75 cts.; ½ pound $1.35; pound $2.50, postpaid**

## Maule's Collection of Three Best Southport Globe Onions

**Red, White and Yellow**

*3167* **COLLECTION. One packet each of the 3 sorts for 25 cents, postpaid.**
*3169* **COLLECTION. One ounce each of the 3 sorts for 75 cents, postpaid.**

## ✻ 444 Southport Red Globe Onion

**120 days. The Standard Red Globe Onion. An Enormous Yielder**

In districts in New York and Ohio, we frequently ship 1,000 pounds of this red Globe onion annually. It is a perfect globe, skin being of a rich glossy red; flesh fine grained, white and always mild and pleasant, maturing in 120 days. It is very hardy and a splendid keeper and is known as the most popular red onion by all growers.

**Packet 10 cts.; ounce 30 cts.; ¼ pound 85 cts.; ½ pound $1.50; pound $2.75; 5 pounds $12.50, postpaid**

## ✻ 445 Southport White Globe Onion

**120 days. The Handsomest and Best Winter Keeping White Onion**

This onion, on account of its handsome appearance, always brings top prices in the city markets. It is silvery white in color, globe shaped in form, flesh of delicious flavor, and a fine keeper. This main crop variety is excellent for the home garden or for onion growers wanting fancy stock; matures in 120 days.

**Packet 10 cts.; ounce 40 cts.; ¼ pound $1.10; ½ pound $2.15; pound $4.00; 5 pounds $18.75, postpaid**

## ✻ 446 Southport Yellow Globe Onion

**120 days. A Sure Cropper and Long Keeping Onion for Home or Market**

One of the most popular of the Yellow Globe onions, and our annual sales run into thousands of pounds. Perfectly globe shaped with rather full shoulder, rich yellow skin, fine grained, mild creamy white flesh. Very productive and a good keeper. The most largely grown yellow market onion and the most profitable; matures in 110 days.

**Packet 10 cts.; ounce 30 cts.; ¼ pound 75 cts.; ½ pound $1.35; pound $2.50; 5 pounds $11.25, postpaid**

446 Southport Yellow Globe Onion

## ✱ 461 Maule's Mammoth Silver King

**85 days. Earliest Giant White, Mild Onion**

We introduced this grand onion to the public over 46 years ago. The skin is a beautiful, silvery white. The flesh is so sweet that it may be eaten raw like an apple. No other white onion attains such mammoth size. The bulbs are of an attractive shape, flattened, but thick, as shown in the illustration. The average diameter of fully grown Mammoth Silver King onions is from 5 to 7½ inches. We have a record of one of these onions weighing 4 pounds and 9 ounces. Matures its crop of large size white onions in about 85 days. An excellent keeper.

**Packet 10 cts.; ounce 35 cts.; ¼ pound 90 cts.; ½ pound $1.65; pound $3.00; 5 pounds $12.50, postpaid**

461 Maule's Mammoth Silver King Onion

450 Maule's Selected Australian Brown Onion

## ✱ 456 Silver Skin or White Portugal

**95 days. The Favorite Mild White Onion**

A mild and pleasant onion, of somewhat flattened shape. It is very popular for family use and one of the best for pickling, also for slicing or boiling. A favorite with many when young as a salad or bunching onion; excellent for winter. This variety is largely grown for sets, and is regarded as a standard sort on account of it being hard and firm, maturing in 95 days. Excellent variety to plant in August for early spring "green" or bunching onions.

**Packet 10 cts.; ounce 40 cts.; ¼ pound $1.00; ½ pound $1.85; pound $3.50; 5 pounds $16.25, postpaid**

## ✱ 450 Maule's Selected Australian Brown

**95 days. Remarkable for Its Uniform Size and Keeping Quality**

The handsome onions are extremely hardy, yielding an enormous crop, both in weight and bulk. The skin is thick and of a beautiful rich brownish red color. The flesh is always white, extremely solid, sweet and mild in flavor. Its keeping qualities are phenomenal. A desirable onion for the home garden as well as for market. Matures in 95 days.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 60 cts.; ½ pound $1.00; pound $1.75; 5 pounds $7.50, postpaid**

## ✱ 437 Maule's Yellow Globe Danvers

**115 days. The Old Reliable Yellow Globe Onion**

Our strain of Yellow Globe Danvers onion is unsurpassed. It always attains a good size, with deep bulb and small neck. It is choice in flavor, being rather mild and is invariably a market favorite at prices above average quotations. It frequently produces 600 bushels per acre, and capable of doing even better under extra culture. Matures in 115 days; a splendid keeper. Our strain of Yellow Globe Danvers has been famous for the past quarter century in every onion growing district. In the Southern States they can be planted in Autumn and will continue growing the entire Winter.

**Packet 10 cts.; ounce 30 cts.; ¼ pound 75 cts.; ½ pound $1.35; pound $2.50; 5 pounds $11.25, postpaid**



437 Maule's Yellow Globe Danvers Onion

## ✱ 436 Maule's Large Red Wethersfield

**120 days. Sure and Heavy Yielder—Very Popular**

This has been one of our leading specialties for more than thirty-seven years. The skin is deep purplish red. The flesh is white, tinged with pink. Onion seed value depends greatly upon the way the stock is selected and cared for, and the seed which we offer is of the earliest form, grown from hand sorted bulbs and sure to produce large onions. Specimens of Maule's Large Red Wethersfield grow to an immense size in about 120 days. They are solid, oval shaped flattened on top, strong flavored and excellent keepers. Many strains of Red Wethersfield are offered the American public, but our careful comparative tests convince us that none surpass the one here described. It is in every way a perfect red onion for home and market purposes.

**Packet 10 cts.; ounce 25 cts.; ¼ pound 70 cts.; ½ pound $1.25; pound $2.25; 5 pounds $10.00, postpaid**

# * 439 Maule's Large Sweet Spanish Onion

439 Maule's Large Sweet Spanish Onion

**110 days. The Sweetest, Largest, Light Yellow Colored Globe Shaped Onion Grown**

**Very Large Onions Are Produced from Seed Sown in Your Garden**

This new large onion is one of the best all-round sorts. It is a world-beater for size, sweetness and shipping qualities. Maule's Large Sweet Spanish produces extra large light yellow colored globe shape onions in 110 days. The pure white flesh is fine grained and exceptionally sweet. Its sweetness makes it a splendid sort to use in salads or other ways without cooking. A good keeper for so early and large variety. An excellent home garden, market or shipping onion.

**Packet 15 cts.; ounce 60 cts.; ¼ pound $1.65; ½ pound $3.15; pound $6.00; 5 pounds $27.50, postpaid**

## 442 White Welsh Onion

**100 days. The Hardy Salad or Bunching Onion**

The best kind for green onions; it forms no bulbs. A very hardy, perennial variety of onions used only for bunching or for early green onions. The pearly white shoots are mild in flavor. They attain marketable size very quickly and sell at top prices before the green onions grown from sets are brought to the market. Much superior to the Egyptian onion. Seed may be sown in the early Spring, but not later than the latter part of July for early Spring onions; further south as late as September. Market gardeners will find the White Welsh Onion an exceedingly profitable crop.

**Packet 10 cts.; ounce 25 cts.; ¼ pound 70 cts.; ½ pound $1.25; pound $2.25; 5 pounds $10.00, postpaid**



442 White Welsh Onion

## 443 Maule's Commercial Yellow Globe

**100 days. Perfect Globe Shape. Large, Mild Flavored**

Maule's Commercial onion has been selected from our original Prizetaker and has been bred to a size that is more merchantable. Our efforts have been rewarded by securing an onion fully as handsome as the Prizetaker in every way; of more uniform size, and whose keeping qualities are simply remarkable and decidedly superior to the parent variety. Six to eight hundred bushels per acre have been no unusual yield, and this quantity has been frequently surpassed.

**Packet 10 cts.; ounce 30 cts.; ¼ pound 75 cts.; ½ pound $1.35; pound $2.50; 5 pounds $11.25, postpaid**

## 466 Extra Early Pearl

**70 days. The Earliest Large White Onion**

Of mild flavor and a good keeper. Sometimes grows 5 to 6 inches in diameter, maturing in 70 days. A very attractive early onion for the home garden or market.

**Packet 10 cts.; ounce 30 cts.; ¼ pound 85 cts.; ½ pound $1.50; pound $2.75; 5 pounds $12.50, postpaid**

## 463 White Barletta

**65 days. Earliest and Smallest for Pickles**

Producing onions 1¼ to 1½ inches in diameter, flattened on top, ready to use in 65 days. Color, beautiful waxy white. A good keeper; excellent for pickling.

**Packet 10 cts.; ounce 30 cts.; ¼ pound 85 cts.; ½ pound $1.50; pound $2.75; 5 pounds $12.50, postpaid**

# Maule's Best Quality Onion Sets

**60 to 75 days. Produced from Thoroughbred Seed and True to Name. We Sell All Onion Sets 32 Pounds to the Bushel**

CULTURE—Onion sets should be planted as early in the spring as the ground can be worked. Set the onions in the ground lightly (do not cover) in shallow furrows, 12 to 18 inches apart and about 2 inches apart in the row. Young onions may be had in 5 weeks. By planting sets, onions can be produced for market or household use 4 to 6 weeks earlier than can be had from seed. Onions from sets are usually harvested in the locality of Philadelphia in July, which allows the sowing of another crop on the same ground the same season. A quart of onion sets will plant a row about 100 feet long, use 8 to 10 bushels to an acre.

### 69B76 Ebenezer or "Japanese" Sets

This is a fine, popular variety, the large, mild onions being very slow in running to seed even in unfavorable seasons.

**Pint 25 cts.; quart 45 cts.; 5 quarts $2.00, postpaid Not prepaid, quart 35 cts; 4 quarts $1.00; peck $1.75; bushel $6.25**

### 69B78 White Multiplier or White Potato

Producing a cluster of large white skin onions. Flesh white and of mild flavor. Hardy, early and a good cropper. Of excellent quality and size for bunching. Crop very short; cannot offer in larger quantities.

**Pint 35 cts.; quart 60 cts.; 5 quarts $2.75, postpaid Not prepaid, quart 50 cts.; 4 quarts $1.75**

### 69B80 Yellow Potato or Yellow Multiplier

It is a large yellow skin onion, flesh white and mild in flavor, and a good cropper. Will produce either green bunching or large, dry ripe onions earlier than any other kind.

**Pint 30 cts.; quart 55 cts.; 5 quarts $2.50, postpaid Not prepaid, quart 45 cts.; 4 quarts $1.25; peck $2.00; bushel $7.50**

Onion Sets

### 69B70 Maule's Yellow Globe Danvers Sets

This is one of the best and most popular for raising early big yellow onions from sets.

**Pint 25 cts.; quart 40 cts.; 5 quarts $1.75, postpaid Not prepaid, quart 30 cts.; 4 quarts 85 cts.; peck $1.50; bushel $5.25**

### 69B72 Maule's White Silver Skin Sets

These sets will produce beautiful, silvery-white onions very early in the season. A favorite sort for home and market gardeners.

**Pint 25 cts.; quart 45 cts.; 5 quarts $2.00, postpaid Not prepaid, quart 35 cts.; 4 quarts $1.00; peck $1.75; bushel $6.25**

### 69B74 Maule's Red Wethersfield Sets

Very hardy; good keepers. One of the best red onions for all purposes.

**Pint 25 cts.; quart 40 cts.; 5 quarts $1.75, postpaid Not prepaid, quart 30 cts.; 4 quarts 85 cts.; peck $1.50; bushel $5.25**

The value of onion sets may vary, so all our prices are subject to change without notice.

**To hasten the maturity and increase the size of Onions, bend over the tops before ripening begins**

# PARSLEY

**Used for Flavoring and Garnishing**

CULTURE—Sow seed in shallow drills in the early spring in borders, or in rows 12 to 18 inches apart, care being taken that the drills be not more than ½ inch in depth, and that the seed be well pressed down after sowing, as the seed germinates very slowly, 3 to 5 weeks elapsing sometimes before it makes its appearance. Use a packet to 25 feet of drill; an ounce to 150 feet, 5 pounds to an acre. Ready to use in 65 to 100 days.

## 471 Champion Moss-Curled

70 days. Beautifully Crimped and Curled

A choice strain. Ready to use in 70 days.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**

## 472 Plain Parsley

75 days. Hardy Italian

Excellent for seasoning. Ready to cut in 75 days.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 25 cts.; ½ pound 45 cts.; pound 75 cts.; 5 pounds $3.25, postpaid**

## ✻ 474 Double Curled Parsley

65 days. Everybody's Favorite

The leaves are handsomely curled, dark green in color and of a very fine flavor. Fit to use in 65 days. Popular home garden or market sort.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**

## 475 Hamburg or Turnip-Rooted Parsley

**100 days. Large Edible Roots, Known as German Parsley**

The edible roots resemble a small parsnip, and it is esteemed for flavoring soups, stews, etc. Roots ready to use in 100 days.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**

474 Double Curled Parsley

Lend This Catalog to Your Neighbor

477 Maule's White Lisbon Parsnip

Maule's Seeds Once Grown Always Grown

# PARSNIPS

CULTURE—Sow in early spring, in rows 2 to 3 feet apart; thin to 4 to 6 inches in the row. packet will sow about 40 feet of drill, an ounce about 200 feet, 4 to 5 pounds per acre in drills 2 feet apart. Cover the seed ½ inch. Ready to use in 80 to 85 days or may be stored in the cell for winter use or left in the ground all winter and dug when weather permits, or leave in t ground for spring use.

## ✻ 477 Maule's White Lisbon

**85 days. Of Uniform Size and Shape**

A striking and attractive parsnip. The shape is well shown in illustration. It is remarkably free from side roots; in fact, in this respect it is about the cleanest of all parsnips. It is fine grained and of superior flavor, maturing in 85 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**

## ✻ 478 Maule's Improved Half Long

**80 days. Roots Smooth, Easy to Harvest**

The root is smooth, and the flesh fine grained and of excellent flavor. It is a heavy cropper. Being larger in diameter and shorter than the Long Smooth, it is harvested with less labor. Matures large roots in 80 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 85 cts.; 5 pounds $3.50, postpaid**

## 483 Maule's Improved Long Smooth

**85 days. Straight, Smooth and Handsome**

This is the same as Hollow Crown or Improved Long Suga A highly improved type producing uniformly large and han some roots of stocky form, heavy at the shoulder, we rounded, gradually tapering to the base. Flesh white, of fi texture, free from core and stringiness; fine flavored. Cool tender; sweet and rich; enormously productive and exce tionally smooth. Matures in 85 days.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 30 cts.; ½ pound 50 cts pound 85 cts.; 5 pounds $3.50, postpaid**

INOCULATE THIS SEED WITH MULFORD CULTURE

Produces a Crop in Any Section

# Peanuts

A Good Money Maker for the South

INOCULATE THIS SEED WITH MULFORD CULTURE

CULTURE—Select warm light or sandy soil rich in lime; if not rich in lime, the soil must be made so by using air slak lime or land plaster. Mark out rows 2½ to 3 feet apart, plant the shelled nuts in May or June, 8 to 10 inches apart in t rows, or if in the hulls 16 to 18 inches apart. Cover with 2 inches of soil; it is not necessary to remove the shucks or hu before planting. Cultivate and hoe freely, keeping the soil mellow around the plants. Matures in 110 to 120 days. In the f before frost, dig and hang them under a shed or in an airy room to cure. A packet will sow from 15 to 25 feet of row; a pou from 100 to 200 feet, according to variety and method planted. Use 35 or 40 pounds of seed per acre.

## ✻ 485 Improved Virginia Peanut

**120 days. The Popular Commercial Sort, Very Productive**

Early, large and prolific, yielding fewer imperfect pods than any other kind, and producing 100 bushels per acre on medium land. With 2 or 3 kernels to the pod; large and of rich flavor, maturing in 120 days. Vines average 3½ to 4 feet across, making valuable fodder for stock. This large podded sort is in great demand everywhere and is known as Jumbo Peanut. Excellent home garden or market sort.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.75, postpaid**

**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $20.00**

Large Size Kernels



True Bush Form

## ✻ 484 Mammoth Bush Peanut

**110 days. The Largest of All, a Heavy Cropper**

This peanut grows to an astonishing size, and does exceedingly w in the North. They make compact bushes 18 inches high, with hea erect stalks and large leaves. They are good producers, and of disti appearance. The giant nuts have a thick, heavily ribbed protecti shell, maturing in 110 days. On light sandy soil makes a good cr

**Packet 10 cts.; ½ pound 30 cts.; pound 50 cts.; 5 pounds $2.25, postpaid**

**Not prepaid, 5 lbs. or over at 35 cts. per lb.; 100 lbs. $30.**

INOCULATE THIS SEED WITH MULFORD CULTURE

# Maule's Garden Peas

INOCULATE THIS SEED WITH MULFORD CULTURE

CULTURE—Sow in earliest spring and make successional plantings every ten days until June 1. In the latter part of August sow early peas for an autumn crop. Drill 1 to 2 inches deep in rows 2½ to 4 feet apart. In the field use no sticks. In garden culture sow in double rows 10 inches apart, and use supports for the tall growing varieties. A packet will sow about 20 feet of drill; a pound to 100 feet; 90 to 120 pounds per acre.

## Extra Early Smooth, Round Seeded Varieties

**Sow as early in Spring as the ground can be worked: they are hardier than the wrinkled varieties. Ready to use in 41 to 50 days**



488 Maule's Earliest of All Pea

### ✱ 488 Maule's Earliest of All Peas

**41 days. Bright Green Peas of Excellent Flavor**

Maule's Earliest of All Pea has become the main reliance of thousands of truckers and gardeners who wish to be first in market with new peas. It is a smooth sort; maturing an abundance of pods in 41 days. It is absolutely unsurpassed in extra early qualities, in flavor, in size of pod and productiveness, in vigor and regularity of growth. Vines grow 30 inches high. Every seedsman claims to sell an "earliest" pea, but, after testing them all, we know that not one excels our own celebrated strain, either in quality, quantity or earliness. Maule's Earliest of All is very hardy, and may be sown as soon as the soil becomes mellow.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 23 cts. per lb.; 100 lbs. $20.00**

### 489 Early Morning Star

**45 days. A Prolific, Hardy, Early Smooth Seeded Sort**

This hardy early maturing pea produces a heavy crop of pods on vines growing 2 to 2½ feet high, which do not require any sticking, so prolific are the pods that they can be readily picked, filling the basket very quickly. The large size pods produce excellent peas which are sweet in flavor. This pea has become a leading favorite with market gardeners, as well as in the home garden, producing a crop in 45 days under favorable weather conditions.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 23 cts. per lb.; 100 lbs. $20.00**

### ✱ 529 Market Surprise

**50 days. A Giant Podded Extra Early Pea for Home Use or Market**

Market Surprise has become the popular extra early large podded sort, producing large pods in abundance which are filled with luscious green peas. The robust growing vines, which require no staking, grow 2½ feet high. The delicious sugary peas are ready for picking in about 50 days. The large pods, which contain eight to nine fine peas, are of rich green color. This is the pea that all progressive gardeners are looking for as it is very hardy, extremely early, large podded and a prolific bearer, making it a quick basket filler. The peas are of excellent flavor, sweet and delicious. A good all purpose pea.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 23 cts. per lb.; 100 lbs. $20.00**

529 Market Surprise

### ✱ 487 Early Bird

**45 days. The largest Podded Hardy Early Pea for the Market or Home Gardener**

A semi-wrinkled large podded dwarf variety that can be planted as soon as the ground can be worked. They do not rot in the ground like fully wrinkled peas. The dwarf vigorous vines measure 2 feet and carry enormous crops of large, beautiful deep green pods, 4 to 5 inches long, and are filled with 9 to 10 large blue marrow peas of fine flavor. Early Bird is a profitable variety for the market gardener. For the home gardener it is unsurpassed.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 27 cts. per lb.; 100 lbs. $24.00**

506 Maule's Radio Pea

### ✱ 506 Maule's Radio

**45 days. The Earliest Dwarf Extra Early Pea in Existence, Hardy and Prolific**

Maule's Radio is a smooth seeded pea, and the earliest dwarf sort in cultivation. Vines usually grow to a uniform height of from 12 to 15 inches, which allows closer planting than most other sorts, thereby yielding a greater quantity of peas from a comparatively small space of ground. The green pods are of medium size, well filled with peas of a most delicious flavor, an ideal kitchen garden sort. Ready to use in 45 days.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**

### 501 Alaska Peas

**45 days. A Popular Extra Early Green Seeded Smooth Sort**

An extra early sort, producing dark green colored pods, in 45 days, making it a desirable shipping variety as it will carry a long distance without losing its color. Vines grow 2½ feet high. A prolific bearer.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 20 cts. per lb.; 100 lbs. $18.00**

### 505 Maule's Improved Extra Early

**45 days. The Best Extra Early Smooth Pea for the Home Garden or Market**

This fine, smooth pea is surpassed in point of earliness only by Maule's Earliest of All. The handsome pods are ready to pick in 45 days. It requires no sticks. It grows about 2 feet high, is a sure cropper, and very productive. The pods are well filled with 5 to 7 medium sized peas.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 23 cts. per lb.; 100 lbs. $20.00**

### 508 Prolific Early Market

**50 days. The Most Productive Extra Early Garden Sort**

A smooth, white seeded extra early sort, with pods one-third larger on vines six inches taller than Maule's Improved Extra Early, maturing in 50 days, but of remarkable productiveness, giving a yield of 30 to 50 per cent more pods than any other strain of extra earlies of which we know.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 23 cts. per lb.; 100 lbs. $20.00**



487 Early Bird

# EXTRA EARLY DWARF WRINKLED GARDEN PEAS

**Should not be planted as early as the smooth, round seeded sorts. Wait until the weather becomes warm and settled. Ready for use in 48 to 55 days**



504 World Record

## ✻ 504 Maule's World Record Pea

**50 days. An Improved Type of Prosperity or Gradus, but Earlier**

This new and improved type of Prosperity or Gradus Pea is slightly earlier than that famous variety, and is the earliest of all the large podded vine sorts. The vines grow about 2 feet in height and are tremendously productive, requiring no brush or stakes, of a medium green color, producing large medium green pods fully 4 to 5 inches long, fairly broad, pointed and well filled with 7 to 9 very large dark green peas of exceptional quality. Matures in 50 days.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $23.00**

## ✻ 509 Laxtonian

**55 days. Known by Some as the Dwarf Gradus Early, Giant Podded**

This is the largest podded of all the early dwarf varieties and is a grand sort of decided merit. The vines are vigorous, growing about 16 inches high, and produce a large crop of good sized pods, averaging from 9 to 10 peas to the pod. The peas are of exquisite flavor, maturing in 55 days. Many people who have tried Laxtonian consider it superior to any of the so-called tall growing later maturing sorts, and claim it to be the best of all early dwarf peas.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 28 cts. per lb.; 100 lbs. $25.00**

## ✻ 494 Prosperity or Gradus

**55 days. An Early and Very Large Podded, Wrinkled Pea**

Prosperity or Gradus is a wrinkled pea, with vine growing about 30 inches high. It requires no sticks or brush, though sticks may be used if preferred. The peas are freely borne, and remain in good condition for a number of days. The pods are of a dark green color, and measure 4 inches or more in length, being as large as Telephone, and equally well filled with luscious peas—8 to 10 or more in a pod. The peas themselves are of first class table quality, and retain their color and attractive appearance after cooking.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**

## ✻ 496 Thomas Laxton

**55 days. One of the Largest Podded Dwarf Vine Sorts**

It grows like Gradus, about 30 inches high. The wrinkled peas are very large, of fine deep green color. The pods are large, long, with square ends and fine color. Many market gardeners have planted the Thomas Laxton in preference to Gradus, to their entire satisfaction. Our opinion of Thomas Laxton is that it is as early as Gradus, maturing in 55 days; at the same time it is, if anything, more productive; peas are fully as large, of a richer green color. Planted side by side, it is frequently a hard matter to tell which is the better of the two varieties.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**



509 Laxtonian

## 491 American Wonder

**48 days. Esteemed for Earliness**

American Wonder is one of the earliest of the wrinkled varieties. It is quite distinct from all other peas in habit of growth and appearance, of dwarf habit, with vines about a foot high. In favorable weather and soil it will mature in the remarkably short period of 48 days, but it is less hardy than Maule's Earliest of All, and must not be planted as soon.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**

**ORDER EARLY**

## 492 Nott's Excelsior

**55 days. Excellent for Home Garden**

One of the best dwarf wrinkled peas; hardy and vigorous, and will mature almost as soon as the smooth varieties. Frequently ready in 55 days. The pods are filled with 7 to 9 large peas. Of superior flavor. Height, 1 foot.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**

510 Little Marvel

## 493 Surprise

**50 days. The Earliest Pea of Quality**

This is one of the best wrinkled peas, producing an abundance of pods in 50 days, and is far superior in quality to any of the smooth early sorts. It ranks with the very earliest of the wrinkled sorts. The vine grows 20 to 24 inches high, and requires no sticks. Its sweetness is noteworthy, and it bears with remarkable profusion. Excellent home garden sort.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**

## ✻ 499 Burpee's Blue Bantam

**55 days. The Best First-Early Dwarf Wrinkled Pea**

Burpee's Blue Bantam is unequaled for its combination of extreme earliness, superb quality, and unusual productiveness. The dwarf, vigorous vines average 15 inches in height and carry really enormous crops of large, deep bluish green pods in 55 days. The pods measure 4 to 4½ inches long and are tightly packed with 8 to 10 large, deep bluish green peas. A desirable home garden sort.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 28 cts. per lb.; 100 lbs. $25.00**

## 500 Pioneer

**55 days. Giant Pods, with Large Luscious Peas**

This large dark green podded, early wrinkled pea is in great favor with market gardeners in all sections. The handsome large pods, which are well filled with big peas of delicious flavor, make it a good seller on the market stall. The vines are extremely vigorous, growing only 15 to 18 inches high, with dark green foliage, and produce a wonderful crop of pods. Pioneer is an early wrinkled pea, bearing its dark green pods in 55 days, as early as the Prosperity or Gradus, but a much heavier cropper and of quality equally as good.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 28 cts. per lb.; 100 lbs. $25.00**

## ✻ 510 Little Marvel

**52 days. A Marvel in Earliness and Productiveness**

A dwarf early pea of unusual value. The vines average 15 inches in height, and the pods 2½ inches in length, frequently borne in pairs. The pods contain from 6 to 7 large dark green peas which remain in good eatable shape a week later than most other varieties, maturing in 52 days, and is as early as Nott's Excelsior but produces a much larger pod, and the vines produce a much heavier crop. A desirable pea for home garden or market.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**



496 Thomas Laxtor

# Second Early or Main Crop

Plant these varieties at the same time as the extra early wrinkled sorts, they will bear when all others are done. All are giant podded sweet wrinkled varieties. Ready for use in 65 to 70 days.



503 Bliss Everbearing Pea

## 503 Bliss Everbearing

**65 days. A Continuous Long Season Bearer**

A celebrated wrinkled pea 2 to 2½ feet high, of good quality and flavor, maturing its pods in about 65 days, and is especially adapted to summer and autumn cropping. It has a remarkable and valuable branching habit. It will do well without sticks or brush. Repeated pickings may be made, for the vines continue to produce a successional crop of pods. It is a continuous bearer through a long season.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 23 cts. per lb.; 100 lbs. $20.00**

## 497 Dwarf Telephone

**65 days. Dwarf Vines, Large Green Pods. A Heavy Cropper**

Dwarf Telephone produces vines 2 feet high and are very productive. The green pods measure 5 inches in length, containing 10 large, luscious peas which fairly melt in your mouth, maturing in 65 days. A desirable home garden sort; requires no brush.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $23.00**

## 511 Alderman

**70 days. Giant Podded, Large Peas of Superior Quality, Main Crop or Late Sort**

A large main crop pea, producing in 70 days long, straight, dark green pods 5 to 6 inches long, well filled with large peas of excellent flavor. The vines grow nearly 5 feet high, vigorous and exceedingly productive. Market gardeners are demanding the dark green, large podded, sorts, which retain their appearance after a distant shipment; the Alderman answers these requirements. A popular home and market sort.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 24 cts. per lb.; 100 lbs. $21.00**

511 Alderman Pea

## ✱ 517 Maule's Telephone

**70 days. The Standard Large Dark Podded Main Crop Pea**

A fine wrinkled pea, growing about 4 feet high. The peas are large and a dark green color, sugary flavor. Matures in 70 days; robust grower, and great bearer. The pods are of large size, containing 8 to 10 peas each. Special value in the choice family garden.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 24 cts. per lb.; 100 lbs. $21.00**

## ✱ 498 Dwarf Champion

**65 days. Also Known as Juno, Profuse Bearer**

This pea is one of the finest we have ever tried. It is a hardy, robust, vigorous grower, producing uniform dark green pods of good size, with great abundance and unsurpassed quality. Grows only 2 to 2½ feet tall, requiring no supports. Matures in 65 days.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 22 cts. per lb.; 100 lbs. $19.00**



517 Maule's Telephone Pea

## 512 Sutton's Excelsior

**55 days. A Dwarf Wrinkled Pea, Known as Melting Marrow**

The Sutton's Excelsior pea resembles Nott's Excelsior, but has longer and broader pods of a dark green color; the pods are square at the ends with 6 or 8 large sized peas to a pod. The vines grow 15 inches long and are hardy, permitting early planting. They are very heavy bearers, and on account of its hardiness and large sized pods, many prefer Sutton's Excelsior to the large podded taller varieties. Comes into bearing in about 55 days. It is a fine pea for either home or market gardeners.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**

## 515 Improved Stratagem

**70 days. Large Podded, Immense Peas of Delicious Sweetness**

An excellent wrinkled pea, with sturdy vine growing 2 feet high; vigorous and productive. The pods are of extra large size, often measuring 5 inches in length, and are always well filled, frequently containing 10 peas to the pod. Matures in 70 days. The flavor is first class. Desirable for the home garden and market.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 28 cts. per lb.; 100 lbs. $25.00**

## ✱ 513 Maule's Prodigious or Prince Edward Pea

### The Giant of the Pea Family

**70 days. The Largest Podded, the Heaviest Cropper, the Greatest and Unrivaled Pea**

There are few varieties of seed in this seed book that are better named than this pea. Nothing more nearly expresses its one remarkable characteristic than its name Prodigious, when you consider that this variety will produce pods attaining the extraordinary length of 7 inches and upwards, closely packed with 11 to 13 large, dark green peas of fine flavor. The plant is of branching habit, growing about 5 feet in height, with dark green foliage. It is of very vigorous and robust constitution, which enables it to withstand drought and mildew. The pods are produced in great profusion, mostly in pairs. Prodigious cannot be excelled as an exhibition sort, on account of its striking and very attractive appearance. Market gardeners who do not know Prodigious should give it a trial. There are thousands of our customers who will be delighted to show their friends such enormous pods of peas, the largest, by far, they have ever seen; matures in 70 days. An excellent large dark green podded sort for the home garden or market.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**



513 Prodigious



495 Perpetual

# Second Early or Main Crop

## ✱ 507 Maule's Potlatch or Big Dinner

**68 days. Decidedly the Best of All Large Podded Semi-Dwarf Peas**

Potlatch or Big Dinner has become one of our most popular sorts, the demand for this excellent variety among our market gardener friends being enormous; it is not only a favorite sort with them but is equally popular for the home garden. The vines grow 20 to 24 inches high with unusually dark green foliage. Long pods of a rich dark green color, often measuring 6 inches or more in length, with 9 to 11 enormous peas in a pod are produced in about 68 days. The growth of vine is sturdy and pods are borne in pairs; it is a wonder in productiveness.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 28 cts. per lb.; 100 lbs. $25.00**

## ✱ 495 Maule's Perpetual

**70 days. A True Pick Forever; Bears Large Pods Throughout the Season**

It is more accurately named than any other pea in the list, and for the private garden is an excellent variety; commences bearing its large pods in 70 days and will continue producing its pods for a long time, making it a desirable main crop variety.

We consider it the best or nearest to a perpetual pea of anything we have ever seen.

It grows about 2 to 2½ feet high, of strong, robust habit, a good cropper. After removing the giant pods as fast as they are filled it will continue to bear right along throughout the season. This one feature makes it especially desirable for home or family garden and we know of no pea that will produce so many pods and none that are so well filled as the Perpetual.

**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. or over at 25 cts. per lb.; 100 lbs. $22.00**



507 Potlatch or Big Dinner

# Maule's Sugar Peas

**Long, Thick, Fleshy, Edible Pods. Choice for Snap Shorts, being cooked in the Same Manner as String Beans**

Should not be planted as early as the smooth, round seeded sorts. Wait until the weather becomes warm and settled. Ready for use in 55 to 70 days.



514 Maule's Mammoth Luscious Sugar Pea

## ✱ 514 Maule's Mammoth Luscious Sugar

**70 days. The Perfect Giant Podded Sugar Pea**

This splendid sugar pea fully maintains its reputation as a choice table variety. Indeed, our sales of the seed increase year by year. The peas are not shelled, but the pod is eaten like a snap bean. The pods are stringless, and in flavor, brittleness and succulence are unexcelled. The vines are very tall, reaching a height of 5 or 6 feet and requiring support. The full grown pods are ready to eat in 70 days and are 6 to 7 inches long and 1½ inches broad and are produced continuously for a considerable period, the vines having great bearing capacity on account of their height. The sweetness and tenderness of this pea insure it a permanent place in the garden. It is enormously productive of delicious pods.

**Packet 15 cts.; ½ pound 30 cts.; pound 50 cts.; 5 pounds $2.00, postpaid**
**Not prepaid, 5 lbs. or over at 33 cts. per lb.; 100 lbs. $30.00**

## 525 Dwarf Gray Sugar

**55 days. The Earliest Edible Podded Sugar Pea**

A distinct variety with edible pods maturing in 55 days. Plants growing 2 feet high with an abundance of medium size, sweet and tender pods. Prepare for the table just as you would snap beans, and serve with butter or white sauce.

**Packet 10 cts.; ½ pound 25 cts.; pound 40 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. or over at 23 cts. per lb.; 100 lbs. $20.00**

## 526 Melting Sugar

**70 days. Large Edible Podded Late Sort**

A great favorite, white seeded sugar pea, with those who have once used them. Plants grow 5 feet high, producing handsome large pods in 70 days, which when cooked resemble wax beans; tender and delicious.

**Packet 10 cts.; ½ pound 30 cts.; pound 50 cts.; 5 pounds $2.00, postpaid**
**Not prepaid, 5 lbs. or over at 30 cts. per lb.; 100 lbs. $28.00**

# Maule's Succession Collection of Peas

**489 Early Morning Star, extremely early, height 2 feet**
**509 Laxtonian, second early, height 16 inches**
**496 Thomas Laxton, mid-season, height 2½ feet**
**498 Dwarf Champion, latest sort, height 2½ feet**

**3189 Collection.** One packet each (4 packets in all), for **30 cts.**, postpaid.
**3191 Collection.** Half pound of each (4 half pounds in all), for **85 cts.**, postpaid.
**3193 Collection.** One pound of each (4 pounds in all), for **$1.50**, postpaid.
**3191 Collection,** half pound of each (4 half pounds in all), **50 cts.**, not prepaid.
**3193 Collection,** one pound of each (4 pounds in all), **80 cts.**, not prepaid.

# PEPPERS

The large fruited, mild varieties are largely used as salads, or stuffed with meat or other ingredients and baked or stewed, or sliced and fried as eggplants. The hot and pungent sorts are largely used for flavoring. The hot peppers may be strung on thread or the whole plant hung up to dry for winter use.

CULTURE—Sow the seed ½ inch deep in hot bed, greenhouse or warm window, in March or April. After all danger of frost, set out in open ground. A warm, moist soil is best, with plenty rotted manure plowed under. Set in rows 2 to 3 feet apart and 18 inches apart in the rows. A packet will produce about 100 plants, an ounce about 1500 plants; ¼ pound to transplant for an acre. Ready for use in 110 to 145 days.



530 Maule's Giant Crimson Pepper

## ✱ 530 Maule's Giant Crimson Pepper

**120 days. A Large, Early, Sweet Mango Pepper**

Anyone wishing an early, large, sweet pepper can have one by planting Giant Crimson. It is an early maturing large variety. Very sweet, with exceptionally thick heavy flesh. The color is a beautiful deep green when young, turning to a deep crimson when matured. An excellent, large mango pepper used for stuffing; equally as good for the table. The plant is vigorous and upright, growing 2 to 3 feet high. An ideal home garden sort, and for market gardeners who wish a quick basket filler. Matures in 120 days.

**Packet 15 cts.; ½ ounce 35 cts.; ounce 60 cts.; ¼ pound $1.75; ½ pound $3.25; pound $6.00; 5 pounds $27.50, postpaid**

## 538 Tom Thumb

**135 days. Very Hot, Used Principally for Pepper Vinegar**

Plant dwarf and branching. Fruit globular, about the size of a red cherry. Very hot and productive. Matures in 135 days. Excellent for soups, pepper vinegar, etc., or dried for winter use.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 40 cts.; ¼ pound $1.10; ½ pound $2.10; pound $4.00, postpaid**



533 Maule's Improved Ruby King Pepper

## 545 Large Bell or Bull Nose

**120 days. An Old Standard and Favorite Sort**

Early, bright red in color at maturity, of large size, and has thick flesh. Sweet but occasionally plants will produce fruits which are hot in flavor. Matures in 120 days. The standard variety for both home and market. Sometimes called Sweet Mountain.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 40 cts.; ¼ pound $1.00; ½ pound $1.85; pound $3.50; 5 pounds $15.00, postpaid**

## ✱ 533 Maule's Improved Ruby King

**130 days. The Standard Shipper, Home and Market Pepper**

This pepper was introduced to the American public more than a decade ago, and it at once took a conspicuous place and became the leader of the sweet red sorts. It grows about 5 to 6 inches long by 3 to 4 inches in diameter; flesh is very thick, sweet and so mild it is often sliced for a salad; also fine for stuffing. We have furnished this seed to tens of thousands of gardeners with the most satisfactory results, and our strain of Ruby King is now noted for perfection of form, large size, brilliancy of color, and sweet, mild flavor. Matures in 130 days. So prominent are these desirable features the words "Maule's Improved" are properly attached to the strain we furnish.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 40 cts.; ¼ pound $1.00; ½ pound $1.90; pound $3.75; 5 pounds $17.50, postpaid**

## 542 Royal King

**125 days. Ideal for Stuffing, Baking or for Slaw**

This grand sweet pepper is exceptionally large in size, thick and meaty. Producing in 125 days uniform shaped crimson colored fruit, and continue bearing an enormous yield throughout the season.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 45 cts.; ¼ pound $1.25; ½ pound $2.40; pound $4.50; 5 pounds $20.00, postpaid**

539 Maule's Early Giant Pepper

## 537 Tabasco

**140 days. The Hottest of All Small Peppers**

Pungent and strong; very prolific. It is easily gathered as the fruit does not adhere to the stem and grows almost erect on the branches. This variety is used in manufacturing the well-known Tabasco Sauce. It is tall growing, producing small, slender and very hot fruits in 140 days, splendid for family use, sauce and pickling.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 40 cts.; ¼ pound $1.10; ½ pound $2.10; pound $4.00, postpaid**

## ✱ 539 Maule's Early Giant

**110 days. The Earliest Large and Most Prolific Sweet Pepper Grown**

Maule's Early Giant is the earliest and largest sweet pepper grown. The plants grow about 2 feet in height and are very productive, producing an enormous yield of extra large size green peppers turning red when fully ripe in about 110 days. The thick flesh is very sweet and of pleasant flavor. Owing to its earliness, Maule's Early Giant will produce a good crop of peppers in the Northern States where other large sorts fail. An excellent home garden sort and a profitable large pepper for the market.

**Packet 20 cts.; ½ ounce 65 cts.; ounce $1.25; ¼ pound $3.25; ½ pound $6.25; pound $12.00, postpaid**

## 540 Pimiento or Sweet Salad

**135 days. The Mildest Flavored of All Peppers**

Its productiveness makes it a desirable sort for the home garden or market. Its smooth, thick flesh and uniform shape make it an excellent shipper. Should be planted in every garden where a delicious sweet flavored pepper is wanted. Matures in 135 days.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 40 cts.; ¼ pound $1.00; ½ pound $1.85; pound $3.50; 5 pounds $15.00, postpaid**

540 Pimiento Pepper

## ✻ 532 MAULE'S CHINESE GIANT

**140 days. The Largest of All and Handsomest Mild Pepper**

Chinese Giant is certainly a wonder. The plants are of strong, stocky growth, of bushy, erect habit, growing 18 inches to 2 feet in height, with abundant foliage. The compact plants are very prolific, setting 3 to 4 extra large fruits at the base quite early in the season, which ripen while a second crop is setting on the branches. The fruit is quite square in appearance, while the flesh is thick and very mild, being entirely free from any fiery flavor. Without exception Chinese Giant is the finest and largest mild flavored pepper ever grown. Matures in 140 days.

**Packet 15 cts.; 2 packets 25 cts.; ½ ounce 45 cts.; ounce 80 cts.; ¼ pound $2.25; ½ pound $4.25; pound $8.00, postpaid**



532 Chinese Giant Pepper

## 543 Small Red Chili

**145 days. Pods Are Small and Hot**

Plants grow 18 inches high, fruit usually erect, about 1½ inches long, cone shaped, bright red and very hot; exceedingly prolific. Matures in about 145 days. Used for pepper sauce or pickling or dried for winter use.

**Packet 10 cts.; ½ ounce 20 cts.; ounce 35 cts.; ¼ pound 90 cts.; ½ pound $1.65; pound $3.00, postpaid**

## 550 Mixed Peppers

**110 to 145 days. Especially Suitable for a Family Garden**

A grand assortment of peppers, whereby anyone can have peppers large or small, sweet or hot in 110 to 145 days.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 40 cts.; ¼ pound $1.10; ½ pound $2.15; pound $4.00, postpaid**

## 536 Golden Queen

**125 days. The Sweetest and Largest Yellow Sort**

Is the best of all yellow peppers. It is always large, specimens reaching 6 to 10 inches in length and 4 to 5 inches in diameter, maturing in 125 days. A single plant sometimes carries 20 large peppers at the same time. The flavor is mild and pleasant. The beautiful golden yellow color contrasting with the green and red of the other sorts makes an excellent combination which is always admired on the table or in pepper sauce. A desirable pepper for the home garden, or for exhibition at County or State Fairs.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 45 cts.; ¼ pound $1.25; ½ pound $2.40; pound $4.50; 5 pounds $21.25, postpaid**

535 Maule's Red Hot Pepper

## 541 Burpee's Sunnybrook

**110 days. An Improved Tomato Pepper**

A most remarkable new pepper for the home garden as well as for market. The plants grow 15 inches tall and measure about 22 inches in diameter. The branches, laden with clusters of fruits, bend down under the heavy weight of the peppers.

The individual fruits run from 2½ to 3 inches in diameter and they are from 2 to 2¼ inches deep from the stem to the blossom-end. The skin is smooth, glossy, and of a brilliant scarlet. The flesh is unusually thick, and in well-developed fruits measures five-eighths of an inch in thickness, surpassing in that respect any other pepper. The rich scarlet flesh is tender and outstandingly sweet and tasty.

**Packet 15 cts.; ½ ounce 40 cts.; ounce 75 cts.; ¼ pound $2.00; ½ pound $3.85; pound $7.50, postpaid**

## ✻ 535 Maule's Red Hot

**120 days. The Hottest of All Large Sorts**

The handsome long peppers grow about 5 to 7 inches long. It produces its fruit in wonderful profusion. It is thick fleshed, bright red in color when fully matured, hot and pungent. Fit to pick in 120 days. Excellent for soups, canning, etc., or dried for winter use.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 45 cts.; ¼ pound $1.25; ½ pound $2.40; pound $4.50; 5 pounds $20.00, postpaid**

## 547 Long Red Cayenne

**125 days. The Well Known Favorite Hot Pepper**

The conical shaped fruits are 3 to 4 inches long, of bright red color, and borne in great profusion. The flesh in character is very hot. A favorite for bunching with pot herbs or for winter use. Matures in 125 days.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 40 cts.; ¼ pound $1.00; ½ pound $1.85; pound $3.50; 5 pounds $15.00, postpaid**

531 Maule's Neapolitan Pepper

## ✻ 544 Worldbeater

**130 days. A Cross Between Chinese Giant and Ruby King**

This wonderful large, mild pepper, shape similar to Ruby King, except broader at the pointed end and almost the size of Chinese Giant, can be sliced and eaten raw without any fear of burning. The color of the fruit is green at first, turning to a beautiful scarlet. Flesh thick and sweet; very productive, maturing in 130 days. An excellent shipper.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 45 cts.; ¼ pound $1.25; ½ pound $2.40; pound $4.50; 5 pounds $20.00, postpaid**

## ✻ 531 Maule's Neapolitan

**110 days. The Earliest of All Large Sweet Peppers**

Neapolitan proves itself to be earlier than any other large, sweet, mild pepper. A wonderful bearer, single plants often yielding 30 to 40 peppers, and continues loaded with fruit right up to frost. Plants are of strong growth, very stocky, and peppers are borne erect, maturing its good sized peppers in 110 days. Flesh is very thick and fruit is pale green turning to a brilliant red color. If our customers want peppers two weeks ahead of their neighbors, they must plant Neapolitan. Our seed is carefully selected. You get headquarters stock from us.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 40 cts.; ¼ pound $1.00; ½ pound $1.85; pound $3.50; 5 pounds $15.00, postpaid**

544 Worldbeater Pepper

# PUMPKINS

CULTURE—Pumpkins will grow almost anywhere, but rejoice in rich soil. In many varieties the size and weight depend almost wholly on culture and fertility of the land. Plant in hills 8x8 feet, or drop three or four seeds in every fourth hill in the corn field. Put seed in ground in May or June. Use a packet to about 5 hills, an ounce for 25 hills; three to four pounds per acre; thin out to 2 or 3 plants to a hill. Ready to use in 65 days to 100 days. For winter use, gather before frost and store in a warm, dry place.

## ✻ 554 Maule's Yellow Sweet Potato Pie Pumpkin

554 Maule's Yellow Sweet Potato Pie Pumpkin

**90 days. A Favorite Household Sort**

Maule's Yellow Sweet Potato Pie is a handsome and high merit pumpkin, famed as a pie-maker, and is one of the most satisfactory that we ever introduced. It has given satisfaction to many thousands of our customers. It is not only a good thing for the kitchen, but is also an unsurpassed food for dairy cows. Matures in 90 days.

The flesh is very thick and fine grained, of a beautiful golden yellow color, and in texture and flavor peculiarly adapted for pie-making purposes.

As a winter keeper it is unexcelled; the pumpkins will remain in perfect condition until spring.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.00, postpaid**

## 566 Winter Luxury or Pie

**90 days. A Great Favorite Pie Pumpkin**

Medium size, nearly round. Skin light yellow, covered with a fine gray netting. The flesh is light yellow, very thick, sweet and finely flavored. Matures in 90 days. Excellent for custards or pies.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**

## 564 Japanese Pie

**90 days. A Large Dark Green Sort**

The skin is dark green, with faint green stripes. Flesh very thick, a rich salmon color, fine grained, dry and sweet. Of large size, early, very productive and a good keeper. Ninety days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.00, postpaid**

## 562 Tennessee Sweet Potato

**90 days. Highly Recommended for Pies and Custards**

Pear shaped, slightly ribbed. Color, creamy white, sometimes lightly striped with green. Flesh light colored, fine grained, dry and of a superior flavor, and when cooked resembles a sweet potato in taste. A good keeper. Matures in 90 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.00, postpaid**

## 563 Cushaw or Crookneck

**75 days. The Popular Crookneck Sort**

One of the widely popular varieties. Often producing pumpkins in 75 days, 2 feet long, light colored. Flesh yellow, solid, sweet; excellent for pies.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 40 cts.; ½ pound 65 cts.; pound $1.15; 5 pounds $5.00, postpaid**

555 Small Sugar Pumpkin

**Pumpkins Continued on Next Page—60**

## ✻ 555 Small Sugar

**65 days. The Yankee Pie Pumpkin; Dry and Sweet**

The pumpkin from which the celebrated Yankee pumpkin pie is made. It has a deep orange skin and fine grained flesh of extra fine flavor, maturing in 65 days. An excellent keeper. Is prolific and desirable.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 90 cts.; 5 pounds $3.75, postpaid**

## 558 Large Cheese or Kentucky Field

**90 days. Makes Good Pies; Rich Stock Food**

A large, round, flattened pumpkin, with broad ribs. Often attains a diameter of 2 feet. Color, creamy buff. The flesh is yellow, fine grain. A large sort and does well amongst corn. Fine for pies; rich food for stock. Matures in 90 days.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 85 cts.; 5 pounds $3.75, postpaid**

556 Maule's Prize Potiron Pumpkin

## ✻ 556 Maule's Prize Potiron

**100 days. Enormous; Have Been Grown Weighing Over 100 Pounds**

A prize winner. Grows to an immense size in 100 days. Flesh bright yellow, fine grained and of good quality. The outer skin is salmon colored. Notwithstanding its great size, it is excellent for making into pies, and a good winter keeper.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 50 cts.; ½ pound 85 cts.; pound $1.50; 5 pounds $6.25, postpaid**

## 559 Green Striped Cushaw

**75 days. An Improved Strain of the Old Cushaw**

Beautiful in appearance; a distinct mottled green, white striped. Fruit solid, average 15 to 25 pounds. Flesh rich yellow, solid, fine grained, very thick and sweet. Excellent for pies; matures in 75 days. Excellent keepers.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**

## ✻ 557 Connecticut Field

**70 days. The Best Yellow Corn Field Sort**

Also known as Big Tom. A large round or slightly oval shape pumpkin. Skin reddish orange color, with rich orange yellow flesh. Extensively grown for stock feeding, and generally planted with corn, producing enormous crops in 70 days. One of the best grown for pies.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 85 cts.; 5 pounds $3.75, postpaid**

## 567 Mixed Pumpkins

**65 to 100 days. All Shapes, Colors and Sizes**

This mixture is especially offered to those who wish to grow a collection of the different kinds of pumpkins here listed for exhibition at County Fairs, or for home use. All are good keepers, maturing small and large pumpkins in 65 to 100 days.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**

## ✻ 561 Maule's Hundred-Weight

**100 days. The Largest of All Pumpkins. The Great Premium Taker**

A selected strain of our Prize Potiron, maturing in 100 days. Seed saved only from specimens weighing over 100 pounds. This is the pumpkin for show purposes, as it not infrequently attains a record of 200 pounds. In spite of its large size, it is one of the best pie and table varieties grown. The outside is a dark salmon, decidedly handsome; the flesh is bright yellow, sweet and tender. These large specimens contain few seeds, so the price is necessarily high.

**Packet 15 cts.; ounce 40 cts.; ¼ pound $1.10; ½ pound $2.25; pound $4.00; 5 pounds $17.50, postpaid**

**Lend This Catalog to Your Neighbor**

# TOBACCO

CULTURE.—Sow seed in a hot bed in February or March and treat same as Tomatoes. Use wood ashes on seed bed. When plants are large enough and weather settled, transplant in rows 3 or 3½ feet apart each way, and cultivate frequently. A packet will produce about 200 plants; an ounce produces about 5,000 plants, sufficient for an acre.

**716 BIG HAVANA.** — An Americanized Havana, large, long leaf. It is one of the earliest. Fine texture.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 40 cts.; ¼ lb. $1.00; ½ lb. $1.90; lb. $3.75, postpaid**

**720 PENNSYLVANIA SEED LEAF.** — Very extensively grown in the Lancaster district of Pennsylvania, which is famous for its fine cigar tobaccos.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 45 cts.; ¼ lb. $1.35; ½ lb. $2.50; lb. $4.75, postpaid**

**724 CONNECTICUT SEED LEAF.**—Grown in all sections of the U. S. and extensively in Connecticut. Broad leaf of medium length. Suitable for cigar fillers.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 40 cts.; ¼ lb. $1.00; ½ lb. $1.90; lb. $3.75, postpaid**

**725 SWEET ORONOKO.**—A long narrow leaf, curing a rich red, the finest plug fillers. Makes the best natural chewing leaf.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 45 cts.; ¼ lb. $1.35; ½ lb. $2.50; lb. $4.75, postpaid**

**726 THE PRIMUS.**—This is the earliest tobacco grown. It will ripen even in Canada. Leaves large, fibre fine, texture silky, flavor superior. It makes an elegant smoking tobacco, either for cigars or pipe.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 45 cts.; ¼ lb. $1.35; ½ lb. $2.50; lb. $4.75, postpaid**

**727 IMPROVED WHITE BURLEY.**—Of especial value for cut or plug tobacco; often used for wrappers. Large, broad leaf, curing a very desirable color.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 45 cts.; ¼ lb. $1.10; ½ lb. $2.25; lb. $4.25, postpaid**

726 The Primus Tobacco

# TREE SEEDS

**Culture directions are plainly printed on each size package.**

**866 Arbor Vitae, American.**—Erect, pyramidal evergreen trees. Useful in groups, beds or borders.

**Packet 15 cts.; ½ oz. 30 cts.; oz. 55 cts.; ¼ lb. $1.50; ½ lb. $2.90; lb. $5.75, postpaid**

**867 Apple.**—Hardy, rooted plants are used for grafting to by nurserymen.

**Packet 10 cts.; oz. 20 cts.; ¼ lb. 60 cts.; ½ lb. $1.00; lb. $1.75, postpaid**

**869 Catalpa Speciosa.**—Valuable for timber, fence posts, railroad ties, etc. A rapid grower.

**Packet 10 cts.; ½ oz. 20 cts.; oz. 35 cts.; ¼ lb. 90 cts.; ½ lb. $1.75; lb. $3.25, postpaid**

**870 Cherry Mazard.**—Hardy, rooted plants are used for grafting to by nurserymen.

**Packet 10 cts.; oz. 25 cts.; ¼ lb. 60 cts.; ½ lb. $1.10; lb. $2.00, postpaid**

**871 Honey Locust.**—Large, vigorous tree with fern-like leaves. Makes a fine defensive hedge.

**Packet 10 cts.; oz. 15 cts.; ¼ lb. 45 cts.; ½ lb. 75 cts.; lb. $1.25, postpaid**

**872 Norway Spruce.**—A popular evergreen tree, effective in groups, hedges or single specimen on lawns.

**Packet 15 cts.; ½ oz. 25 cts.; oz. 40 cts.; ¼ lb. $1.00; ½ lb. $1.85; lb. $3.50, postpaid**

**873 Osage Orange.**—Valuable hedge plant with fern-like leaves, branches closely thorned. Sometimes planted as specimen trees.

**Packet 10 cts.; ½ oz. 20 cts.; oz. 30 cts.; ¼ lb. 85 cts.; ½ lb. $1.50; lb. $2.75, postpaid**

**874 Pear, Kieffer.**—Hardy, rooted plants are used for grafting to by nurserymen.

**Packet 15 cts.; ½ oz. 30 cts.; oz. 50 cts.; ¼ lb. $1.40; ½ lb. $2.60; lb. $5.00, postpaid**

**878 Fir, Douglass.**—A rapid grower. Makes fine specimen evergreen tree for the lawn also valuable for timber.

**Packet 15 cts.; ½ oz. 60 cts.; oz. $1.00; ¼ lb. $3.25; ½ lb. $6.25; lb. $12.00, postpaid**

**879 White Pine.**—A rapid growing evergreen tree for the lawn. Useful for groups beds, etc.

**Packet 15 cts.; ½ oz. 40 cts.; oz. 75 cts.; ¼ lb. $2.00; ½ lb. $3.90; lb. $7.50, postpaid**

**880 Yellow Locust.** — Produces trees of large size. A rapid grower. Valuable also for timber.

**Packet 10 cts.; oz. 15 cts.; ¼ lb. 35 cts.; ½ lb. 60 cts.; lb. $1.00, postpaid**

**881 Yellow Pine.**—A quick, strong grower heavy needled evergreen tree for the lawn also valuable for timber.

**Packet 15 cts.; ½ oz. 35 cts.; oz. 65 cts.; ¼ lb. $1.85; ½ lb. $3.50; lb. $6.75, postpaid**

# RADISH

**Early round and olive shaped radishes are very popular for early spring use; the half long and long varieties planted at the same time follow a little later**

CULTURE—Sow in ground well enriched with rotted manure. Quality depends on quickness of growth. Sow seed ½ inch deep in the early spring in rows 12 to 18 inches apart; for a succession sow every 10 days. Cultivate frequently. A packet will sow about 20 feet of drill, an ounce about 100 feet, or use 8 to 10 pounds per acre. Thin to 1 inch apart for small varieties and 3 or 4 inches for the large varieties.

## Early Round Radishes.

### ✱ 583 Maule's Earliest Scarlet

**18 days. The Best Early All Red Round Radish**

If you wish to have the finest and first ed radishes sow Maule's Earliest Scarlet. t is crisp and brittle. The skin is of a ich, scarlet color, while the flesh is pure white, and always tender, mild and weet. It has a small, short top, and is vell adapted to open air culture or to orcing under glass. Matures in 18 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

### ✱ 580 Maule's Sparkler

**20 days. Best of the Round White Tips**

Crisp and sweet, remaining fit for use onger than most of the other globe-haped sorts. The colors are very vivid nd attractive. The upper part is a rich armine scarlet, with a large tip of the urest white. An excellent forcing sort nd highly recommended for growing in he open ground. Ready in about 20 days.

**Packet, 10 cts.; ounce, 15 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 90 cts.; 5 pounds $4.00, postpaid**

### 594 Golden Globe

**5 days. Quick Grower. Best Summer Radish**

This quick growing, round, yellow rad-sh is used extensively for Spring or ummer planting in the home garden, naturing in 35 days. Stands heat and dry veather well without becoming pithy or trong. Flesh clear white, crisp and solid; ine quality.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 90 cts.; 5 pounds $4.00, postpaid**

580 Maule's Sparkler Radish

## Fit for forcing or out-door planting.

### 588 Philadelphia White Box

**30 days. The Favorite Round White Radish**

A most excellent radish for forcing under glass or for growing in the open ground. Its short top and rapid growth make it a great favorite with market men, and its mild, sweet quality wins the favor of the consumer. It remains solid and crisp for a long time. Matures its white globe shape radishes in about 30 days.

**Packet, 5 cts.; ounce, 10 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 90 cts.; 5 pounds $4.00, postpaid**

### ✱ 579 Maule's American Beauty

**25 days. Early Turnip Shaped Radish of Surpassing Quality**

Maule's American Beauty produces eatable size round bright rose-red colored radishes which are always crisp and tender in 25 days, and continues to be in good eating condition for several weeks. It has the best keeping qualities of any turnip shaped sort. Maule's American Beauty is an excellent market or kitchen garden variety.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

579 Maule's American Beauty Radish

### ✱ 573 Maule's Just So

**30 days. The Best White Globe Shape Radish for Home or Market**

Maule's Just So is the best all around radish ever offered the American public. Good either for forcing or open ground culture. We have tested nearly every variety sent out, and have originated many varieties ourselves, but nothing has ever come to our notice that will equal Just So. Crisp and tender radishes may be had in 30 days, white and smooth.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

### ✱ 590 Rapid Red or Saxa

**16 days. Quickest Growing Round Red**

This desirable, quick growing, red button radish produces its crop in 16 to 20 days. Round as a marble, having a very small top and tap root. The skin is a bright scarlet color, with firm white flesh, which is crisp, brittle and juicy. Adapted for forcing or outdoor planting.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 40 cts.; ½ pound 65 cts.; pound $1.15; 5 pounds $5.00, postpaid**

## Ready for use in 15 to 35 days.




### ✱ 585 Maule's Earliest White

**15 days. The Earliest of All Radishes**

A splendid, olive-shaped radish, pure white in color. It is distinctly earlier than any other radish grown of any color, as will be understood when we say that good sized radishes may be pulled in about 15 days from the sowing of the seed. It has a small top, is solid and crisp, of good flavor, and first-class in every respect. An elegant home garden or early market sort.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

### 597 Early Scarlet Globe

**20 days. The Popular Round Red Sort**

This grand radish has established a reputation as a forcing sort. Its color is a rich scarlet. It has a small top. Matures in about 20 days and is an excellent variety for sowing outdoors.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**



590 Rapid Red or Saxa Radish

# Round and Olive Shape Radishes—Ready for Use in 15 to 30 Days

## ✻ 592 French Breakfast

**20 days. The Ideal Early Olive-Shape Radish**

This pretty radish in color is bright red, tipped with white. It is oblong in shape, and in quality is crisp and tender. It is a quick grower, maturing in 20 days. Exceedingly popular.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**

## 575 Burpee's Relish

**22 days. Round, Crisp, Bright Carmine Sort**

Burpee's Relish is an excellent, crisp, bright carmine radish. A joy to the eye and a treat to the palate. Appetizing in appearance, with pure white flesh. Regular in size and shape, forming superb round roots of surprising crispness and a delightful, snappy radish flavor. A foremost variety which retains its good qualities until fully grown.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 50 cts.; ½ pound 90 cts.; pound $1.75; 5 pounds $7.50, postpaid**

## 598 Scarlet Olive Shaped

**20 days. The 20-Day Radish**

This highly desirable early radish is of quick growth and attractive rich carmine color. Of good appearance, with crisp, white, tender flesh of mild flavor. Fit to eat in 20 days.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**

## ✻ 582 Maule's Scarlet Turnip White Tipped

**20 days. Attractive and Handsome**

The color is rich carmine scarlet and tipped white. It is extremely quick to mature, being ready for the table in 20 days from the time of sowing the seed. It is invaluable for forcing under glass, as well as for growth in the open air. Its flavor is excellent, and its qualities high in all respects. Market gardeners find it a quick selling sort at good prices.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**

## 569 The Maule Radish

**30 days. Large Round Red Early Sort**
**See Front Cover for Colored Illustration**

This new Giant Radish is early, crisp and long standing. It is perfectly globular in shape; no early variety we know of retains its firmness of flesh so long after attaining full size. It is undoubtedly a marvel in this respect. Beautifully shaped and with a bright, shining scarlet skin, when cut the flesh is pure white and of great solidity. In addition to its crispness it has the true full radish flavor. The tops are of good size to allow for easy bunching, this greatly adding to its desirability as a money-making market variety. Also an excellent home garden sort.

**Packet 25 cts., postpaid**



582 Maule's Scarlet Turnip White Tipped Radish

## ✻ 572 Crimson Giant

**30 days. Grows Double the Size of Any of the Early Round Sorts**

A large growing sort, of a beautiful deep crimson color, often measuring from 6 to 7 inches in circumference. The flesh is white, mild in flavor, firm and crisp. Good for market or home gardeners, for forcing or open ground culture, maturing in about 30 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 25 cts.; ½ pound 45 cts.; pound 85 cts.; 5 pounds $3.75, postpaid**

## 610 Mixed Radishes

**15 to 50 days. All kinds, Colors and Shapes**

This mixture contains a great variety. Just what is wanted for the home garden where the space is limited. One sowing is all that is required for a continuous supply, as they become ready for table use in 15 to 50 days.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00, postpaid**

# Half Long Radishes—Ready to Use in 40 to 42 Days



571 Maule's 1834 Radish

## ✻ 571 Maule's 1834 or All Year Round

**40 days. A Radish Adapted to Every Season**

This high-bred white radish, widely known under the name of 1834, is of a beautiful ivory color, crisp and brittle. That it has been in favor for almost a century is proof of its extra good quality, and still maintains its original excellence. The shape is shown in the illustration. Ready to use in 40 days. Gives satisfaction everywhere.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

## ✻ 593 White Strasburg

**40 days. The Popular White Summer Variety**

A white radish, of large size, often growing 4 to 5 inches in length, of good quality, and ability to resist severe heat. This variety keeps continuously crisp and tender for a long time. The home and market gardeners' favorite Summer radish. Ready to use in about 40 days.

**Packet 5 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**

## 577 Maule's White Delicious

**42 days. One of the Very Best Large Summer Varieties**

This half long radish is far superior to any other white radish yet introduced, producing handsome shaped white radishes, whose crisp, sharp, brittle quality has no superior, while the roots are always smooth and regular in shape and solid all the way through. A rapid grower. A popular market or home garden sort, maturing in 42 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 40 cts.; ½ pound 65 cts.; pound $1.15; 5 pounds $5.00, postpaid**

593 White Strasburg Radish

# LONG RADISHES—Ready to Use in 23 to 35 Days

## ✻ 584 ICICLE RADISH

584 Icicle Radish

**25 days. The Finest Early Long White Radish**

The Icicle radish is perfectly white in color, and long, slender and tapering in shape. It quickly grows to market size, is crisp and brittle, and of mild, sweet flavor. It remains tender during the entire growing period, and is quite as good when an inch in diameter as when only half an inch. Excellent and profitable. Ready for use in about 25 days. Admirable alike for outdoor planting and forcing under glass.

A fine variety for market and private gardeners, who have a demand for an early, long, white radish. It is a marvel of excellence, most attractive in appearance and very popular.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 20 cts.; ½ pound 35 cts.; pound 65 cts.; 5 pounds $3.00, postpaid**

## ✻ 581 Maule's Improved Long Scarlet Short Top

**30 days. The Very Best Long Red Radish**

Our strain of this very popular long radish is the finest to be had on the market. In it we have, without exception, the very best long brittle, brightest scarlet radish we are acquainted with. It matures beautiful radishes, which are always brittle and sweet, in 30 days from the sowing of the seed. It is undoubtedly the standard long red variety that will withstand the hot dry weather and remain firm and crisp and of fine flavor. For either the market or home gardener, it is the best.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**

581 Long Scarlet Radish

## ✻ 587 Improved Chartiers

**35 days. A Large, Handsome and Crisp Sort**

One of the best long radishes for general planting. Matures in about 35 days, and continues hard and crisp. Red above and shading to clear white at the tip. Large, but both brittle and tender. Widely popular and desirable. The best long red radish for Summer planting.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 25 cts.; ½ pound 45 cts.; pound 85 cts.; 5 pounds $3.75, postpaid**

## 591 Long Cardinal

**23 days. Known as Brightest Scarlet**

Fit for use in 23 days from sowing. It is of a bright red color, with white tip. Noted for its crisp, tender flesh and good appearance. It is smooth and uniform and highly colored.

**Packet 5 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**

## 586 Cincinnati Market

**30 days. Sometimes Called Glass or Red Icicle**

This radish is widely sown in the south, and is certainly of high quality, very early, maturing in about 30 days. Splendid for forcing or open ground. Handsome bright red in color, growing straight and smooth; about 6 inches long.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**

## 601 White Lady Finger

**35 days. Snow White, Brittle and Crisp**

Sometimes called Long White Vienna. An extremely popular sort, and is one of the very best long white radishes. It is graceful in form and in flavor is sweet and mild, with brittle flesh. Ready to use in about 35 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**



587 Improved Chartiers Radish

# WINTER RADISHES



603 Maule's Winter

CULTURE—Thrive best in a light, sandy soil enriched with rotted manure. Sow the seed ½ inch deep in rows 15 to 24 inches apart, in June, July or August; thin out to stand 4 to 6 inches apart in the rows. Cultivate frequently. Use a packet to 20 feet of drill, an ounce to 100 feet, 8 to 10 pounds per acre. Ready for use in 60 to 70 days. Can be kept over winter by placing in box of sand stored in cool cellar.

## ✻ 603 Maule's Winter

**65 days. Large White, the Best of the Winter Sorts**

This is a fine, large, white radish, superior to any other variety. It will grow to a very large size in 65 days, 8 to 15 inches in length and even larger.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.50, postpaid**

## 604 Japanese Colossal

**70 days. Solid, Crisp and Mild**

Every radish grower should plant some of this great variety; it is oval shaped, flesh and skin pure white, and grows to immense size in 70 days and retains the delightful crispness of the smaller sorts; excellent keeper.

**Packet 10 cts.; ounce 25 cts.; ¼ pound 65 cts.; ½ pound $1.10; pound $2.00; 5 pounds $8.75, postpaid**



604 Japanese Colossal Winter Radish

## 605 Long Black Spanish

**70 days. White Flesh, Solid and Pungent**

A large, black-skinned radish. Roots oblong, black, with firm white flesh and firm texture of pungent flavor; matures in 70 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.50, postpaid**

## ✻ 607 China Rose

**60 days. A Quick Grower; a Splendid Keeper**

A large, fine shaped rose colored radish, growing partly above the ground. The portion above ground is darker in color than that below ground. The size is 3 to 4½ inches long and in proportion. Flesh pure white. Flavor mild. A splendid keeper for use in winter; matures in 60 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**



607 China Rose Winter Radish

# Spinach

**When properly prepared, no vegetable makes more nutritious and palatable greens**

CULTURE—Sow seed in good, rich soil in early spring 1 inch deep in rows 1 foot apart or broadcast. For a succession, sow every two weeks until June 15th, and again from August 10th to September 15th. For early spring use, seed may be sown in September, and covered with a few inches of hay, leaves or litter the last of November and left on during the winter. A packet will sow about 25 feet of drill, an ounce to 100 feet, 8 to 10 pounds per acre in drills; 12 to 15 pounds broadcast. Ready to cut in about 40 to 55 days.

## ✻ 617 New Princess Juliana Spinach

**45 days. Remains in Good Condition After Others Have Gone to Seed**

A new spinach of the long season type, but leaves are more crumpled, of a darker green color. Good size, thick and of good quality. Although it is ready to cut almost as soon as the medium-early sort, it will remain fit for use after other varieties have bolted to seed, except King of Denmark, and retain their freshness during the hot summer months. Matures in about 45 days. We recommend Princess Juliana to all our customers. You need have no hesitancy in planting this variety for it is exceptionally good and can be depended upon to produce extra fine quality Spinach in abundance. Excellent home or market sort.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 20 cts.; ½ pound 30 cts.; pound 55 cts.; 5 pounds $2.25, postpaid**
**100 lbs. $35.00, charges prepaid**

617 New Princess Juliana Spinach

## ✻ 621 Bloomsdale or Savoy Leaved

**40 days. Hardiest; Best for Early Summer and Fall Planting**

Also called Norfolk Savoy Leaved. A favorite with the home and market gardeners. Matures in 40 days. It has thick, dark green crumpled leaves, and is perfectly hardy. One of the best spinaches.
**Packet 5 cts.; ounce 10 cts.; ¼ pound 20 cts.; ½ pound 30 cts.; pound 45 cts.; 5 pounds $1.75, postpaid**
**100 lbs. $25.00, charges prepaid**

## 618 Victoria 45 days. True Savoy Type

An excellent variety, forming very large, exceedingly thick, very dark green leaves slightly crumpled in the center. Ready to eat in 45 days. The leaves are usually blunt or rounded at end but sometimes broad arrow-shaped. Unexcelled for Spring or Fall sowing.
**Packet 5 cts.; ounce 10 cts.; ¼ pound 15 cts.; ½ pound 25 cts.; pound 35 cts.; 5 pounds $1.50, postpaid**
**100 lbs. $22.50, charges prepaid**

## 625 Long Season 50 days. A Good All Season Sort

A very dark green, crumpled variety, in general appearance similar to Savoy Leaved but considerably larger and broader in leaf, less crumpled and very much longer standing.
**Packet 5 cts.; ounce 10 cts.; ¼ pound 15 cts.; ½ pound 25 cts.; pound 35 cts.; 5 pounds $1.50, postpaid**
**100 lbs. $22.50, charges prepaid**

## ✻ 624 King of Denmark 48 days. Stands Two Weeks Longe Than Most Sorts

King of Denmark is far superior to any of the other sorts. Its principal advantage is that it stands two weeks longer before running t seed than any other variety except Princess Juliana. The leaves ar large, rounded, Savoy or crumpled, of deep green color.
**Packet 10 cts.; ounce 15 cts.; ¼ pound 20 cts.; ½ pound 30 cts. pound 50 cts.; 5 pounds $2.00, postpaid**
**100 lbs. $30.00, charges prepaid**

## 623 Long Standing 45 days. Remains Fit for Use a Long Time

An improved round seeded strain of excellent quality. Ready to cu in 45 days, but after reaching maturity it remains in condition fo use much longer than most sorts. The plant is very large, becoming rather procumbent when mature. The leaves are usually very broad arrow-shaped, smooth and dark, rich green.
**Packet 5 cts.; ounce 10 cts.; ¼ pound 15 cts.; ½ pound 25 cts. pound 35 cts.; 5 pounds $1.50, postpaid**
**100 lbs. $22.50, charges prepaid**

## 619 Viroflay or Improved Thick Leaved 45 days. A Quick Growe

A variety which grows rapidly, and is one of the best market sorts, producing large, thick, dark green crumpled arrow-shaped but somewhat rounded leaves in 45 days, of fine quality.
**Packet 5 cts.; ounce 10 cts.; ¼ pound 15 cts.; ½ pound 25 cts. pound 35 cts.; 5 pounds $1.50, postpaid**
**100 lbs. $22.50, charges prepaid**

## ✻ 620 Giant Fillbasket 48 days. The Largest Growing Variet

The glossy dark green foliage is attractively crumpled and thicl in texture. The numerous leaves are extra large, broad and rounded Ready to cut in 48 days, will stand a long time without bolting to seed
**Packet 10 cts.; ounce 15 cts.; ¼ pound 20 cts.; ½ pound 30 cts. pound 50 cts.; 5 pounds $2.00, postpaid**
**100 lbs. $27.50, charges prepaid**

# ✻ 622 Maule's Everlasting or New Zealand Spinach

622 Maule's Everlasting or New Zealand Spinach

**55 days. A Grand Hot Weather Vegetable. Endures Heat; Best Spinach fo Summer Use**

Maule's Everlasting or New Zealand Spinach is a different plant, botanically, both in habit of growth and in the size and shape of its seeds; but in color, shape, succulence and taste of leaf it is remarkably like the true spinach Thrives during hot weather and in any soil, rich or poor. Ready to cut in 5 days. The tender shoots are of good quality and may be cut throughout th summer. The plant becomes very large and spreading. The leaves are comparatively small, broad and pointed. Both types of spinach are boiled an served as "greens," and are appetizing and wholesome; in fact, no othe vegetable can quite take the place of spinach. This is why Everlasting Spinach, served in midsummer, has attracted the attention and won the praise of so many of our customers.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.00, postpaid**
**100 lbs. $70.00, charges prepaid**

# Summer Squashes

CULTURE—About the same as melons. Make the ground very rich. A good sandy loam is best. The squashes are all tender and the seed should not be planted until warm weather. Allow 4 x 4 feet for the hills of the summer squashes and 8 x 8 feet or more for the winter varieties. Use seed freely, thin out summer varieties 4 plants to a hill; winter varieties 2 to 3 plants to the hill. A packet will sow about 8 hills; an ounce, about 40 hills; 3 to 4 pounds to the acre. Summer squashes are ready for use in 45 to 55 days; winter sorts in 60 to 90 days.

628 Earliest White Bush Squash

## 628 Earliest White Bush 45 days. Earliest of All

The bush or patty pan squashes are earlier than any other summer variety. The illustration shows the characteristic shape. The skin of this one is white and it is tender when ready for use. It is of dwarf bushy habit, quite hardy and very productive. Matures in 45 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 40 cts.; ½ pound 65 cts.; pound $1.15; 5 pounds $5.00, postpaid**

## 631 Early Yellow Bush

**45 days. Golden Yellow, of Good Quality**

Similar to the white bush in every way, except color and markings. The skin and flesh is of a clear yellow. Matures in 45 days.

**Packet 5 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.00, postpaid**

## ✱639 Cocozelle or Italian Vegetable Marrow

**55 days. Fine Grained Flesh of Excellent Flavor**

Fruits large, oblong shaped, dark green at first, but as they mature become marbled with yellow, and lighter green stripes. Ready for the table in 55 days. Fine grained, tender and of excellent flavor.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 40 cts.; ½ pound 65 cts.; pound $1.15; 5 pounds $5.00, postpaid**

632 Mammoth Golden Crookneck

## 647 Fordhook Bush

**55 days. Perfect for Summer or Winter Use**

A true bush type of Fordhook, that can be grown much more closely. The fruits are rather shorter and thicker than those of the running type, also thicker fleshed. Ready for the table in 55 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 40 cts.; ½ pound 65 cts.; pound $1.15; 5 pounds $5.00, postpaid**

## 650 Mixed Squashes

**45 to 90 days. Supplies the Table the Entire Season**

In this mixture will be found early and late, small, medium and large, whereby any one can have a good supply of delicious squashes which mature in 45 to 90 days.

**Packet 5 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00, postpaid**

## ✱ 632 Mammoth Golden Summer Crookneck

**55 days. Largest of the Crooknecks**

One of the best of the summer squashes. It is of dwarf, bushy habit and very productive, maturing in 55 days. The skin is yellow. Flesh deep golden yellow, tender, dry and of agreeable flavor.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.25, postpaid**



639 Cocozelle Bush Squash

*See next page, 66, for Winter Squashes*

# Easily Grown Horse Radish Sets In Great Demand for Seasoning

The culture is by sets or root cuttings. These sets are planted vertically in rows or furrows 2 to 3 feet apart and 15 to 18 inches apart in the rows with the small end down, so that the top end is about 2 inches below the surface. Ready to use in the late fall or winter months.

## 69B84 Maliner Kren The Large White Horse Radish from Bohemia

The roots are so much larger and heavier than the common variety that the yield is about doubled. Then, too, it matures much quicker, which enables the grower to market or use his roots earlier. The flesh is pure white.

**6 for 30 cts.; 50 cts. per dozen; $2.50 per 100, postpaid**
**Not prepaid, $2.00 per 100; $8.00 per 500; $15.00 per 1,000**

**Full cultural directions for growing Rhubarb and Horse Radish sent with every order.**

69B84 Maliner Kren Horse-Radish

# Rhubarb or Pie Plant Seed

CULTURE—Plants easily grown from seed. Sow in drills about 18 inches apart, and thin the plants 7 to 12 inches in the drills. Use a packet to about 10 feet of drill, an ounce to 75 feet. Stalks should not be cut until the third year.

## 611 Victoria The Most Popular Variety Grown

A good market sort, with beautiful red stalks, giving satisfaction everywhere.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 50 cts.; ½ pound 85 cts.; pound $1.50; 5 pounds $6.25, postpaid**

## 69B88 Victoria Rhubarb or Pie Plant Roots

Plant roots 4 feet apart each way. Stalks can be cut the following spring.

**20 cts. each; 3 for 50 cts.; 12 for $1.75, postpaid**
**Not prepaid, 25 for $2.00; 50 for $3.50; 100 for $6.00; 500 for $25.00; $50.00 per 1,000**

# Salsify Also Known as Oyster Plant or Vegetable Oyster

CULTURE—Treat about the same as carrot, except that salsify is hardier, and may be left in the ground all winter. Sow in April or May in drills a convenient distance, 1 to 2 feet apart, and thin to 4 inches in the row. Cover seed about 1 inch. Use a packet to about 20 feet of drill, an ounce to 75 feet; 8 to 10 pounds per acre. Ready to use in about 140 days.

## ✱ 614 Mammoth Sandwich Island

**140 days. The Best Strain, with Large Smooth Roots**

This is an improved type and the largest and most profitable salsify now in cultivation. It is white in color; being quite smooth, is a satisfactory sort in every way.

**Packet 10 cts.; ounce 25 cts.; ¼ pound 70 cts.; ½ pound $1.25; pound $2.25; 5 pounds $10.00, postpaid**

616 Sorrel

# Sorrel Used as a Salad or Boiled and Served Like Spinach

CULTURE—Sow in early Spring or in August in drills 12 to 24 inches apart and cover seed lightly. Use a packet to 15 feet of drill, an ounce to 100 feet. Ready to use in about 60 days.

## 616 Large Leaved French

**60 days. The Pale Green Leaves Resemble Spinach**

The best garden variety, having large pale green leaves of fine quality, resembling spinach, only not so broad. Perfectly hardy; can be cut five or six times in a season.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

614 Mammoth Sandwich Island

# Fall and Winter Squashes

## ✻ 641 Blue Hubbard Squash

**65 days. Splendid for Pies. Good Keeper. An Excellent Shipper**

The Blue Hubbard is an entirely distinct variety, resembling the Chicago Warted Hubbard in size and shape, but the color is a clear blue gray. Matures in 65 days. The bright yellow thick flesh is fine grained, very dry, sweet and delightfully flavored. The Blue Hubbard is an exceptionally heavy cropper, producing an extraordinary number of squashes of even size, and has excellent qualities, keeping with proper storage as long as any of the Hubbards. Be sure to try this one in your garden, either for the home or market. An excellent shipper.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.50, postpaid**



641 Blue Hubbard Squash

## ✻ 634 New Kitchenette

**65 days. A Miniature Hubbard Squash**

This new squash is a trifle smaller than the old famous Hubbard. It is just the right size to sell on the market stall. The shell is dark green in color. Flesh dry and sweet in flavor. A good keeper. Excellent family garden sort.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

## 648 Chicago Warted Hubbard

**65 days. One of the Best of the Winter Keepers**

This is a distinct strain of the famous Hubbard and an ideal squash for home or market. The shell is deeply warted and a dark green in color, the flesh dry and sweet in flavor. It grows to a large size, its cooking qualities are unsurpassed. Matures in 65 days.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 25 cts.; ½ pound 45 cts.; pound 85 cts.; 5 pounds $3.75, postpaid**

## 645 Red or Golden Hubbard

**65 days. Golden Yellow Flesh of Excellent Flavor**

A valuable squash, a sport of the old Hubbard. It has the shape and virtues of its parent, differing in color of the skin which is deep yellow or orange red. Flesh richer in color than Hubbard, and of equal quality. Fine grained and sweet, cooking dry. It is a splendid keeper; matures in 65 days. A desirable home garden or market sort.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.25, postpaid**

## ✻ 630 New Acorn or Table Queen

**80 days. Good Family Size. The Last Word in Squash Quality**

The fruit is just the right size to cut in half and bake to serve one person amply, of good family size, 7 inches long by 5 inches thick. The hard shell is smooth dark green with sometimes a blotch of red at the pointed end, and keeps as well as the Hubbards. Flesh is a rich orange yellow which cooks as dry and sweet as a sweet potato, and if you like pie, try one from Table Queen. The vines are very productive and do not seem to be attacked by squash bugs. Matures in 80 days. A desirable home garden sort. It is comparatively new and has distinct merit.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

## 633 Banana Squash

**60 days. The Most Delicious of All for the Table or Pies**

A delicious squash that has become very popular, and is one of the best all purpose varieties ever grown. It can be used when quite young, or left to grow to a large size for winter use, often growing 20 to 36 inches long and 6 to 9 inches in diameter. The tough shell is a grayish green in color. The beautiful orange yellow flesh is firm and solid, free from fibre or stringiness, cooks smooth and of delicious flavor, excellent for pies, etc. Vines very productive. Matures in 60 days. Good winter keeper.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

## ✻ 635 Maule's Improved Hubbard

**65 days. The Acknowledged Standard for Quality**

Maule's Improved Hubbard represents the perfection of the type. It is the choicest type of Hubbard grown. The flesh is of a rich yellow or orange color, and is very fine grained, solid, dry and sweet. The toughness of the dark olive green rind or shell makes the squash a good winter keeper. Ready to pick in 65 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 30 cts.; ½ pound 50 cts.; pound 85 cts.; 5 pounds $4.00, postpaid**



635 Maule's Improved Hubbard Squash

## ✻ 642 Boston Marrow

**60 days. Rich, Sweet Flavor. Makes Good Pies**

This is a widely popular squash for autumn and winter use. Its color is a bright orange. Flesh is salmon yellow, rich and sweet. Matures in 60 days. Fine for making pies and largely used by canners.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.00, postpaid**

## 637 Essex Hybrid

**75 days. Hard Shell Turban**

Very large and smooth. Skin and flesh a rich orange red. Flesh thick and solid. The flavor is excellent. One of the most productive squashes. An extra good winter keeper. Matures in 75 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.35; 5 pounds $6.00, postpaid**

## 644 Mammoth Chili

**90 days. Largest of All Squashes**

The outer skin of this great squash is a rich orange yellow. The flesh is yellow and very thick, and the quality is good and nutritious. It is of the highest value as a stock food, far exceeding ordinary pumpkins in this respect, maturing in 90 days. It is a prolific variety, and a good winter keeper. Has reached the great weight of 100 pounds or more. It is a typical sort to grow for exhibition at the fairs.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25; 5 pounds $5.50, postpaid**

# Maule's Tomatoes

**Extra Early Varieties**
**Ready for Use in 80 to 90 Days**

Every garden should have an early as well as a main or general crop of tomatoes. Either for market or home use, the idea of growing rly tomatoes is to get them as soon as possible and follow up with the main crop, which may be used in many ways and are especially sirable for canning. Do not plant in over-rich soil as it will cause an over-growth of foliage and few fruits.

CULTURE—Sow the seed in February or March in a hotbed, greenhouse or in shallow boxes in the house in rows 4 to 6 inches apart and lf an inch deep. When the plants are about 2 inches high transplant to 3-inch pots or into shallow boxes 4 inches apart each way. Transant in the open ground after all danger of frost is past, 3 to 4 feet apart each way. Cultivate frequently. A packet will produce about 100 ants, an ounce about 3,500 plants, enough for an acre. Ready to pick in 80 to 120 days.

651 Maule's Earliest of All Tomato

## ✻ 651 Maule's Earliest of All

**80 days. The Greatest of All Early Tomatoes**

**Four Days to a Week Earlier Than Any Other Tomato**

(Bright Red.) If you have not given this wonderful variety a trial you will neglect your own interests if you do not include it in your order for 1927. Maule's Earliest of All is the best extra early tomato in America for the home or market gardener.

Nor is its extreme earliness its only virtue, for it is of large size, good color and delicious flavor. It does not crack and has no large core. Color is a bright red, a little irregular in shape, but not rough. Ready to pick in 80 days.

Pages of this Seed Book could be filled with statements and comments about the money value of this fine, early tomato. Maule's Earliest of All is all its name implies, namely: **the earliest tomato in existence**, notwithstanding the claims made for June Pink, Earliana, King of the Earlies, Wayahead, Chalk's Early Jewel, John Baer, etc.

**Packet 15 cts.; ½ ounce 30 cts.; ounce 50 cts.; ¼ pound $1.35; ½ pound $2.60; pound $5.00; 5 pounds $22.50, postpaid**

## ✻ 655 New Red Head

**) days. An Exceptionally Fine, Large, Bright Red Sort**

(Bright Red.) This wonderful new bright red tomato produces ceptionally fine, large and smooth, nearly globe-shape fruit, which very meaty and contains few seeds. The thick, solid flesh is of scious flavor. The vines are of medium growth and resistant to ght; extremely productive and bear continuously good size and ape, rich red colored tomatoes in 90 days. An excellent canning riety, or for the home garden it is one of the best, and is a oney maker for the market gardener.

**acket 10 cts.; ½ ounce 25 cts.; ounce 40 cts.; ¼ pound $1.00; ½ pound $1.85; pound $3.50; 5 pounds $15.00, postpaid**

## 659 Greater Baltimore

**90 days. Firm and Meaty. Excellent for the Table**

(Brilliant Red.) This grand, early variety produces large bright d tomatoes in clusters in about 90 days. The vines are vigorous, mpact and healthy growers; a heavy cropper of large, smooth, ll formed tomatoes; deep from stem to blossom end. Very firm d meaty. Free from ridges, cracks and blight. For canning or e home garden the results have been far beyond expectations.

**acket 10 cts.; ½ ounce 25 cts.; ounce 40 cts.; ¼ pound $1.00; ½ pound $1.85; pound $3.50; 5 pounds $15.00, postpaid**

## ✻ 654 Florida Special

**90 days. A Blight Resistant Red Tomato**

(Bright Red.) Florida Special resembles Chalks Early Jewel in size id shape, and has a beautiful bright red color, fine flavored, firm and eaty, which makes an excellent shipper. The vines, which resist the vages of blight, are very productive, producing tomatoes ready for ie market or table in about 90 days. You should not fail to include lorida Special in your order.

**acket 10 cts.; ½ ounce 25 cts.; ounce 45 cts.; ¼ pound $1.10; ½ pound $2.10; pound $4.00; 5 pounds $18.75, postpaid**

## 662 June Pink

**85 days. The Earliest of All Bright Pinks, a Pink Earliana**

(Bright Pink.) June Pink ripens in 85 days, as early as Earliana, markets where pink varieties are preferred it is a great seller. The ne is compact and branches freely, with handsome, good size, deep nk fruit hanging in clusters of 6 to 8 fruits. A popular market ariety, excellent for shipping, and equally desirable for home use.

**acket 10 cts.; ½ ounce 35 cts.; ounce 60 cts.; ¼ pound $1.75; ½ pound $3.25; pound $6.00; 5 pounds $27.50, postpaid**

## ✻ 657 Maule's Imperial

**90 days. The Truckers Favorite Purple Fruited Sort**

(Purplish Pink.) Maule's Imperial is unquestionably the best purple fruited tomato in the market today. Not quite as early as Maule's Earliest of All. The fruits are beautifully smooth, and in market this variety invariably commands the highest prices at all times and in all seasons.

Maule's Imperial, in color, is between pink-purple and glossy crimson. The flavor is of the best. It ripens evenly to the stem, and is highly productive, the yield under favorable field culture having reached 1½ bushels of ripe fruit per plant. It bears early, maturing in about 90 days, and produces fruit until frost. A desirable home garden or market tomato.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 40 cts.; ¼ pound $1.10; ½ pound $2.10; pound $4.00; 5 pounds $17.50, postpaid**

654 Florida Special Tomato

# Maule's Extra Early Tomatoes Ready for Use in 85 to 95 days

## ✻ 660 John Baer

**85 days. Extremely Early, Smooth, Solid and Meaty**

(Bright Red.) This grand early tomato produced in 85 days, very large and attractive bright red colored fruit. The introducer has this to say: John Baer produces large, beautiful, solid tomatoes which ripen early right up to the stem and is an enormous cropper, and when dead ripe will not burst. Unexcelled for early home or market use.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 40 cts.; ¼ pound $1.00; ½ pound $1.85; pound $3.50; 5 pounds $15.00, postpaid**

660 John Baer Tomato

## 663 Chalk's Early Jewel

**95 days. One of the Best Second Early Tomatoes for Home or Market**

(Bright Scarlet.) Within a week or ten days as early as Spark's Earliana, it is even a heavier cropper, with tomatoes of larger size and sweeter flavor, while its more robust growth makes it a sure cropper. Large, handsome fruits, very solid, deep through. Ripening right up to the stem without any cracks or green core. Ready to pick in 95 days. For the home garden or market it is one of the best.

**Packet 10 cts.; ½ ounce 20 cts.; ounce 35 cts.; ¼ pound 90 cts.; ½ pound $1.70; pound $3.25; 5 pounds $15.00, postpaid**

## 668 Gulf State Market

**95 days. A Blight Resistant, Pink Skin, Globe Shaped Tomato**

(Deep Purplish Pink.) This new globe-shape tomato was developed from Early Detroit and is as early as that variety. Matures in 95 days. The medium to large size fruits are almost true globe shape and are entirely free from cracks or blemishes about the blossom end. Flesh solid and meaty. Color deep purplish pink. A dependable long distance shipper. Its excellent qualities make it also a very desirable sort for the home gardener.

**Packet 10 cts.; ½ ounce 30 cts.; ounce 50 cts.; ¼ pound $1.35; ½ pound $2.65; pound $5.00; 5 pounds $22.50, postpaid**

658 Spark's Earliana Tomato

## 670 Redfield Beauty

**95 days. Excellent for the Home Garden or for Shipping**

(Glossy Purple.) Redfield Beaut has done so well in all sections tha it is a favorite everywhere. Produce a vigorous vine growth with lon bearing qualities, heavily laden wit large, glossy purple tomatoes, read to eat or ship in 95 days, of perfe shape, solidity and toughness of ski making it a valuable sort for mark gardeners for long distance shippin or market, as the skin does not brea easily. For the home garden it is ju right for shape, size, color, earline and bearing qualities, and is one the most satisfactory tomatoes grow for the table, or for slicing ar canning. Our seed was grown fro stock seed supplied by the introduce

**Packet 10 cts.; ½ ounce 25 cts.; ounce 40 cts.; ¼ pound $1.00; ½ pound $1.90; pound $3.75; 5 pounds $17.50, postpaid**

## 674 Golden Queen

**95 days. A Very Early, Large, Smooth, Yellow Tomato**

(Bright Yellow.) Early, large, bright golden yellow tomato. Sometimes with a slight blush of red. Size and shape like Matchless, except in color. Always smooth, and ripens in about 95 days. Quality excellent in all respects, either for slicing or preserving.

**Packet 10 cts.; ½ ounce 30 cts.; ounce 50 cts.; ¼ pound $1.35; ½ pound $2.65; pound $5.00, postpaid**



683 Bonny Best Tomato

## 678 Dwarf Champion

**95 days. The Best Pink Tree Tomato**

(Purplish Pink.) The famous Dwarf Champion tomato owe its wide popularity to its stiff, vigorous, upright growth, wit fruit well above the soil, and to its earliness; matures larg size fruit in 95 days. In color it is a purplish pink.

**Packet 10 cts.; ½ ounce 30 cts.; ounce 55 cts.; ¼ pound $1.50; ½ pound $2.85; pound $5.50, postpaid**

## ✻ 658 Spark's Earliana

**85 days. Extremely Early, Good Size and Quite Smooth**

(Scarlet Red.) Very popular with many growers of toma toes for early market. The fruits are of good size, scarl red color and crowded in clusters over the entire plant. A excellent first early tomato for home use. Matures its goo size red fruit in 85 days.

**Packet 10 cts.; ½ ounce 20 cts.; ounce 35 cts.; ¼ pound 90 cts.; ½ pound $1.70; pound $3.25; 5 pounds $15.00, postpaid**

## ✻ 683 Bonny Best

**88 days. Very Early, Large and Smooth; Heavy Cropper**

(Scarlet Red.) This variety is a vigorous grower; eno mously prolific. In shape it is slightly flattened but thick through than most other tomatoes. In color it is a beautif scarlet red, setting its fruit in clusters of five or more at clo intervals. Ready to pick in 88 days. Makes a magnifice variety for greenhouse growing. Also an excellent quali tomato for all purposes, growing in all sections.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 40 cts.; ¼ pound $1.00; ½ pound $1.85; pound $3.50; 5 pounds $15.00, postpaid**

# Maule's Main Crop Tomatoes Ready for use in 95 to 120 days

652 Maule's Success Tomato

## ✱ 652 Maule's Success Tomato

**100 days. The Best All Around Red Sort**

(Bright Red.) Maule's Success is smooth, well formed and extremely deep from stem to blossom, making it unusually heavy. It ripens evenly to the stem, and is without ridges or cracks; has great meatiness and few seeds. It is firm, without being hard. The vines are vigorous but compact. Maule's Success is the heaviest for its size of any variety; on account of its brilliant red color, depth and solidity, it is the handsomest main crop tomato we have ever seen. On the market stall its beautiful appearance and color make it sell ahead of all sorts, and its unusual solidity, few seeds and desirable form make it the most desirable canning variety known. Ready to pick in about 100 days.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 40 cts.; ¼ pound $1.10; ½ pound $2.25; pound $4.00; 5 pounds $18.75, postpaid**

## 653 Maule's Magnificent

**110 days. The Popular Large, Smooth Red Sort**

(Deep Red.) The vines give larger crops than other tomatoes of equal acreage. The fruit is large, solid and smooth. Ready to pick in 110 days. If you want an abundant crop of solid, smooth, deep red, meaty tomatoes that will be large and good, send for Maule's Magnificent. It is a good shipper, does not crack or rot; unsurpassed for the home garden, market or for canning.

**Packet 5 cts.; ½ ounce 20 cts.; ounce 35 cts.; ¼ pound 90 cts.; ½ pound $1.70; pound $3.25; 5 pounds $15.00, postpaid**

## ✱ 675 Golden Ponderosa

**110 days. Produces Golden Yellow Tomatoes in Great Size and Profusion**

(Golden Yellow.) This grand large tomato equals its famous parent, the Crimson Ponderosa, in every respect but color. The vines are vigorous, luxuriant and healthy and bear a tremendous load of tomatoes, right up to frost. The fruit is very uniform in shape and size and contains but few seeds. It is the largest and heaviest of the yellow sorts, free from acid, sweet and luscious, with very heavy meat. Ripens first fruit in about 110 days and continues to bear until frost. Excellent for slicing or for making into preserves.

**Packet 15 cts.; ½ ounce 40 cts.; ounce 70 cts.; ¼ pound $1.85; ½ pound $3.60; pound $7.00, postpaid**

## ✱ 665 Norton Wilt-Resistant

**120 days. Selected, Bred and Developed by the U. S. Department of Agriculture for Its Wilt-Resistant Qualities**

(Scarlet Red.) This new tomato was selected from the famous Stone, producing a heavy yield of large, smooth, solid scarlet red fruit which ripens in about 120 days. It is somewhat larger than Stone, and highly recommended because of its wilt-resistant features. If you have met with disappointment in growing tomatoes on account of wilt, you will be interested in this new variety. Norton produces a heavy crop either on wilt-infested soils or on soils that are free from wilt. An excellent tomato for canning, for the home garden, for market gardeners and for shipping.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 45 cts.; ¼ pound $1.25; ½ pound $2.40; pound $4.50; 5 pounds $20.00, postpaid**

665 Norton Wilt-Resistant Tomato

## ✱ 682 Ponderosa

**110 days. Nearly Seedless and as Solid as Beefsteak**

(Purple Crimson.) Although introduced many years ago, up to the present time no tomato has yet surpassed the genuine Ponderosa in size or delicious, meaty flavor. It is not only the largest but also the heaviest tomato grown. The color is a glowing purple crimson; shape quite regular considering its size, and it is considered by thousands of people the best table variety in existence for slicing, having but few seeds. Ripens in about 110 days, and bears well until very late. A good tomato for home use. We offer the genuine headquarter's stock.

**Packet 15 cts.; ½ ounce 35 cts.; ounce 65 cts.; ¼ pound $1.75; ½ pound $3.40; pound $6.50, postpaid**

## 679 Livingston's Globe

**95 days. Distinct Globe Shape, Firm and Blight Proof**

(Purplish Pink.) This tomato has become a leader with prominent and successful tomato growers. In shape it is distinct, being globe shape, which permits a greater number of slices to be made. Of large size, smooth, firm and has very few seeds. Color a glossy pink, tinged with purple. Bears fruit in clusters of from 3 to 7; ready to pick in 95 days. Of special value to all long distance shippers or for forcing under glass. An excellent home garden or market sort.

**Packet 10 cts.; ½ ounce 35 cts.; ounce 65 cts.; ¼ pound $1.75; ½ pound $3.40; pound $6.50, 5 pounds $30.00, postpaid**

# Maule's Main Crop Tomatoes Ready for use in 95 to 120 days

## ✱ 656 Maule's Enormous Tomato

**110 days. The Largest Red. The Sweetest of All**

(Deep Red.) Maule's Enormous tomato, bred by Mr. Miesse, was first introduced to the public by us under the name "Eight to the Yard." Maule's Enormous, however, was not bred merely for large size. The name was selected from the fact that it seemed to apply better to this wonderful tomato than to any other. In comparative trials with other sorts, under ordinary conditions, Maule's Enormous has made a record for both quality and quantity, while the beauty of the fruit makes it an easy and quick seller in all markets. The fruit is remarkably solid and firm. Enormous is now universally recognized as a standard main crop red tomato, of great size and productive ability. Ready for the table or market in about 110 days.

**Packet 15 cts.; ½ ounce 35 cts.; ounce 60 cts.; ¼ pound $1.75; ½ pound $3.25; pound $6.00; 5 pounds $28.75, postpaid**

656 Maule's Enormous Tomato

## 666 Dwarf Stone

**100 days. The Largest Red Dwarf Tree Sort**

(Bright Red.) This strain of Dwarf Stone tomato is more productive, earlier and larger fruited than any other so-called tree sort. In fact, it is about the largest of all the dwarf or bush red skin varieties, very meaty and delicious. Ready to pick in 100 days.

**Packet 10 cts.; ½ oz. 25 cts.; oz. 45 cts.; ¼ lb. $1.25; ½ lb. $2.40; lb. $4.50, postpaid**

## ✱ 672 New Stone

**120 days. The Standard Main Crop Variety for the Garden or Canners**

(Bright Red.) The fruit is of good size, bright red in color, perfectly smooth and of the best table quality. It is a famous main crop tomato; unsurpassed for slicing or canning. Matures in 120 days. The plants are productive.

**Packet 10 cts.; ½ oz. 25 cts.; oz. 40 cts.; ¼ lb. $1.00; ½ lb. $1.85; lb. $3.50; 5 lbs. $15.00, postpaid**

672 New Stone Tomato

## 664 Matchless

**120 days. A Large Red Tomato Well Named**

(Deep Red.) One of the best an most popular for general planting. Th color is a rich deep red. Fruit is larg very smooth, solid. Absence of core, to gether with its freedom from rot, a unite in making this grand tomato we worthy of the name of "Matchless. Always large, even at the end of th season. Fine, both for the private an market garden and canning. Th Matchless is what we would call thoroughly dependable tomato.

**Packet 10 cts.; ½ oz. 25 cts.; oz. 40 cts.; ¼ lb. $1.00; ½ lb. $1.85; lb. $3.50; 5 lbs. $15.75, postpaid**

## 676 Pear-Shaped Red

**95 days. Used for Making Tomato Figs or Preserving**

(Bright Red.) Fruit small and pear shaped, about the size of a plum; colo bright red. Ripens in about 95 day Flesh tender and of good flavor. Exce lent for preserves or canning.

**Packet 10 cts.; ½ oz. 35 cts.; oz. 60 cts.; ¼ lb. $1.75; ½ lb. $3.25; lb. $6.00, postpaid**

## 677 Pear Shaped Yellow

**95 days. Used for Pickling and Preserving**

(Bright Yellow.) A small early tomato, ready to pick in 95 days. Similar to pear-shaped red, but of rich, clear yellow color. Very sweet, and free from acid. Very desirable for preserving, canning or making fancy pickles.

**Packet 10 cts.; ½ ounce 35 cts.; ounce 60 cts.; ¼ pound $1.75; ½ pound $3.25; pound $6.00, postpaid**

### MATURITY DATES

**At the heading of all VEGETABLE SEED descriptions we are giving the maturity dates, starting from day of sowing the seed, thus: 110 days. This will tell you when you may expect vegetables ready for the table; of course the weather conditions must be favorable for producing the crop.**

667 Cooper's Special Tomato

## ✱ 680 Maule's Columbia Wilt-Proof

**110 days. A Wonderful Cropper. The Greatest Tomato**

(Bright Red.) Columbia is a very large, smooth tomato, well formed and deep from stem to blossom. It is of a bright red colo and ripens up to the stem; flesh is solid, with very few seeds. Th wilt-resistant foliage is larger and much heavier than Matchless It is a wonderful bearer, outyielding many of the best croppin sorts. Tomatoes run more uniform than any other variety, an it does not have as many small fruits in the latter part of th season, a fact that will be greatly appreciated by all growers Ready to pick in 110 days. Splendid for market gardeners, hom gardeners or canners wanting a strictly large, fancy tomato.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 45 cts.; ¼ pound $1.25; ½ pound $2.40; pound $4.50; 5 pounds $20.00, postpai**

## ✱ 667 Cooper's Special or Self-Pruning

**95 days. Distinct in Growth, Pink Fruited and Globe Shaped**

(Purplish Pink.) A new tomato of recent introduction becomin very popular with Florida growers on account of being what the term a self-topper. The vines produce a limited number of sid shoots close to the ground and branch but little on the upper pa of the vines. The vines are shorter than any of the original ta vine sorts. The fruits are set in clusters of 4 to 5 fruits every 5 t 6 inches along the vines. They are perfectly smooth, firm fleshe and solid, of good size but not as large as Livingston's Globe whic it resembles. The color is a bright purplish pink. Matures in 9 days. A good long distance shipper, also an excellent home c market gardener's sort. Does well in all sections, North or Soutl

**Packet 15 cts.; 2 packets 25 cts.; ½ ounce 40 cts.; ounce 75 cts.; ¼ pound $2.00; ½ pound $3.85; pound $7.50; 5 pounds $35.00, postpai**

# MAULE'S GARDEN TURNIPS

CULTURE—Sow early flat varieties in April, in drills 12 to 18 inches apart. Cover seed ½ inch and thin out to 4 to 6 inches in the row. Cultivate frequently. For succession, sow at intervals until the last week in May. For Fall and Winter crop, sow in July or August in drills or broadcast. A packet will sow about 50 feet of drill, an ounce about 250 feet; 1½ pounds to acre in drills or 2½ pounds broadcast. Ready to use in 45 to 75 days. After a few light frosts take up roots and store in a cool cellar or pit outdoors for winter use.

## 686 Red or Purple Top White Globe Turnip

**65 days. The Popular Variety for General Planting**

One of the handsomest and most salable turnips. Adapted to any soil or section. It is a large, rapid growing sort, being ready for the table or market in about 65 days, with globular shaped roots of attractive appearance. Flesh pure white, fine grained and tender, and is the best flavored of all turnips, raw or cooked. The skin is white, with a purple or dark red top. This sort keeps well for so early a variety and is one of the best all purpose white turnips for the kitchen garden or for market use. The most desirable sort.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 25 cts.; ½ pound 40 cts.; pound 75 cts.; 5 pounds $3.25, postpaid**

695 Early White Flat Dutch Turnip

686 Red or Purple Top White Globe Turnip

**Order by Number or Name**

Order all SEEDS or COLLECTIONS by NUMBER or NAME. If by NUMBER only, be sure to give CORRECT NUMBER.

## ✱ 695 Early White Flat Dutch

**50 days. Held in High Esteem by All Growers**

A flat, smooth, white turnip; one of the best for the family garden in the spring, also grown for a fall crop. Medium size; matures in about 50 days. Skin is clear white; flesh excellent, mild, juicy. A good keeper.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 20 cts.; ½ pound 30 cts.; pound 50 cts.; 5 pounds $2.25, postpaid**

## 700 Large White Norfolk Globe

**75 days. Excellent for Table or Winter Salad**

A popular variety for winter. Makes large, round white roots; flesh white, solid, sweet and fine grained, maturing in about 75 days. Excellent for table or stock; also quite largely used for winter salad.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 25 cts.; ½ pound, 40 cts.; pound 65 cts.; 5 pounds $2.75, postpaid**

## 697 Cow Horn

**75 days. Excellent for the Table or Stock**

A long white turnip, 12 to 15 inches in length, 2½ inches in diameter and growing well above the ground. Of rapid growth, producing large, heavy roots in 75 days. One of the best and sweetest for home use or for stock feeding, and excellent to plow under as a green fertilizer.

**Packet 5 cts.; ounce 10 cts.; pound 25 cts.; ½ pound 40 cts.; pound 65 cts.; 5 pounds $2.75, postpaid**




## 704 Japanese Turnip

**70 days. A Large, Tender and Sweet Turnip**

This turnip is a large white variety, of great merit, and comes directly from Japan; in fact, the seed which we offer was actually grown in Japan, and was imported expressly for this season's sales. The shape of the turnip is between flat and globe. The color is pure white, both outside and inside, except that there is a pale tinting of green on top, near the leaves. As it is a large turnip it has correspondingly large and vigorous leaves. It is solid and meaty in flesh. As a heavy cropper and reliable winter keeper it cannot be excelled, and we are able to recommend it highly to all growers. It will be found adapted to table use as well as to stock. Maturing in 70 days.

**Packet 10 cts.; ounce 25 cts.; ¼ pound 65 cts.; ½ pound $1.10; pound $2.00; 5 pounds $8.75, postpaid**

## ✱ 687 Red or Purple Top Strap Leaf

**55 days. A Very Quick Grower and a Good Keeper**

Fine grained, never stringy and of mild flavor. It is white below with a bright purple top; flesh white, leaves short, narrow and erect. Will mature in 55 days. Desirable for the home garden or market.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 20 cts.; ½ pound 35 cts.; pound 60 cts.; 5 pounds $2.50, postpaid**

## ✱ 694 Extra Early White Milan

**45 days. Sweet and Tender**

An excellent extra early white flat turnip, maturing in about 45 days. Mild flavor, and fine grained. Desirable for spring or fall sowing.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 35 cts.; ½ pound 60 cts.; pound $1.00; 5 pounds $4.00, postpaid**



694 Extra Early White Milan Turnip

## ✱ 698 Golden Ball

**65 days. The Best for Family Gardens**

A superior table turnip, of bright yellow color. Rich and sweet in flavor. A rapid grower, producing handsome globular shaped roots in 65 days. An excellent keeper. Makes an ideal fall crop to store for winter use.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 25 cts.; ½ pound 40 cts.; pound 70 cts.; 5 pounds $3.00, postpaid**

Turnips continued on pages 72 and 73

698 Golden Ball Turnip

## ✱ 693 Extra Early Purple Top Milan

**45 days. The Earliest and Best for Spring or Fall Sowing**

The earliest of all turnips, producing in 45 days good sized, flat, smooth turnips with bright purple top and few leaves, of perfect shape and color. Flesh white and choice, sweet and fine grained. They are without equal for the table. Adapted to spring and fall planting outdoors, and is especially desirable for forcing under glass for early use.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 25 cts.; ½ pound 40 cts.; pound 75 cts. 5 pounds $3.25, postpaid**

693 Extra Early Purple Top Milan Turnip

## 691 Southern Seven Top

**30 days. *Known as the Salad Turnip***

A variety of turnip grown entirely for its tops, which are used as a salad. Can be cut at all times. This is a very hardy sort, standing through the winter.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 25 cts.; ½ pound 40 cts.; pound 65 cts.; 5 pounds $2.75, postpaid**

## 692 Yellow Aberdeen

**75 days. Long Keeping, Sweet Yellow Flesh**

A turnip of high merit. The flesh is yellow, tender, sugary and very sol In color the turnip is purple above and deep yellow below. Producing large roc which resemble ruta bagas in 75 days. Used on the table or for stock feedir

**Packet 10 cts.; ounce 15 cts.; ¼ pound 25 cts.; ½ pound 40 cts.; pound 65 cts.; 5 pounds $2.75, postpaid**

699 Petrowski Turnip

## ✱ 696 White Six Weeks

**55 Days. *Known as Early Snowball***

This globe-shaped white skinned early turnip is large, smooth and handsome; flesh white and of mild flavor, an excellent winter keeper, maturing its crop in about 55 days.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 20 cts.; ½ pound 30 cts.; pound 50 cts.; 5 pounds $2.25, postpaid**

## ✱ 699 Petrowski

**50 days. The Quickest Growing Yellow Table Turnip**

A distinct variety, and is one of the most delicately flavored of the yellow fleshed turnips. The roots are of medium size, flat in shape, perfectly smooth, and of a rich orange-yellow color. The flesh is a beautiful light orange, fine grained, tender and sweet. This variety is of quick growth, maturing in 50 days. Adapted to Spring as well as late Summer planting. Can be sown as late as August for Winter storing and keeps exceptionally well. Do not fail to plant Petrowski in your garden. It grows rapidly from the vary start; its flavor is most pleasing.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 25 cts.; ½ pound 40 cts.; pound 65 cts.; 5 pounds $2.75, postpaid**



696 White Six Weeks Turnip

## 690 Yellow Stone

**75 days. *A Good Winter Keeper***

This favorite sort is a sure cropper, maturing in 75 days, globe-shaped, perfectly smooth, light yellow in color, fine grained, sweet, and of exceptionally mild flavor. Good table sort.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 20 cts.; ½ pound 30 cts.; pound 50 cts.; 5 pounds $3.25, postpaid**

## 703 White Globe 70 Days. *Extra Large, Round, Pure White*

This is one of the most productive turnips and in good rich soil the roo grow large. It is globe-shaped. The skin is white and smooth.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 25 cts.; ½ pound 40 cts.; pound 65 cts.; 5 pounds $2.75, postpaid**

702 Large Yellow Globe Turnip

## ✱ 702 Large Yellow Globe

**75 Days. *Fine for the Table or Stock***

Globe shape, pale yellow with green top. The skin is smooth, yellow flesh, firm and sweet, maturing in about 75 days. A splendid keeper.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 20 cts.; ½ pound 30 cts.; pound 50 cts.; 5 pounds $2.25, postpaid**

## ✱ 701 White Egg

**50 days. *Solid, Fine Grained, Good Keeper***

Egg-shaped root; with white skin. The white flesh is always firm, solid, sweet, a quick growing sort, maturing in about 50 days. A good keeper.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 20 cts.; ½ pound 35 cts.; pound 60 cts.; 5 pounds $2.50, postpaid**

## 689 Mixed Table Turnips

**45 to 75 days. *A Grand Mixture***

A grand mixture of garden turnips, including both white and yellow flesh varieties. This mixture matures its crop in 45 to 75 days.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 25 cts.; ½ pound 40 cts.; pound 65 cts., postpaid**

701 White Egg Turnip

# RUTA BAGAS or SWEDE TURNIPS

CULTURE—Does best on new land, or light and sandy soil. Sow the seed from the latter part of June until August in drills to 24 inches apart. Cover seed ½ inch and thin out to 6 to 8 inches in the rows. Cultivate frequently. Can be sown broadcast. Use a packet to about 50 feet of drill, an ounce to 250 feet, 1½ pounds to the acre in drills or 2½ pounds broadcast. Ready to use in 80 to 95 days.



## ✻707 Maule's Heavy Cropping

**90 days. The Perfect Ruta Baga, with Firm Yellow Flesh**

Maule's Heavy Cropping Ruta Baga is more largely grown than any other variety. It is the most profitable to grow of all yellow purple top Swede turnips, being the hardiest, heaviest, best shaped and most productive. The roots are better keepers than most sorts. The flesh is of a beautiful yellow color, of the choicest quality, full of nourishment. Excellent for table use and stock feeding. Matures in 90 days.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 25 cts.; ½ pound 40 cts.; pound 75 cts.; 5 pounds $2.25, postpaid**

## ✻708 Improved Purple Top or Long Island

**90 days. Very Richly Colored, Fine Grained and Sweet**

Next in yield and value after our Heavy Cropping Swede, we place this old standard variety. It is of fine quality and is widely grown. It keeps perfectly all winter. It is hardy, productive, sweet, solid and satisfactory. It is globe shaped, purple top, yellow skin and flesh. With smaller top and shorter neck than most sorts. It is justly held in high esteem for both table and stock feeding purposes.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 25 cts.; ½ pound 40 cts.; pound 65 cts.; 5 pounds $2.75, postpaid**

## ✻710 Maule's Golden Heart

**80 days. The Quickest Grower and a Sure Cropper**

This grand Ruta Baga is large, perfect in shape, uniform in size and the quickest grower we know of. Roots are globe shape, smooth; flesh yellow, fine grained, solid, tender and sweet. A sure cropper; a perfect winter keeper. Can be planted as late as August 15th, in the vicinity of Philadelphia, producing a crop when other sorts fail. Matures in 80 days. An excellent home garden or early market sort.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 70 cts.; pound $1.25; 5 pounds $5.25, postpaid**

## 711 White French or Sweet Russian

**90 days. Hardy, Pure White, Good Keeper**

Grows to a large size, and is most excellent for table use or for live stock. Roots are large, nearly globe shaped, with a small neck, color white with a green shade at the neck. The white flesh is firm, rich and of sweet nutritious quality. Matures in 90 days.

**Packet 5 cts.; ounce 10 cts.; ¼ pound 25 cts.; ½ pound 40 cts.; pound 65 cts.; 5 pounds $2.75, postpaid**



## ✻713 White Rock, Known as Breadstone

**90 days. A Reliable Keeper**

This fine grade white ruta baga is an American variety and in all sections it has long had an enviable reputation as an extra good cropper and reliable keeper. Roots large, nearly globe shape, small neck, firm and sweet, with a shade of green or bronze at the top; flesh white. Matures in 90 days. It is equally desirable for table purposes or for stock feeding.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 25 cts.; ½ pound 40 cts.; pound 65 cts.; 5 pounds $2.75, postpaid**

## Mulford Cultures

FOR LEGUMES

For inoculating all Clovers, Vetch, Garden Beans, Garden Peas, Soy Beans and Cow Peas. Be sure to specify which one you want to inoculate, as there is a different culture for each.

### Prices for Mulford Cultures

| FOR SMALL SEEDS | | FOR LARGE SEEDS | |
|---|---|---|---|
| Alfalfa | Crimson Clover | Garden Peas | Cow Peas |
| Sweet Clover | White Clover | Garden Beans | Soy Beans |
| Red Clover | Alsike Clover | Vetch | |
| 10 Bushel size | $8.00 | 20 bushel size | $8.00 |
| 2½ " " | 2.25 | 5 " " | 2.25 |
| 1 " " | 1.00 | 2 " " | 1.00 |
| ½ " " | .60 | 1 " " | .60 |

All Sizes of Mulford Cultures Are Postpaid

708 Improved Purple Top Ruta Baga

713 White Rock Ruta Baga

# Maule's Farm and Grain Seeds

The following varieties of field and grain seeds are especially adapted to Spring, Summer and Fall sowing. In the description of each variety we give the quantity of seed required to plant an acre. Write for special prices on larger quantities. We make no charge for bags. **All prices on pages 74 to 80 are subject to change without notice.**



## 856 Mammoth Russian Sunflower

Flowers 18 to 20 inches in diameter. Very showy, and largely grown for the amount of seed produced. Stalks often grow 10 feet high. Plant in hills, 3½ to 4 feet apart each way, allowing 3 to 4 plants to each hill, or in drills; 5 pounds will sow an acre. Cultivate the same as corn.

**Packet 10 cts.; ½ pound 20 cts.; pound 35 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 6¼ lbs. (peck) 75 cts.; 25 lbs. (bushel) $2.75**

## 789 Japanese Buckwheat

The best and most profitable variety. From ½ bushel of seed sown a crop of 40 bushels has been harvested. Flour is superior to that from any other variety. Ripens early. Sow 36 pounds in drills or 48 pounds broadcast per acre.

**Packet 10 cts.; pound 30 cts.; 3 pounds 75 cts., postpaid**
**Not prepaid, 12 lbs. (peck) 75 cts.; 48 pounds (bushel) $2.50**

## 787 Imp. Evergreen Broom Corn

The best. Brush firm, of good length and bright green color. The standard sort. Sow in drills, using 10 to 12 pounds of seed per acre.

**Packet 10 cts.; pound 30 cts.; 3 pounds 90 cts., postpaid**
**Not prepaid, 11½ lbs. (peck) $1.00; 46 lbs. (bushel) $3.50**

## 849 Spring Rye

Used with profit as a catch crop where grain has winter killed. Quite commonly employed recently. Sow 84 lbs. to 112 lbs. to acre.

**Packet 10 cts.; pound 30 cts.; 3 pounds 75 cts., postpaid**
**Not prepaid, 14 lbs. (peck) 90 cts.; 56 lbs. (bushel) $3.00**

## 831 Thousand Headed Kale

Produces plants growing 3 to 4 feet high; the stems are covered with rosettes of leaves. It is a heavy cropper, often yielding 10,000 lbs. per acre in one season. All fowls and animals, especially hogs and sheep, eat it greedily. Hardy and will thrive on most any soil. Sow 2 pounds per acre in rows or broadcast.

**Packet 10 cts.; ¼ pound 25 cts.; ½ pound 45 cts.; pound 75 cts.; 5 pounds $3.25, postpaid. Not prepaid, 5 pounds $2.75**

787 Imp. Evergreen Broom Corn



783 White Swiss Barley

## 860 Hairy or Winter Vetch

This useful plant is noted for its extreme hardiness. As a winter cover crop, to prevent leaching, as well as for grazing, hay and fertilizing purposes, it is one of the best. Sow 90 pounds of seed per acre alone, or 60 pounds of Vetch with 28 pounds of winter rye or oats.

**Packet 10 cts.; pound 50 cts.; 3 pounds $1.25, postpaid**
**Not prepaid, 15 lbs. (peck) $3.25; 60 lbs. (bushel) $12.75**

## 861 Spring Vetch

Spring Vetch or Tares is a rapid grower and should be sown in May or June. It is highly recommended for making a fine grade of hay, for excellent grazing or for turning under to improve the land. It makes a splendid substitute for clover for sections or on lands that will not grow clover. It is much relished by all stock. It is very rich, nutritious, containing even more protein than alfalfa. Sow 90 pounds per acre alone, or 60 pounds of Vetch with 28 pounds of spring wheat, rye or oats.

**Packet 10 cts.; pound 35 cts.; 3 pounds $1.00, postpaid**
**Not prepaid, 15 lbs. (peck) $1.75; 60 lbs. (bushel) $6.00**

## 863 Marquis Spring Wheat — The Popular Milling Sort

A wonderful variety which has become popular and met with widespread interest. It is remarkably early, pale red grained and exceedingly productive. Sow at the rate of 90 pounds to 120 pounds per acre.

**Packet 10 cts.; pound 30 cts.; 3 pounds 75 cts., postpaid**
**Not prepaid, 15 lbs. (peck) $1.00; 60 lbs. (bushel) $3.75**

## 783 White Swiss Barley — The Heaviest Yielding Six Rowed Bearded Sort

The straw is very strong and stiff, growing from 36 to 40 inches high. The heads are of the bearded type, long and well filled with six rows of plump grains of the finest quality. It yields abundantly, 50 to 68 bushels to the acre. An excellent variety for growing on light, thin soils, while on rich, fertile soils its yields are wonderful. It is a great drought resister and especially adapted to Northern latitudes. For yield, malting, milling and feeding has no superior. 96 pounds of seed usually sown to an acre.

**Packet 10 cts.; pound 30 cts.; 3 pounds 75 cts., postpaid**
**Not prepaid, 12 lbs. (peck) 65 cts.; 48 lbs. (bushel) $2.00**

## 841 Improved Swedish Oats — A Wonderful Stooler and Reliable Yielder

The heaviest yielding white seeded branch oats for spring sowing, ranking first in weight, stiffness of straw and thin hulling qualities. The stiff straw which holds up unusually well grows from 4 to 5 feet tall with heads measuring from 8 to 11½ inches long and produces grain weighing from 36 to 40 pounds to the measured bushel. These oats are quite early, less liable to smut or rust than other sorts. Sow at the rate of 64 to 96 pounds to the acre.

**Packet 10 cts.; pound 30 cts.; 3 pounds 75 cts., postpaid**
**Not prepaid, 8 lbs. (peck) 50 cts.; 32 lbs. (bushel) $1.35; 320 lbs. (10 bushels) $12.50**

841 Improved Swedish Oa

**Customers may order half-pecks at the peck rate, half bushels at the bushel rate. BAGS FREE.**

# Sorghums and Forage Crops

## MILLETS

*Fine hay of excellent feeding value. Much used as a catch crop. Ready to cut in 45 to 65 days.*

### 834 Hungarian Millet

Often called Hungarian grass. In general favor for summer forage purposes, as it can be sown in June and can be cut in 60 days. Yields 2 or 3 tons of hay per acre. It grows well on light soils, and withstands heat and drought. Sow seed broadcast; 48 pounds to the acre.

**Packet 10 cts.; pound 30 cts.; 3 pounds 75 cts., postpaid**
**Not prepaid, 12 lbs. (peck) $1.00; 48 lbs. (bushel) $3.50**

### 835 Japanese Millet

Widely advertised as the Billion Dollar, also barnyard grass. It attains a height of 7 feet. The yield per acre is at the rate of 6 to 8 tons of cured hay and 15 to 18 tons of green forage. A field sown July 26th, after a hay crop, yielded 12 tons per acre. Valuable for forage or the silo. Sow 12 to 15 pounds per acre.

**Packet 10 cts.; pound 30 cts.; 3 pounds 75 cts., postpaid**
**Not prepaid, 7½ lbs. (peck) 75 cts.; 30 lbs. (bushel) $2.50**

### 833 German or Golden Millet

German millet is a fine crop for both soiling and hay. For the latter purpose it must be cut just as it begins to head before blooming. It is ready for use in 60 or 65 days after sowing. When used at the proper stage of development it is one of the most valuable of soiling plants. Sow 48 pounds per acre for hay.

**Packet 10 cts.; pound 30 cts.; 3 pounds 75 cts., postpaid**
**Not prepaid, 12 lbs. (peck) 90 cts.; 48 lbs. (bushel) $3.25**

### 836 Pearl or East Indian Millet

Also called Pencillaria or Cattail Millet. This fodder plant grows 6 to 10 feet high, and furnishes an enormous bulk of fodder. It can be cut several times during the season. It produces long, broad leaves somewhat resembling Indian corn. The stem is stout, and the terminal spike is 6 to 12 inches in length. Sow in drills 3 feet apart, using 5 pounds of seed per acre; or broadcast, sowing 8 pounds to the acre.

**Packet 10 cts.; pound 40 cts.; 3 pounds $1.00, postpaid**
**Not prepaid, 12½ lbs. (peck) $2.00; 50 lbs. (bushel) $7.00**

833 German Millet

### 854 Texas Seeded Ribbon Cane — The Favorite for Syrup

A saccharine sorghum. One of the best varieties for making syrup and used extensively for that purpose. This variety will grow anywhere that sorghum will grow and produces a larger yield. The stalks grow 12 to 16 feet high and mature early. Sow seed broadcast, using 50 pounds per acre or in drills 12½ pounds of seed per acre.

**Packet 10 cts.; pound 35 cts.; 3 pounds 90 cts., postpaid**
**Not prepaid, 12½ lbs. (peck) $1.25; 50 lbs. (bushel) $4.75**

### 852 Early Amber Sorghum — Relished by All Kinds of Stock

A saccharine sorghum. An early Southern variety grown almost exclusively for forage crop either alone or broadcast with peas. Sow broadcast alone 50 pounds seed per acre. If with peas broadcast, use 25 pounds seed with 60 pounds peas per acre.

**Packet 10 cts.; pound 30 cts.; 3 pounds 75 cts., postpaid**
**Not prepaid, 12½ lbs. (peck) $1.00; 50 lbs. (bushel) $3.25**

835 Japanese Millet

### 819 White Kaffir Corn — Relished by Poultry and Cattle

A valuable non-saccharine sorghum, producing two to four heads per stalk. The stalks make excellent fodder, the grains make fine poultry and stock food, also splendid flour. For grain, use 4 to 5 pounds of seed per acre; for fodder, sow 28 to 56 pounds in drills or broadcast.

**Packet 10 cts.; pound 30 cts.; 3 pounds 75 cts., postpaid. Not prepaid, 14 lbs. (peck) 75 cts.; 56 lbs. (bushel) $2.50**

### 818 Red Kaffir Corn

**Excellent Fodder; Either Green or Dry**

This non-saccharine sorghum is the same as White Kaffir Corn, with exception of color of grain, which is red. A heavy cropping sort.

**Packet 10 cts.; pound 30 cts.; 3 pounds 75 cts., postpaid**
**Not prepaid, 14 lbs. (peck) 85 cts.; 56 lbs. (bushel) $3.00**

### 850 Shallu or Egyptian Wheat

**Makes Nutritious Flour**

A non-saccharine sorghum, producing very large yields of both grain and fodder. On account of its stooling habit, 3 to 6 stalks are produced from a single grain. Seed white. An excellent feed for all stock. Use 3 to 5 pounds in hills or for fodder sow 25 to 50 pounds to the acre.

**Packet 10 cts.; pound 35 cts.; 3 pounds 90 cts., postpaid**
**Not prepaid, 14 lbs. (peck) $1.50; 56 lbs. (bushel) $5.50**

### 839 Yellow Milo Maize — Excellent for Ensilage

A non-saccharine sorghum; cultivated like corn. A vigorous grower, attaining a height of 10 feet. It will stand great drought and for this reason is admirably adapted to dry land farming. The seed is fed to chickens, etc. Matures its main head in 100 days. Plant 4 to 5 pounds per acre.

**Packet 10 cts.; pound 30 cts.; 3 pounds 75 cts., postpaid**
**Not prepaid, 14 lbs. (peck) 75 cts.; 56 lbs. (bushel) $2.50**

### 830 Feterita — The Great Drought Resister

A non-saccharine sorghum, maturing its crop earlier than Kaffir Corn. Grows about 5 feet high. Excellent for feeding chickens or any stock. For grain, sow 5 pounds of seed per acre in hills or drills. For fodder, sow 28 pounds per acre, broadcast or in rows.

**Packet 10 cts.; pound 30 cts.; 3 pounds 75 cts., postpaid**
**Not prepaid, 14 lbs. (peck) $1.00; 56 lbs. (bushel) $3.50**

830 Feterita

### 847 Dwarf Essex Rape

**Gives a Tremendous Yield and a Luxuriant Pasture**

This is the best early summer or autumn forage known; used for sheep, pigs and cows with success and profit. Under favorable circumstances it is ready for pasturage in six weeks from the time of sowing. It is grown exclusively for its leaves. Rape is a plant which loves cool weather, and thrives best in spring or autumn. The seed should be used at the rate of 3 pounds per acre in drills, or 5 pounds per acre broadcast. Rape is an excellent food for chickens or for green manure for plowing down.

**Packet 10 cts.; pound 35 cts.; 3 pounds 90 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 3 lbs. 55 cts.; 5 lbs. 75 cts.; 10 lbs. or over at 12 cts. per pound**

### 829 Canada Field Peas — Sown with Oats Makes Good Feed for Cows

Makes good ensilage, and is an admirable food, either green or dry, for cattle. It is quite hardy, may be sown early in the spring. Sow at the rate of 120 pounds per acre alone, or 60 pounds of Canada Peas mixed with 48 pounds of oats.

**Packet 10 cts.; pound 35 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 15 lbs. (peck) $1.25; 60 lbs. (bushel) $4.75**
**5 bushels or over at $4.50 per bushel**



## Speltz 851 or Emmer

*Yields More than Wheat or Barley*

It ripens early; the grain is intermediate between wheat and barley. The chaff adheres to the grain when threshed, and is fed in that condition to stock. It is adapted for milling purposes, as well as for feeding, making a grade somewhat similar to rye. The straw resembles wheat straw. It grows large crops—40 to 80 bushels per acre—on comparatively poor soil, and it is said to give full double the crop of barley. It resists drought successfully, and is adapted to Northern latitudes. Sow in the spring or in the fall at the rate of 80 pounds per acre.

**Packet 10 cts.; pound 30 cts.; 3 pounds 75 cts., postpaid. Not prepaid, 10 lbs. (peck) 75 cts.; 40 lbs. (bushel) $2.25**

INOCULATE THIS SEED WITH MULFORD CULTURE

# Cow Peas

**Makes Fine Hay When Cut. A Great Soil Enricher.**

INOCULATE THIS SEED WITH MULFORD CULTURE

Cow Peas may be sown during May, June or July at the rate of 60 to 90 pounds per acre.

## 823 New Era

60 days. The Earliest

An early maturing variety of quick, upright growth. The vines make a splendid dry forage, cure easily, and produce a heavy yield of peas. Maturing in about 60 days; valuable in sections where the season is short.

**Packet 10 cts.; lb. 35 cts.; 5 lbs. $1.50, postpaid**
**Not prepaid, 15 lbs. (peck) $1.25;**
**60 lbs. (bushel) $4.75**
**5 bushels or over at $4.50 per bushel**

## 824 Extra Early Black Eye

**65 days. Dry Peas are Desirable for Home or Market Use**

A strong grower and moderate trailer. Mature seed in about 65 days. In the South it is grown mainly for table use.

**Packet 10 cts.; lb. 40 cts.; 5 lbs. $1.75, postpaid**
**Not prepaid, 15 lbs. (peck) $1.50;**
**60 lbs. (bushel) $5.75**
**5 bushels or over at $5.50 per bushel**

## 827 Whip-poor-will

70 days. The Favorite

It is an early variety, and matures in about 70 days. It is not a heavy forage maker, but a very productive variety and largely grown as a soil improver and for pasturage. Trails very little and usually in bush form.

**Packet 10 cts.; lb. 35 cts.; 5 lbs. $1.50, postpaid**
**Not prepaid, 15 lbs. (peck) $1.25;**
**60 lbs. (bushel) $4.75**
**5 bushels or over at $4.50 per bushel**

## 828 Mixed Cow Peas

60 to 70 days

Where the crop is wanted for soil improving, pasturage, silage or hay crop, this mixture is very satisfactory, producing a thick growth of vines and forage.

**Packet 10 cts.; lb. 35 cts.; 5 lbs. $1.50, postpaid**
**Not prepaid, 15 lbs. (peck) $1.25;**
**60 lbs. (bushel) $4.75**
**5 bushels or over at $4.50 per bushel**

Soja Beans

INOCULATE THIS SEED WITH MULFORD CULTURE

# Soja Beans

***One of the Best Summer Forage Crops Grown Anywhere***

Sow Soja Beans in May or June, using 60 pounds per acre in drills or broadcast for hay; 30 pounds for beans. Can also be sown with cow peas using 30 pounds of each per acre, well mixed.

## 784 Wilson Black

The Earliest Soja Bean

A very satisfactory variety to grow in the Northern States where a quick early shell bean or hay variety is desired. The plants average 2½ to 3 feet in height on good land. It branches well and is a prolific cropper. Requires about 90 days to be ready to cut for hay, maturing seed in about 115 days.

**Packet 10 cts.; pound 35 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 15 lbs. (peck) $1.00;**
**60 lbs. (bushel) $3.75**
**5 bushels or over at $3.60 per bushel**

## 786 Mammoth Yellow

The Heaviest Fodder Producer

Mammoth Yellow does equally as well on light or heavy soils, and makes a most desirable land improver, and is one of the most valuable and important ensilage, forage or hay crops.

**Packet 10 cts.; pound 35 cts.; 5 pounds $1.50, postpaid**
**Not prepaid, 15 lbs. (peck) $1.00;**
**60 lbs. (bushel) $3.25**
**5 bushels or over at $3.15 per bushel**

Cow Peas

# Maule's Maine Grown Seed Potatoes

CULTURE—Cut to one or two eyes. Plant in rows 3 feet apart, and drop 15 to 18 inches apart in row. One-half peck of potatoes should be sufficient for 100 feet of row, use 10 to 12 bushels per acre. Cultivate constantly and thoroughly. Mature in 80 to 140 days, according to variety.

**DATE OF POTATO SHIPMENTS** Potatoes will be shipped at any date ordered during the winter, but at your own risk. Where no special instructions are given to the contrary, we will hold same until in our judgment there is no danger from freezing, then ship promptly.

## 69B90 Irish Cobbler

**80 days. Extremely Early—A World Wide Favorite**

A most excellent extra early variety, producing plump, handsome tubers of good size and excellent quality. It has also the remarkable characteristic of producing very few, if any, small potatoes, all the tubers being of marketable size. The flesh is pure white, with a clean, smooth, white skin with strong well-developed eyes slightly indented. Splendid keepers, matures in 80 days.

**Pound 35 cts.; 3 pounds 90 cts., postpaid**
**Not prepaid, pk. (15 lbs. net) $1.25; ½ bu. (30 lbs. net) $2.00; 1 bu. (60 lbs. net) $3.75; bag (150 lbs. net) $8.50**

## 69B92 Pure Early Rose

100 days. An Old Standard and Favorite Early Sort

This standard variety has been a great favorite with planters for many years on account of its yield and quality. Potatoes are long in shape, good size, and light pink in color, maturing in about 100 days. They cook mealy and of the finest flavor.

**Pound 35 cts.; 3 pounds 90 cts., postpaid**
**Not prepaid, pk. (15 lbs. net) $1.25; ½ bu. (30 lbs. net) $2.00; 1 bu. (60 lbs. net) $3.75; bag (150 lbs. net) $9.00**

## 69B94 Maule's Early Thoroughbred

100 days. A Basket Filler

On account of its extreme earliness it is not much affected by the usual midsummer and autumn droughts, while in keeping qualities it is unsurpassed. The large, light pink skin tubers run very uniform as to size and are practically all marketable; matures in 100 days. Excellent yielder; cook perfectly white, dry and floury.

**Pound 35 cts.; 3 pounds 90 cts., postpaid**
**Not prepaid, pk. (15 lbs. net) $1.25; ½ bu. (30 lbs. net) $2.00; 1 bu. (60 lbs. net) $3.75; bag (150 lbs. net) $9.00**

## 69B96 The Snow

135 days. The Money Maker

This large main crop potato originated in Maine, and after repeated trials in various sections of the country has proved itself to be of great value on account of its immense yield, together with the fact that it invariably produces very few small potatoes and is now attracting widespread attention. In shape the Snow potato is roundish, slightly flattened, eyes on the surface, the skin is well netted. It is very fine grained and flaky. Grows a large crop of handsome tubers in 135 days.

**Pound 35 cts.; 3 pounds 90 cts., postpaid**
**Not prepaid, pk. (15 lbs. net) $1.25; ½ bu. (30 lbs. net) $2.00; 1 bu. (60 lbs. net) $3.75; bag (150 lbs. net) $8.50**

## 69B97 Green Mountain

140 days. An Improved State of Maine Potato

This is a most excellent late potato; it does remarkably well on poor soils, and is very free from disease; it resists drought wonderfully well and produces tubers of large size and attractive appearance; flesh white. It is a good keeper, and when put away in the fall will keep well until spring. Matures in 140 days.

**Pound 35 cts.; 3 pounds 90 cts., postpaid**
**Not prepaid, pk. (15 lbs. net) $1.25; ½ bu. (30 lbs. net) $2.00; 1 bu. (60 lbs. net) $3.75; bag (150 lbs. net) $8.50**

## 69B98 Gold Coin

140 days. The Most Popular and Quickest Seller

A splendid main-crop variety of remarkable productiveness and finest table quality; slightly oblong in shape, skin light golden, flesh pure white. Cooks a dry, floury whiteness. Matures in 140 days. A excellent winter keeper.

**Pound 35 cts.; 3 pounds 90 cts., postpaid**
**Not prepaid, pk. (15 lbs. net) $1.25; ½ bu. (30 lbs. net) $2.00; 1 bu. (60 lbs. net) $3.75; bag (150 lbs. net) $8.50**

# MAULE'S FIELD CORNS

CULTURE—Plant when weather has settled and ground has become warm, in hills 4 feet apart each way, allowing 2 or 3 ants to remain in a hill, or sow in drills 4 feet apart, dropping one seed each foot in the drill; use 14 pounds of seed for an re. For fodder or ensilage, sow thickly in drills, 3 to 4 feet apart, using 56 to 84 pounds of seed per acre. With each riety, we give time of maturing under favorable weather conditions. **All prices are subject to change without notice.**

## 802 *Maule's Droughtproof Yellow Dent Corn*

**90 to 100 days. Resists Drought and Scorching Heat Better Than Any Other Variety**

Droughtproof Yellow Dent produces handsome ears of good size and symmetrical shape with the largest grains and the smallest cob of any Yellow Dent corn. In fact, from 70 pounds of corn on the ear, 64 pounds of shelled corn and only 6 pounds of cobs were obtained, which cannot be equalled by any other corn in existence. Grains are deep wedge shaped and of the brightest color. Yield not excelled by any other early sort.

We do not hesitate to say that, all points considered—its beautiful color, long yellow grains, large ears—taking all points combined, it is the finest yellow corn ever introduced.

**Packet 10 cts.; pound 30 cts.;**
**3 pounds 75 cts., postpaid**
**Not prepaid, 14 lbs. (peck) $1.00;**
**56 lbs. (bushel) $3.50**

## 799 Maule's Earliest of All Dent

**75 days. The newest and earliest dent corn in cultivation. It will mature in New York, any of the New England States, also the Dakotas, Northern Minnesota, Wisconsin, Montana, Michigan and Canada. Often yielding 100 bushels of corn per acre.**

This variety of Dent Corn we believe to be the heaviest yielder of any extreme early variety of corn yet introduced.

It is a very hardy grower, and prolific yielder for so early a corn. The leafy stalks average 8 feet or more in height, often producing two nice ears measuring 8 to 10 inches in length, well filled with good sound kernels, of a dark red shade, tipped with pure white, making it a very handsome corn in appearance.

It matures in 75 days from date of planting and yields on an average of 100 bushels of corn per acre.

This new corn can be grown with success anywhere that Early Canada Flint Corn matures, as it is some 10 days earlier than Early Canada Flint Corn. We strongly recommend the planting of this new dent corn in the northern climate or in any climate where a good strong early growing variety of dent corn is wanted.

**Packet 10 cts.; pound 35 cts.;**
**3 pounds 90 cts., postpaid**
**Not prepaid, 14 lbs. (peck) $1.10;**
**56 lbs. (bushel) $4.00**

## 801 Canada Early Yellow Flint

**85 days. Invaluable Where Seasons Are Short**

The most popular of all flint varieties; bears close planting. Matures in about 85 days. Ears are of medium length and have 8 rows of large, deep yellow grains, which fill out to the extreme tip; cob small. Stalks grow about 7 to 8 feet high and make an excellent fodder.

**Packet 10 cts.; pound 35 cts.;**
**3 pounds 90 cts., postpaid**
**Not prepaid, 14 lbs. (peck) $1.10;**
**56 lbs. (bushel) $4.00**

## 803 Hickory King

**115 days. Makes a Splendid Quality of Cornmeal**

This has the largest grains with the smallest cob of any white corn. Of strong growth, the stalks take a firm hold in the ground and stand upright. It yields splendid crops on light soil and is the most productive white field corn. Ripens in about 115 days. It husks and shells easily and produces much fodder. Excellent for silage.

**Packet 10 cts.; pound 35 cts.;**
**3 pounds 90 cts., postpaid**
**Not prepaid, 14 lbs. (peck) $1.10;**
**56 lbs. (bushel) $4.00**

## 806 Improved Leaming

**100 days. Very Popular and Productive**

An early long-eared corn, averaging 10 inches in length, with 18 to 20 rows of wedge shaped, deep golden yellow grains. A good ensilage or silo corn and extensively grown by stock feeders everywhere. Improved Leaming grows 8 to 10 feet in height. The ears are uniform with medium sized cob, and husks easily. Very productive and an ideal Yellow Dent corn. It requires about 100 days to mature its splendid grains.

**Packet 10 cts.; pound 30 cts.;**
**3 pounds 75 cts., postpaid**
**Not prepaid, 14 lbs. (peck) $1.00;**
**56 lbs. (bushel) $3.50**



99 Maule's Earliest of All Dent Corn



802 Maule's Droughtproof Yellow Dent Corn

# 809 Maule's Improved Mastodon Yellow Dent Corn



809 Maule's Improved Mastodon Corn

**95 to 100 days. The Earliest of All Large Eared Yellow Dent Corn**

It is the largest eared, extra early yellow dent corn; the ears measuring to 12 inches in length, and from 7½ to 8 inches in circumference, with 16 22 rows of grains, and averaging at husking time nearly one pound eac Out-yields any other variety ripening at the same time.

It makes a rapid, strong and rank growth, attaining a height of 9 to feet, often producing 2 to 3 large ears to a stalk. The foliage is larg making fine fodder, and is one of the best varieties for that purpose.

We consider Improved Mastodon the variety to plant where an extra earl large eared corn is wanted that will mature in 95 to 100 days under favo able growing conditions. It makes fine looking shelled corn, showing tw shades, a golden yellow with a white cap.

**Packet 10 cts.; pound 30 cts.; 3 pounds 75 cts., postpaid**
**Not prepaid, 14 lbs. (peck) $1.00; 56 lbs. (bushel) $3.75**

## 807 Johnson County White Dent

**120 days. The Heaviest Cropping White Corn Known**

The high breeding of this variety makes its growth more uniform. The beautiful large ears are cylindrical in shape up to within about 2 inches of the tip. Both kernel and cob are white. The tips of the ears are well filled, a large percentage being completely covered with grain. The kernels are uniform in size and very long and wedge-shaped; 18 to 24 rows on a cob. The ears will average about 10 inches in length and from 7½ to 8 inches in circumference. There is very little space between the rows and this variety yields a very high percentage of shelled corn. The stalk is good and thrifty, ranging in height from 10 to 12 feet. Matures in about 120 days.

**Packet 10 cts.; pound 30 cts.; 3 pounds 75 cts., postpaid**
**Not prepaid, 14 lbs. (peck) $1.00; 56 lbs. (bushel) $3.75**

## 812 Reid's Yellow Dent

**110 days. The Most Popular Yellow Dent Corn**

For a number of years past Reid's Yellow Dent has been one of the most popular varieties of the Middle West, some people going so far as to say there is more of this corn planted than of all other sorts combined. It is a true dent corn, color a beautiful golden yellow, with one of the smallest cobs for size of ear of any yellow corn. Ears are frequently 9 to 11 inches long, and from 7 to 8 inches in circumference. It is easily shelled and matures its crop under favorable conditions in about 110 days. It undoubtedly has taken more prizes at the Illinois State Fair and other great corn shows than any other variety.

**Packet 10 cts.; pound 30 cts.; 3 pounds 75 cts., postpaid**
**Not prepaid, 14 lbs. (peck) $1.00; 56 lbs. (bushel) $3.50**

## 814 Red Cob Ensilage

**110 days. One of the Best for Ensilage**

A pure white corn cropping as high as 45 tons of fodder per acre. Sweet, tender and juicy. More nourishment than from any other variety. Short joints, abundance of leaves and of tall growth. An excellent corn for cutting green, to cure for hay or for the silo. Esteemed by dairymen, stockmen and breeders everywhere. Matures in about 110 days.

**Packet 10 cts.; pound 30 cts.; 3 pounds 75 cts., postpaid**
**Not prepaid, 14 lbs. (peck) $1.00; 56 lbs. (bushel) $3.25**

## 815 Sugar Corn for Green Forage

**Ready to cut in 50 days. Excellent for Dairy Stock**

For forage purposes, it is the best of all corns both as green corn for ensilage or to be cut and used dry. Both the stalks and fodder contain large amounts of saccharine matter which is both fattening and relished by stock. It is sown in drills 2½ to 3 feet apart and requires 40 to 60 pounds of seed per acre. Ready to cut in 50 days.

**Packet 10 cts.; pound 25 cts.; 5 pounds $1.00, postpaid**
**Not prepaid, 5 lbs. or over at 12 cts. per lb.; 100 lbs. $10.00**



807 Johnson County White Dent Cor

# Maule's Clover and Grasses

NOTE.—5-pound and 100-pound prices on Clovers and Grasses are net F. o. b. Philadelphia, and are subject to market changes

Customers may order 2 lbs. or over at the 5 lb. rate, 10 lbs. or over at the 100 lb. rate

796 Red Clover

791 Alfalfa Clover

888 Sudan Grass

882C English Rye

890 Timothy

## 791 *Alfalfa* American Grown Certified

### The Supreme Leader of All the Clovers

No crop ever grown has had such a conspicuous place in increasing e profit from agriculture as alfalfa. Its long fibrous roots working eir way far down into the soil liberate, after the hay is cut, an im- ense volume of plant foods to be drawn on for years to come by ture crops. It can be cut 3 to 5 times a year and produces from 3 7 tons of hay per acre. As a feed for cattle, swine, poultry or stock any kind, owing to its large percentage of protein, it is unsurpassed. an be grown successfully anywhere. Lime must be supplied or the ants will fail. Suggest using 1 to 2 tons of lime per acre before anting alfalfa seed. Sow from 15 to 25 pounds per acre in April or ay or July and August.

**Packet 10 cts.; pound 50 cts.; 3 pounds $1.35, postpaid**
**Not prepaid, 5 lbs. $1.75; 100 lbs. $30.00**

## 98 Grimm or Everlasting Alfalfa Extremely Hardy

Endures extremes of cold and withstands excessive heat, accepting ost all soils and has obtained a reputation for productiveness and rdiness all through the Northwest. Winter never kills, no re-seed- g, always makes a crop. Does equally as well in every state in the nion. Sow 15 to 25 pounds per acre in April or May or July and ugust.

**Packet 15 cts.; pound 70 cts.; 3 pounds $2.00, postpaid**
**Not prepaid, 5 lbs. $2.50; 100 lbs. $45.00**

## 92 Alsike or Swedish Does Well on Wet or Dry Soils

Perfectly hardy, and one of the very best of all the clovers, for cow asturage, bee pasturage or for making hay. Deliciously fragrant and ghly nutritious. Lasts for years. Sow 8 to 10 pounds per acre.

**Packet 10 cts.; pound 75 cts.; 3 pounds $2.00, postpaid**
**Not prepaid, 5 lbs. $2.75; 100 lbs. $50.00**

## 793 Bokhara or Sweet A Money Making Crop

Plants grow 4 to 6 feet high, with numerous small white flowers of reat fragrance which are sought by bees. Valuable for pasture or ay. It is being urged by agriculturists to sow as a forerunner of lfalfa; for where Bokhara thrives, Alfalfa will grow. Sow 15 pounds the acre.

**Packet 10 cts.; pound 40 cts.; 3 pounds $1.00, postpaid**
**Not prepaid, 5 lbs. $1.25; 100 lbs. $21.00**

## 794 Crimson or Scarlet For Cover Crop and Soil Enricher

A well-known and favorite winter cover crop and soil enricher, af- rding excellent early forage. Seed should be sown in August or ptember. Use seed at the rate of 15 pounds per acre. It grows all inter when ground is not frozen. Valuable for cover crop, for asture or hay.

**Packet 10 cts.; pound 35 cts.; 3 pounds 90 cts., postpaid**
**Not prepaid, 5 lbs. $1.00; 100 lbs. $18.00**

## 796 Red The Favorite Well Known June Clover

Makes a valuable hay crop for dairy cows on account of its high rcentage of nitrogenous elements. Sow 8 to 12 pounds per acre.

**Packet 10 cts.; pound 65 cts.; 3 pounds $1.75, postpaid**
**Not prepaid, 5 lbs. $2.50; 100 lbs. $47.00**

## 797 White Dutch Adapted for Lawn

It should find a place in all grass mixtures, whether for lawn, eadow or permanent pasture. Does well in all soils. It is perfectly ardy. Sow 3 pounds per acre with other grasses; 6 pounds alone.

**Packet 15 cts.; ¼ pound 25 cts.; pound 75 cts., postpaid**
**Not prepaid, 5 lbs. $3.25; 100 lbs. $60.00**

## 890 *Timothy* For Hay Crop or Pasture

By far the most popular and valuable hay producing and pasturage grass of America. It is the one grass that is always sure to grow. Height, 2 to 3 feet. Sow seed in the early Spring or Fall. If sown alone, use 15 pounds of seed per acre. To sow with Clover use 10 pounds Timothy and 3 pounds Alsike or 5 pounds Red Clover.

**Pound 35 cts.; 3 pounds 90 cts., postpaid**
**Not prepaid, 5 lbs. 75 cts.; 100 lbs. $12.00**

## 888 Sudan Grass The Hay Maker and Drought Resister

Sudan is an annual grass and must be reseeded every year. The plant under favorable weather conditions grows to a height of 6 to 10 feet, but when broadcasted thickly it grows only 3 to 5 feet high. It frequently produces 20 or more stalks to a plant. The stems are unbranched, seldom larger than a lead pencil and are covered with an abundance of leaves. Is easily cured, making hay of excellent quality, which is readily eaten by all kinds of stock without injury to them. Sow seed by drilling or broadcasting, using 10 to 15 pounds per acre.

**Pound 35 cts.; 3 pounds $1.00, postpaid**
**Not prepaid, 5 lbs. 75 cts.; 100 lbs. $10.00**

**882 BERMUDA GRASS Known as Southern Blue Grass**
Much used in the south for lawns, pasturage, and for binding drifting sand, or steep embankments. Resists extreme drought and heat. Will not stand winter north of Virginia. Sow 5 to 7 pounds per acre.

**Pound 75 cts.; 3 pounds $2.00, postpaid**
**Not prepaid, 5 lbs. $2.50; 100 lbs. $45.00**

**882A CANADIAN BLUE Grows on Poorest and Dryest Soils**
Used on steep places or exposed situations. Sow 28 pounds to the acre. **Pound 55 cts.; 3 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. $2.00; 100 lbs. $35.00**

**882C ENGLISH OR PERENNIAL RYE Lasts for Years**
Largely used in lawn and pasture mixtures. It makes a rich, green sod and a nutritious hay. Lasts for years. Use 36 to 48 pounds per acre. **Pound 40 cts.; 3 pounds $1.00, postpaid**
**Not prepaid, 5 lbs. $1.25; 100 lbs. $21.00**

**882D ITALIAN RYE An Annual or Biennial Grass**
For soiling purposes. It is a rapid grower on good soil, being ready to cut in four or five weeks from seeding. Sow 36 pounds per acre.

**Pound 40 cts.; 3 pounds $1.00, postpaid**
**Not prepaid, 5 lbs. $1.25; 100 lbs. $20.00**

**882E MEADOW FESCUE OR ENGLISH BLUE The Pasture Grass**
Lives longer than most other grasses. Does well in heavy, low laying soils or wet places. Produces the first year a good crop of hay or pasture. Matures the same time as Timothy. Sow 40 pounds per acre.

**Pound 60 cts.; 3 pounds $1.65, postpaid**
**Not prepaid, 5 lbs. $2.25; 100 lbs. $40.00**

**882F RED TOP OR HERD Fancy Recleaned for Lawns or Pasture**
One of our best native grasses. Useful for lawn or pasture fields. Does well on moist or even quite dry soils. Sow 20 pounds per acre.

**Pound 60 cts.; 3 pounds $1.65, postpaid**
**Not prepaid, 5 lbs. $2.25; 100 lbs. $40.00**

**882G WOOD MEADOW For Shady Places, under Trees, etc.**
Makes a compact green sod in shady places. Use 28 pounds to the acre.

**Pound 80 cts.; 3 pounds 2.25, postpaid**
**Not prepaid, 5 lbs. $3.25; 100 lbs. $60.00**

**883 KENTUCKY BLUE The Best Grass for Lawn or Pasture**
Uninjured by extremes of cold, heat or drought. Sow 28 pounds to the acre. **Pound 55 cts.; 3 pounds $1.50, postpaid**
**Not prepaid, 5 lbs. $2.00; 100 lbs. $35.00**

**889 ORCHARD Admirable for Pasture or Mowing**
Furnishes green grass early in Spring until Fall. Use 28 lbs. to the acre. **Pound 45 cts.; 3 pounds $1.25, postpaid**
**Not prepaid, 5 lbs. $1.50; 100 lbs. $24.00**

## 891 *Maule's Extra Lawn Grass Mixture*

### *A Beautiful, Smooth, Low Growing Evergreen Grass for the Yard or Lawn*

This mixture will insure a beautiful, compact, evergreen sod on any lawn where the essential requirements of grass culture have been complied with. Its component parts are the grasses peculiarly adapted to lawns and yards, including choice selected strains of Kentucky Blue, etc., along with the best known creeping or sod forming sorts. We have included a little white clover in the mixture, regarding it as essential. Full provision is made for a succession of growth, so that there shall be no break in the richness of the verdure from spring until autumn, and experience proves that Maule's Extra Lawn Gras Mixture is now perfect. Nothing better can be purchased on th American market. Our friends will please note that this seed is sol 20 pounds per bushel. This is because we employ the choicest an heaviest strains of grass seed in making the mixture. For those tha wish this mixture without white clover we can supply it at the sam prices but in ordering please mention you want it without clover.

Grass seed can be sown any time between April and September.

**½ pound 35 cts.; pound 60 cts.; 3 pounds $1.65, postpaid**
**Not prepaid, 3 lbs. $1.35; 5 lbs. (peck) $2.00; 20 lbs. (bushel) $7.50**

## 884 *Quick Results Lawn Mixture*

### *A Rapid Growing Velvety Green Grass*

This mixture is for producing an immediate greensward that will be followed by a good, permanent sod. It is especially to be recommended for late spring seeding, without a nurse crop. For early seeding we would rather use Maule's Extra Lawn Grass Mixture, but after May 1st (in the latitude of Philadelphia) we would much prefer this one. It will make rapid growth, and will be ready to cut two weeks in advance of any other mixture which we offer; nor is it lacking in permanence.

**½ pound 35 cts.; pound 60 cts.; 3 pounds $1.65, postpaid**
**Not prepaid, 3 lbs. $1.35; 5 lbs. (peck) $2.00;**
**20 lbs. (bushel) $7.50**

## 886 *Maule's Steep Slope Mixture*

### *A Lasting Grass for Embankments and Terraces*

This is for banks, terraces, steep or exposed slopes and bare spots in general; in fact, for any place, however dry, stony or barren. It will produce a sod that is absolutely proof against heat or drought, and that cannot be injured by cold. The grasses produce strong, spreading roots, thus preventing heavy rains from washing them out; will withstand exposure, thrives on shallow soils, and at the same time produces a rich, velvety green turf throughout the season.

**½ pound 40 cts.; pound 75 cts.; 3 pounds $2.10, postpaid**
**Not prepaid, 3 lbs. $1.65; 5 lbs. (peck) $2.50;**
**20 lbs. (bushel) $9.50**

## 797 White Dutch Clover **Adapted for Lawn**

It should find a place in all grass mixtures, whether for lawn, meadow or permanent pasture. Does well in all soils. It is perfectly hardy. Sow 3 pounds per acre with other grasses; 6 pounds alone.

**Packet 15 cts.; ¼ pound 25 cts.; pound 75 cts., postpaid**
**Not prepaid, 5 lbs. $3.25; 100 lbs. $60.00**

## 885 *Maule's Shady Lawn Mixture*

### *Flourishes Under Trees or in Shady Nooks*

This mixture is intended for all situations that are in partial or com plete shade, and will be found invaluable on grounds lying under th shadows of trees or buildings. This mixture is adapted to its purpos

**½ pound 40 cts.; pound 75 cts.; 3 pounds $2.10, postpaid**
**Not prepaid, 3 lbs. $1.65; 5 lbs. (peck) $2.50;**
**20 lbs. (bushel) $9.50**

## 887 *Maule's "Sunny South"*

### *A Grass Mixture Especially Suited For Hot Climates*

A special preparation that will resist extremes of heat and drough this mixture has given very satisfactory results and by proper care an continued watering a beautiful lawn can be had in the Southern state where grasses do not generally thrive during the summer months.

**½ pound 40 cts.; pound 75 cts.; 3 pounds $2.10, postpaid**
**Not prepaid, 3 lbs. $1.65; 5 lbs. (peck) $2.50;**
**20 lbs. (bushel) $9.50**

## *Quantity of Grass Seed to Sow*

| | | | | | | | | |
|---|---|---|---|---|---|---|---|---|
| 1 pound | will sow a plot | | | 15 x | 20 | feet | 300 | sq. ft. |
| 5 pounds | " | " | " | 40 x | 50 | " | 2000 | " |
| 20 pounds | " | " | ¼ acre | 100 x | 108 | " | 10800 | " |
| 100 pounds | " | " | 1 " | 209 x | 209 | " | 43681 | " |

If intended for renovating an old lawn, about half the above quantities are sufficient for the given spaces.

## *Maule's Three Permanent Pasture Mixtures*

### *Best Adapted for Producing an Abundant Hay Crop or for Pasturage*

It is true beyond all question that a mixture of grasses produces a better mowing field and subsequent permanent pasture than a mere combination of timothy and clovers. The former will last five times as long as the latter. Timothy "runs out" in a couple of years or so, while a good permanent pasture will last ten or even twenty years. This has been frequently and forcibly shown by experience. Our completed mixtures are sold in two parts, one containing grass seeds and the other clover seeds, to be sown separately, on account of their different weights. The grass seeds may be sown in spring or fall; the clover seeds preferably in the spring. In preparing the permanent pasture grass mixtures we employ mainly Kentucky Blue, Timothy, English or Perennial Rye, Italian Rye, Red Top or Herd, Orchard, Meadow Fescue or English Blue, Canadian Blue and Crested Dogsta

In the clover mixture we employ Red, Alsike and White. A few these components will disappear in a few years, but the others a absolutely permanent. We vary the proportions to suit the differe soils.

**Maule's Permanent Pasture Mixture for Light and Sandy Soils.**—Use at the rate of 60 pounds (3 bushels) per acre.

**Maule's Permanent Pasture Mixture for Average Soils.**—For gener use, everywhere. Sow at the rate of 60 pounds (3 bushels) per acr

**Maule's Permanent Pasture Mixture for Heavy Soils.**—Use at th rate of 60 pounds (3 bushels) per acre.

***Any of the above PERMANENT PASTURE MIXTURES: Not prepaid, 5 pounds (peck) $1.50; 20 pounds (bushel) $5.50; 60 pounds (3 bushels) Mixed Grass seeds and 10 pounds Mixed Clover seeds $21.00.***

# Maule's Superior Flower Seeds



## The Best of the New Flowers Recently Introduced

### and all the old and well-tried favorites

The sales of flower seeds and bulbs continue to increase with us each year, but the increased sales last season far ceeded all previous years. Two reasons may be attributed to this large increase; the superior excellence of ule's seeds and the desire of more people to beautify their home surroundings.

The large business done by us in bulbs and seeds last fall is a sure indication there will be a greater demand flowers this coming spring than ever before. Our stocks were never of better quality; our supply was never complete; we are prepared to properly care for your orders.

The different varieties listed on the following pages are designated either as Annuals, Biennials or Perennials.

**Hardy Annuals.** Easily raised and suitable for many purses; excellent for cutting; invaluable for bedding, some for or, others for foliage effect. They will always be popular h those who want quick results with the least expenditure time and money. Seed may be started in the open ground early spring or sown indoors for earlier effect. Plants will wer and die in the one season.

**Half Hardy Annuals.** Seeds should be sown in boxes in the use or in hot-beds during March or April and the plants out in the open ground in May. They will flower for the season and die.

**Hardy Biennials.** Sow seed as you would the hardy annual. e plants will not bloom until the following year, after ich they die.

**Half Hardy Biennials.** Seed should be sown as you would half hardy annuals. The plants require protection during winter. They will bloom and die the following season.

**Hardy Perennials.** Seeds may be sown in early spring, or during July and August to produce plants that will flower the next season, and continue to bloom each succeeding year. Seed of some hardy perennials, if sown very early, will produce plants that will bloom the same season. It is unnecessary to give protection to these plants during the winter, but it will prove beneficial to the plants if a covering of leaves, litter or strawy manure is provided. A hardy bed or border, when once established, requires practically no attention and will, if varieties have been properly selected and arranged, provide an abundance of flowers from early spring until frost.

**Half Hardy Perennials.** Sow seed as you would the half hardy annuals. If plants are set out in the open ground they must be lifted before frost, potted up and taken in the house during the winter.

**When ordering flower seeds, it is unnecessary to write the long names—it is sufficient to GIVE THE NUMBER ich we have assigned each variety, but you must GIVE THE VARIETY NUMBER CORRECTLY to receive just at you desire.**

All flower seeds are delivered by parcel post to your door or post-office, free of all extra charges, at prices given.

## st of Plants, Grown from Seed, Suitable for Special Purposes and Different Situations

The lists below were compiled for your convenience so that you can readily select proper varieties for different rposes or locations. These lists are by no means complete, but merely suggestive. Each variety, throughout the catog, is clearly described; height, growing habits and for what purposes they are best suited. The Flower Garner's Calendar on page 142 tells when and what to plant at certain periods to procure the best results. Directions w to plant are printed on every package of Maule's Flower Seeds. A study of both should make your flower grow a success. Your success is our success—we are as much interested as you are in the results obtained from wing Maule's Seeds.

### Plants Suitable for Pots


utilon ..... 82
eratum ..... 82
ssum ..... 82
tirrhinum ..... 83
temisia ..... 85
paragus ..... 85
gonia ..... 85
ie Daisy ..... 90
achycome ..... 91
tterfly Flower.. 91
lceolaria ..... 91
endula ..... 91
rnation ..... 93
eraria ..... 95
eus ..... 96
clamen ..... 96
ns ..... 101
Fuchsia ..... 101
Geranium ..... 102
Gloxinia ..... 102
Heliotrope ..... 103
Jerusalem Cherry.. 105
Lantana ..... 105
Lemon Verbena... 106
Lobelia ..... 106
Mignonette ..... 107
Petunia ..... 112, 113
Phlox ..... 114
Primula ..... 113
Purple Feather Grass ..... 116
Stocks ..... 117
Umbrella Plant .. 121
Vinca ..... 122


### Climbing and Trailing Vines


lumia ..... 82
apelopsis ..... 84
istolochia ..... 85
lloon Vine..... 85
gnonia ..... 90
ter Sweet ..... 90
nary Bird Flower ..... 92
rdinal Climber.. 93
matis ..... 95
œa ..... 95
press Vine ..... 96
erlasting Pea...101
urds ..... 103
Ipomœa ..... 104
Japanese Hop Vine 104
Kudzu Vine, Japanese ..... 105
Momordica ..... 109
Morning Glory ...107
Nasturtium, Tall..108
Scarlet Runner Bean ..... 121
Smilax ..... 117
Sweet Peas...118, 119, 120
Thunbergia ..... 121
Wistaria ..... 124


### Plants Succeeding in Partial Shade


Anchusa, Capensis. 84
Antirrhinum ..... 83
Aquilegia ..... 84
Begonia ..... 85
Butterfly Flower .. 91
Campanula ..... 92
Coreopsis ..... 96
Daisy, English..... 98
Delphinium ..... 99
Digitalis ..... 100
Feverfew ..... 101
Myosotis ..... 109
Poppy, Hardy.....115
Viola ..... 122


### Plants Suitable for Edging or Bordering Walks and Beds


African Gold Daisy 98
Ageratum ..... 82
Alyssum ..... 82
Antirrhinum ..... 83
Arabis ..... 84
Balsam, Dwarf.... 90
Brachycome ..... 91
Calliopsis, Dwarf.. 91
Candytuft ..... 92
Carnation ..... 93
Centaurea, Gymnocarpa ..... 94
Coleus ..... 96
Daisy, English ... 98
Dianthus .....99, 100
Eschscholtzia .....100
Euphorbia, Variegata .....101
Gypsophila .....103
Kochia .....105
Lobelia .....106
Marigold, French..106
Mignonette .....107
Myosotis .....109
Nasturtium, Dwarf.108
Nigella .....109
Petunia .....112, 113
Phlox Drummondii .....114
Portulaca .....114
Salvia .....116
Stocks .....117
Sweet William.....121
Verbena .....122
Vinca .....122
Zinnia .....123, 124


### Long Stemmed Flowers for Cutting


Antirrhinum ..... 83
Arctotis ..... 84
Aster ....86, 87, 88, 89
Blue Lace Flower. 90
Calendula ..... 91
Celosia ..... 94
Centaurea ..... 94
Chrysanthemum .. 95
Coreopsis ..... 96
Cosmidium ..... 96
Cosmos ..... 97
Dahlia ..... 98
Delphinium ..... 99
Gaillardia .....102
Gypsophila .....103
Helenium .....103
Larkspur .....105
Marigold .....106
Mignonette .....107
Pyrethrum .....116
Salpiglossis .....117
Scabiosa .....117
Sunflower .....117
Sweet Peas.118, 119, 120
Valeriana .....121
Woolflower, Chinese ..... 94
Zinnia .....123, 124


### Drooping Plants Suitable for Vases, Hanging Baskets, Porch Boxes, etc.


Alyssum, Sweet... 82
Asparagus ..... 85
Centaurea, Gymnocarpa ..... 94
Lantana .....105
Nasturtium .....108
Oxalis .....109
Petunia .....112, 113
Smilax .....117
Thunbergia .....121


### Everlasting or Straw Flowers to Dry for Winter Bouquets


Acroclinium ..... 82
Everlasting mixed.101
Globe Amaranth ..102
Gypsophila .....103
Helichrysum .....103
Ornamental Grasses .....109
Pampas Grass ....109
Xeranthemum ....122


On page 144 will be found a complete index of the botanical and common names of all flowers listed.

892 Abutilon, Choicest Hybrids

896 Achillea, The Pearl

## ABUTILON (Flowering Maple)

### Half Hardy Perennial

They make handsome plants, growing 1 to 3 feet high. Will bloom during summer and autumn out-doors, or at any time in the house.

*892* **CHOICEST HYBRIDS.** Pretty, drooping, bell-shaped flowers, on slender, thread-like stems. The colors are white, lemon, rose, scarlet, crimson, yellow, red, etc. Some of the flowers are large and flaring, others crinkled like crepe or shining like satin, and some so full as to be almost double. All sorts and colors mixed.

**Packet 15 cts.; 1/16 ounce 50 cts.; ⅛ ounce 75 cts.**

## ACHILLEA (Milfoil or Yarrow)

### Hardy Perennial

*896* **THE PEARL.** Grows 2 feet high, bearing many heads of the purest white, globular flowers, in loose bunches from spring until frost. Easily grown from seed, blooming the first season if sown early. A grand plant for cemetery decorations and highly valued for cutting.

**Packet 15 cts.; 1/16 ounce 50 cts.; ⅛ ounce 75 cts.**

898 Acroclinium, Finest Mixed

900 Adlumia, Cirrhosa

## ACROCLINIUM (Everlasting)

### Hardy Annual

One of the so-called everlasting flowers, which when cut and dried is very valuable for winter bouquets. A graceful plant, growing about 15 inches high and bearing lovely rose and white flowers, which are very effective in beds or borders during the summer, but it is for their use in a dried state during the winter that they are extensively grown.

*898* **FINEST MIXED. Packet 10 cts.; ¼ ounce 25 cts.**

## ADLUMIA (Allegheny Vine or Mountain Fringe)

### Hardy Biennial Climber

*900* **CIRRHOSA.** A graceful, beautiful climbing vine with feathery foliage resembling Maidenhair Fern. Bears profusely pretty rose colored, tube-shaped flowers. Grows 10 to 15 feet high. Blooms the first year from seed and as it resows itself year after year, might be classed as a perennial. Very desirable for covering trellises, tree stumps, etc., delighting in a sunny position.

**Packet 10 cts.; 1/16 ounce 50 cts.; ⅛ ounce 75 cts.**

## AGERATUM (Floss Flower)

### Hardy Annual

A plant of the greatest beauty and value for garden or w dow, unexcelled for borders or bedding. Early and const bloomer.

*All Flower Seeds, Flowering Bulbs and Roots offered in this catalog are sent postpaid at prices listed*

904 Ageratum, Little Blue Star

*902* **DWARF IMPERIAL BLUE.** A comp plant, with dark flowers rising w above the foliage.

**Packet 10 cts.; ¼ ounce 25 cts.; ounce 75 cts.**

*904* **LITTLE BLUE STAR.** The best Ageratum for edging purposes, as the pla grow only 4 or 5 inc high, and literally c ered with bright flowers from ea summer u frost. They m very desira winter wind plants, and be taken up potted, for purpose, in t autumn.

**Packet 15 cts.; 1/16 ounce 50 cts.; ⅛ ounce 90 cts.**

*908* **FINEST VARIETIES MIXED.** All sorts and colors.

**Packet 10 cts.; ¼ ounce 25 cts.; ½ ounce 40 cts.**



914 Alyssum, Little Gem

## ALYSSUM (Mad Wort)

### Hardy Annual

A free flowering annual of great utility and beauty; ea grown and everywhere popular. It thrives in almost ev soil and situation.

*910* **DWARF YELLOW.** Pale yellow flowers; changing they age, to white; of dwarf, compact, erect growth. F continuous bloomer.

**Packet 10 cts.; ¼ ounce 25 cts.; ounce 75 cts.**

*912* **LILAC QUEEN.** Pale lilac flowers, changing to wh as they age. The plants are of dwarf, compact and upri growth.

**Packet 10 cts.; ¼ ounce 25 cts.; ounce 75 cts.**

*914* **LITTLE GEM.** Flowers are pure white and borne profusely that it resembles the appropriate name, "Carpet Snow," throughout the summer. Of dwarf, compact ha growing only 3 or 4 inches high. One of the easiest gro and most satisfactory white flowered plants for edgings low beds. Desirable winter pot plant.

**Packet 10 cts.; ¼ ounce 25 cts.; ½ ounce 40 cts.; ounce 75**

916 Alyssum, Saxatile Compactum

*918* **SWEET.** T well-known s Should be in ev garden.

**Packet 5 cts.; ¼ ounce 15 cts.; ounce 40 cts.**

### Hardy Perennial Alyssum (Basket of Gold)

*916* **SAXATILE COMPACTUM.** T plants grow about inches high; of easi culture and very f blooming. Br masses of bright y low flowers in ea Spring. An excell plant for the rock or front of borders.

**Packet 10 cts.; ¼ ounce 30 cts.**

# Maule's Antirrhinums or Snapdragons

**Hardy Annual**

Antirrhinums, in recent years, have become very popular. The long spikes are well adapted for cut-flowers. Few flowers give such a range of gorgeous colorings. They are very satisfactory for borders, bedding and pot culture for house decoration, especially during the winter, for which purpose the plants should be cut back in September. In some sections, if given protection during the winter, they will live over and furnish earlier and better blooms the second season.

## Maximum, New Giant Flowered Antirrhinums

Far surpasses any strain of Antirrhinums yet introduced. Grow slightly taller than the Tall Giant Flowering varieties. The flowers are the largest of all and closely placed on the spike. Indispensable for cutting, attractive in beds or borders.

*929* **CATTLEYA.** A soft, silvery, rosy-lilac with golden yellow lip.
**Packet 15 cts.; 1/16 ounce 50 cts.; ⅛ ounce 75 cts.**

*931* **DIAMOND.** Scarlet carmine with golden-yellow lip and pinkish throat. The three colors on the one flower make a pleasing effect. Particularly showy and attractive. Equally suitable for bouquets or garden decoration.
**Packet 15 cts.; 1/16 ounce 50 cts.; ⅛ ounce 75 cts.**

*932* **GOLDEN QUEEN.** Beautiful, bright golden yellow.
**Packet 15 cts.; 1/16 ounce 50 cts.; ⅛ ounce 75 cts.**

*933* **THE ROSE.** A pleasing shade of rose-pink in demand for cutting.
**Packet 15 cts.; 1/16 ounce 50 cts.; ⅛ ounce 75 cts.**

*934* **SNOWFLAKE.** Lovely pure white with yellowish throat.
**Packet 15 cts.; 1/16 ounce 50 cts.; ⅛ ounce 75 cts.**

## Maximum Antirrhinum Collection

**The largest flowered of all Antirrhinums in a range of quite distinct colors**

*4109* **One packet each of the above 5 named Maximum New Giant Flowered Antirrhinums (value 75c) for 50c**

*935* **MAXIMUM, CHOICEST MIXED COLORS.** The above and other choice colors in a grand mixture; a wonderful display of attractive shades.
**Packet 15 cts.; 1/16 ounce 40 cts.; ⅛ ounce 60 cts.; ¼ ounce $1.00**

935 Antirrhinum, Maximum, Choicest Mixed Colors

## Half Dwarf Giant Flowering Antirrhinums

Compact, bushy growth, 12 to 20 inches high; especially valuable for bedding and cutting purposes. Bear large flowers profusely.

*941* **DAPHNE.** Soft blush pink; a very effective color.
**Packet 10 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.**

*943* **DEFIANCE.** Orange or russet red; striking.
**Packet 10 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.**

949 Antirrhinum, Philadelphia Pink

*944* **FIREBRAND.** Rich, deep red; a superb shade.
**Packet 10 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.**

*945* **GOLDEN QUEEN.** Rich, golden yellow; very attractive.
**Packet 10 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.**

*949* **PHILADELPHIA PINK.** Very large individual flowers of an exquisite shade of pink, considered by many growers as the finest pure pink. Especially desirable for forcing; excellent both for beds and as a cut-flower. Plant is of compact half-dwarf habit, bearing profusely massive, upright spikes of the most lovely color.
**Packet 15 cts.; 1/16 ounce 40 cts.; ⅛ ounce 60 cts.**

*951* **ROSE D'ORE.** A charming variety of a particularly pretty color, golden rose. Unique and attractive; large flowers.
**Packet 10 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.**

*950* **SILVER PINK.** A beautiful shade of pearly pink; flowers of large size and set closely on long spikes. Far surpasses any other pink of its shade. Of vigorous habit.
**Packet 15 cts.; 1/16 ounce 50 cts.; ⅛ ounce 75 cts.**

*947* **WHITE BEAUTY.** Pure white flowers; handsome.
**Packet 10 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.**

*940* **HALF DWARF, FANCY MIXED COLORS.** Many shades and tints will be found in this desirable mixture.
**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**

## Half Dwarf Giant Antirrhinum Collection

See inside back cover for colored illustrations

*4113* **One packet each of Firebrand, Golden Queen, White Beauty and Rose d'Ore Antirrhinums for 35c**

## Tall Giant Flowering Antirrhinums

Robust growers, 2 to 3 feet high, bearing long spikes of large flowers.

*936* **GIANT PINK.** **Packet 10 cts.; ⅛ ounce 25 cts.**

*942* **GIANT SCARLET.** **Packet 10 cts.; ⅛ ounce 25 cts.**

*946* **GIANT YELLOW.** **Packet 10 cts.; ⅛ ounce 25 cts.**

*952* **QUEEN VICTORIA (Giant White).** Flowers are pure white.
**Packet 10 cts.; ⅛ ounce 25 cts.**

*948* **GIANT, TALL MIXED.** A splendid mixture of many colors.
**Packet 10 cts.; ⅛ ounce 20 cts.; ¼ ounce 35 cts.**

950 Silver Pink Antirrhinum

920 Amaranthus, Tricolor Splendens



926 Ampelopsis, Veitchii

## AMARANTHUS (Joseph's Coat)

### Hardy Annual

Brilliant foliaged plants, particularly useful for backgrounds, centres of beds, among shrubs, etc. Height 3 to 5 feet.

*920* **TRICOLOR SPLENDENS.** The leaves are glowing scarlet-crimson effectively marked with yellow and bronze-green. Bears crimson flower heads. **Packet 10 cts.; ¼ ounce 30 cts.**

*921* **SALICIFOLIUS.** A graceful grower, 3 feet tall. The leaves are 5 to 8 inches long and ¼ inch wide. They are a bronzy green changing to orange-red shaded with gold. **Packet 10 cts.; ¼ ounce 35 cts.**

*922* **MIXED.** All colors. **Packet 10 cts.; ¼ ounce 25 cts.**

## AMPELOPSIS (Japanese or Boston Ivy)

### Hardy Perennial Climber

*926* **VEITCHII.** The leaves are olive green, turning to scarlet in the autumn. Perfectly hardy; grows 30 to 60 feet. It clings firmly and permanently to walls, trees, etc. **Packet 10 cts.; ¼ ounce 25 cts.; ounce 60 cts.**

## ANCHUSA ROOTS Hardy Perennial

*70B06* **OPAL.** Large pale blue flowers; very beautiful.

**35 cts. each; 3 for $1.00; 6 for $1.75; $3.25 per dozen**

928 Anchusa, Capensis

930 Anchusa, Italica Dropmore

## ANCHUSA (Cape Forget-me-not)

### Hardy Annual

*928* **CAPENSIS.** Easily grown from seed. The flowers resemble a large Forget-me-not, but nicer in every respect, and very suitable for bouquets and cut flowers. A most lovely shade of a clear, deep blue with a white centre, 2 feet high. **Packet 10 cts.; ¼ ounce 25 cts.**

### Hardy Perennial Anchusa (Alkanet)

*930* **ITALICA, DROPMORE.** A variety which should be in every hardy border. 4 feet high. The flowers are of a beautiful gentian blue produced in long loose sprays. One of the few really blue flowers. Free and early flowering. If cut back after flowering, it will bloom again in the fall. **Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**

958 Aquilegia, Long Spurred Hybrids

962 Aquilegia, Single Mixe
960 Aquilegia, Double Mixe

## AQUILEGIA (Columbine)

### Hardy Perennial

Thrives luxuriantly in any good soil; suitable for the o garden, permanent beds or borders or edges of shrubb Blooms during May and June when flowers are scarce. Pla grow 2 to 3 feet high.

*956* **CŒRULEA HYBRIDS, MIXED.** A beautiful mixt of large single flowered varieties in a wide range of color **Packet 10 cts.; ⅛ ounce 50 cts.; ¼ ounce 85 cts.**

*958* **LONG SPURRED HYBRIDS, EXTRA CHOICE MIX** The flowers of this new strain are quite distinct from Aquilegias, having broader petals and longer spurs. Sha of blue, orange, scarlet, yellow, white, mauve, pink, etc. **Packet 15 cts.; ⅛ ounce 60 cts.; ¼ ounce $1.00**

*960* **FINEST DOUBLE FLOWERING, MIXED.** Beaut double flowers in various shades. Well adapted for cutt **Packet 10 cts.; ¼ ounce 30 cts.; ounce $1.00**

*962* **FINEST SINGLE FLOWERING, MIXED.** Large flow in a great variety of colors. Handsome and very showy. **Packet 10 cts.; ¼ ounce 25 cts.; ounce 85 cts.**

## AQUILEGIA ROOTS Hardy Perennial

*70B18* **Long Spurred Hybrids, Mixed Colors**

**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen**

964 Arabis, Alpina

966 Arctotis, Grandis

## ARABIS (Rock Cress)

### Hardy Perennial

*964* **ALPINA.** One of the earliest and prettiest spr flowering perennials, the plant attaining a height of not ov inches. Grows in a spreading tuft. Flowers white, deliciou fragrant, and in the early spring make a pleasing contr with the yellow flowers of Alyssum Saxatile Compactum. **Packet 10 cts.; ¼ ounce 25 cts.**

## ARCTOTIS (African Daisy)

### Hardy Annual

*966* **GRANDIS.** Forms branched bushes 2 to 3 feet hi flowers pure white on the upper surface, the reverse of petals being lilac blue. Easily grown, blooming all sum until frost. Valuable for cutting. **Packet 10 cts.; ¼ ounce 30 cts.; ounce 90 cts.**

970 Aristolochia, Sipho

971 Armeria, Formosa

## ARISTOLOCHIA (Dutchman's Pipe)

**Hardy Perennial Climber**

*970* **SIPHO.** A vigorous and rapid grower with large, heart-haped leaves, having curious flowers which resemble pipes. rows 50 feet or more in a season. Its handsome light green eaves give a quick dense shade. Flowers brownish purple.
**Packet 10 cts.; 3 packets 25 cts.**

## ARMERIA (Sea Pink or Thrift)

**Hardy Perennial**

*971* **FORMOSA.** Height 18 inches. Very useful in the hardy order and excellent for cutting, as the long-stemmed rose-olored flowers retain their brilliant appearance for a long while after being cut. Blooms early; valuable for rockeries.
**Packet 10 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.**

972 Artemisia or Summer Fir

1124 Balloon Vine

## *972* ARTEMISIA (Summer Fir)

**Hardy Annual**

Forms pyramidal shaped bushes with rich, dark green foliage, 3 to 5 feet high, branching freely, giving it the appearance of a nicely developed Christmas tree. It is pretty as a pot plant or may be grown successfully as a solitary specimen, clump or hedge.
**Packet 10 cts.**

## *1124* BALLOON VINE (Love-in-a-puff)

**Hardy Annual Climber**

A rapid growing climber, attaining a height of 10 to 16 feet. Bears small white flowers, followed by inflated seed pods resembling small balloons, hence the name.
**Packet 5 cts.; ounce 25 cts.**

**SOW MAULE'S SEEDS**
**There are None Better**

974 Asparagus, Plumosus Nanus

1136 Begonia, Prima Donna

**Order Your Seeds Now**

1140 Bidens

## ASPARAGUS (Lace Fern or Emerald Feather)

**Half Hardy Perennial**

For house use as pot plants, n hanging baskets, vases, etc., ew plants equal the Asparagus Fern. They thrive under onditions which would kill ther plants. The foliage, vhen cut, retains its color a ong time.

*974* **PLUMOSUS NANUS.** A lesirable pot plant of wonderful beauty. Cheerful, green, ern-like foliage, of delicate exture. Individual fronds or eaves grow from 4 to 8 inches across. Very graceful when used in bouquets.
**Packet 15 cts.; 100 seeds 85 cts.**

*976* **SPRENGERII.** This plant is especially adapted to suspended baskets, window boxes, vases, etc.; 1 to 4 feet. An excellent house plant, as it withstands a dry atmosphere, succeeding practically everywhere.
**Packet 10 cts.; 100 seeds 40 cts.**

976 Asparagus, Sprengerii

## BEGONIA

**Tender Perennial**

Beautiful bedding plants, easily raised from seed, doing well in full sunlight or shady positions. For winter flowering house plants, they are especially desirable.

*1135* **LUMINOSA.** Brilliant fiery dark scarlet.
**Packet 25 cts.; 3 packets 60 cts.**

*1136* **PRIMA DONNA.** Beautiful clear pink shading to carmine rose; everblooming.
**Packet 25 cts.; 3 packets 60 cts.**

*1137* **VERNON.** Brilliant deep carmine with a bright yellow centre. Rich metallic green foliage changing to dark red.
**Packet 15 cts.; 2 packets 25 cts.**

*1138* **SEMPERFLORENS, SINGLE MIXED.** Contains all colors.
**Packet 15 cts.; 2 packets 25 cts.**

## *1140* BIDENS (Black Dahlia or Cosmos)

**Hardy Annual**

The plants grow 2½ feet high, producing an abundance of crimson-maroon colored flowers of velvety texture about 4 inches in diameter. Excellent for cut flowers.
**Packet 15 cts.; 2 packets 25 cts.**

# Maule's Giant American Asters Hardy Annual

In recent years we have paid particular attention to American grown Asters, for they have greatly increased the popularit of this flower. We know of no other flower so easily raised from seed, which combines so much beauty with grace and us fulness and are more satisfactory than Asters. They make a brilliant effect when grown in masses and furnish a consta supply of cut flowers. On the inside front cover we illustrate seven sorts in colors. Every garden, large or small, shou contain Asters.

**GIANT ASTERMUM ASTERS.** A beautiful strain of the Comet type, in size the peer of the grandest Chrysanthemums; hence the appropriate name of Astermums. A conspicuous and valuable border, bedding or pot plant, attaining a height of 18 to 24 inches. The flowers are large, with long, gracefully curled petals. Unrivaled for table decoration, and particularly appreciated as cut flowers, coming in bloom a little earlier than the Crego type.

*983* **DARK BLUE. Packet 15 cts.; ⅛ ounce 50 cts.**
*984* **LAVENDER. Packet 15 cts.; ⅛ ounce 50 cts.**
*985* **ROSE PINK. Packet 15 cts.; ⅛ ounce 50 cts.**
*986* **SHELL PINK. Packet 15 cts.; ⅛ ounce 50 cts.**
*989* **PURE WHITE. Packet 15 cts.; ⅛ ounce 50 cts.**
*990* **MIXED COLORS.** All the above shades in mixture.
**Packet 10 cts.; ⅛ ounce 45 cts.; ¼ ounce 80 cts.**

## *4117* Giant Astermum Collection

**The largest of the Comet type**

One packet each of the above 5 separate colors (value 75c), .....for **65c**

1066 Aster, Violet King

**MAULE'S GIANT BRANCHING ASTERS.** These admirab Asters are usually at their best in September. The tendency form numerous branches gives the class its name. The flowe are 4 inches in diameter, rich and showy and are borne long stems.

*1101* **LIGHT ROSE PINK. Packet 10 cts.; ⅛ ounce 35 c**
*1102* **AZURE BLUE. Packet 10 cts.; ⅛ ounce 35 cts.**
*1103* **CRIMSON. Packet 15 cts.; ⅛ ounce 40 cts.**
*1104* **LAVENDER. Packet 10 cts.; ⅛ ounce 35 cts.**
*1105* **ROSE PINK. Packet 10 cts.; ⅛ ounce 35 cts.**
*1106* **SHELL PINK. Packet 10 cts.; ⅛ ounce 35 cts.**
*1107* **PURPLE. Packet 10 cts.; ⅛ ounce 35 cts.**
*1108* **DARK VIOLET. Packet 10 cts.; ⅛ ounce 35 cts.**
*1109* **PURE WHITE. Packet 10 cts.; ⅛ ounce 35 cts.**
*1110* **ALL COLORS MIXED.** All colors in this mixture.
**Packet 10 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.; ounce $1.**

## *4121* Giant Branching Aster Collection

**Particularly desirable for cutting**

We have selected 6 of the most desirable colors for this collection

One packet each of Crimson, Lavender, Rose Pink, Shell Pink, Purple and White (value 65c) for **50c**

**KING ASTERS.** Bear very large double flowers from Au ust to October. Of branching habit with vigorous growt stems long and stiff. In form the flower is distinct from a other variety, petals longer and broader and more or le quilled.

*1063* **PINK. Packet 15 cts.; ⅛ ounce 45 cts.**
*1065* **ROSE. Packet 15 cts.; ⅛ ounce 45 cts.**
*1066* **VIOLET. Packet 15 cts.; ⅛ ounce 45 cts.**
*1067* **WHITE. Packet 15 cts.; ⅛ ounce 45 cts.**
*1068* **MIXED COLORS.** Includes the four leading colors.
**Packet 10 cts.; ⅛ ounce 40 cts.; ¼ ounce 75 cts.**

## *4127* King Aster Collection

**Should be largely grown as they are so different**

One packet each of the above 4 separate colors (value 60c) .....for **40c**

**EARLY BRANCHING OR ROYAL ASTERS.** Has all the ood qualities of Maule's Late Branching type but comes to bloom in July or early August. Free flowering. Flowers e large, of beautiful form, petals flat and incurved or shell haped, which gives an effect of shading that enhances the eauty of the flower, which is ideal for cutting.

*1100* **MIXED COLORS.** A fine mixture, embracing all colors.
**Packet 10 cts.; ⅛ ounce 45 cts.; ¼ ounce 75 cts.**

**IMPROVED INVINCIBLE ASTERS.** Of robust, branching abit, a favorite for cutting or bedding. Large Peony-shaped owers on long stems.

*1050* **DARK BLUE. Packet 10 cts.; ⅛ ounce 35 cts.**
*1051* **CRIMSON. Packet 10 cts.; ⅛ ounce 35 cts.**
*1052* **LAVENDER. Packet 10 cts.; ⅛ ounce 35 cts.**
*1054* **PINK. Packet 10 cts.; ⅛ ounce 35 cts.**
*1055* **PURPLE. Packet 10 cts.; ⅛ ounce 35 cts.**
*1057* **WHITE. Packet 10 cts.; ⅛ ounce 35 cts.**
*1058* **MIXED COLORS.** A magnificent mixture of all colors.
**acket 10 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.; ounce $1.50**

**CREGO GIANT COMET ASTERS.** Plant strong and well branched, grows about two feet high, and produces many long flower stems, bearing immense fluffy flowers as fine as Chrysanthemums, measuring 4 to 5 inches in diameter; very profitable for the gardener or florist.

*1002* **AZURE BLUE. Packet 10 cts.; ⅛ ounce 35 cts.**
*1003* **CRIMSON. Packet 15 cts.; ⅛ ounce 40 cts.**
*1004* **LAVENDER. Packet 10 cts.; ⅛ ounce 35 cts.**
*1005* **ROSE. Packet 10 cts.; ⅛ ounce 35 cts.**
*1006* **SHELL PINK. Packet 10 cts.; ⅛ ounce 35 cts.**
*1007* **PURPLE. Packet 10 cts.; ⅛ ounce 35 cts.**
*1009* **WHITE. Packet 10 cts.; ⅛ ounce 35 cts.**
*1010* **MIXED COLORS.** Composed of all the colors.
**Packet 10 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.; ounce $1.50**

## *4123* Crego Giant Comet Aster Collection

**The shaggy arrangement of the petals makes the flowers especially desirable for cutting or garden decoration**

One packet each of the above 7 separate colors (value 75c) .....for **50c**

**DAYBREAK ASTERS.** Sturdy upright plants growing 12 to 18 inches high, and producing a mass of bloom unequalled by any other variety, from August to October. Every plant is a bouquet itself.

*1023* **MIXED COLORS.** All colors in a superfine mixture.
**Packet 10 cts.; ⅛ ounce 50 cts.; ¼ ounce 85 cts.**

*1080* **PEERLESS PINK ASTER.** The plants are of robust, branching habit, 24 to 30 inches high, bearing magnificent blooms on strong stems, averaging 18 inches in length; the globular-shaped flowers grow to an immense size, are of great depth and densely petaled. The center petals are prettily incurved, while the wide outer petals reflex, making a most artistic flower. The color is a very pleasing shade of rich shell pink. It blooms about the middle of August, being at its best during the early part of September; elegant for cutting.

**Packet 15 cts.; ⅛ ounce 45 cts.; ¼ ounce 75 cts.**

*1081* **PEERLESS WHITE.** Conceded to be the best white late branching Aster; of upright growth, extra large, double flowers on long stems. Similar in habit and growth to Peerless Pink offered above.

**Packet 10 cts.; ⅛ ounce 45 cts.; ¼ ounce 75 cts.**

*4115* **Maule's Collection of**

## America's Finest Giant Asters

**See inside front cover of this book for colored illustrations, which give but a faint idea of the size and beauty of these choice and desirable varieties.**

**7 of the Newest and Best (Value 80 cts.)**

**Only 50 cents**

992 Aster, Silver Pink

1111 Aster, Heart of France

*992* **SILVER PINK.** Of the branching type, long stemmed, very robust and large flowering. The color is a deep glowing pink, the tips of the petals having a silvery sheen which gives the flowers a most artistic and pleasing appearance. Very attractive.

**Packet 10 cts.; ⅛ ounce 50 cts.; ¼ ounce 85 cts.**

*1111* **HEART OF FRANCE.** Plants grow about 24 inches high, nicely branched, bearing from September until frost, large flowers of ruby-red, deepening with age, which color is retained to the end. A striking color; the best pure red Aster yet introduced. Very desirable for cut flowers and makes a brilliant bed or border plant.

**Packet 15 cts.; ⅛ ounce 45 cts.; ¼ ounce 75 cts.**

**MAULE'S EARLIEST BLOOMING ASTERS.** Blooms in July two weeks earlier than most of the other types. Of open spreading habit, producing flowers of good size on long stems 1½ feet high. A very distinct and valuable cut flower Aster for the home garden or florists.

*1026* **CRIMSON. Packet 10 cts.; ⅛ ounce 35 cts.**
*1027* **LAVENDER. Packet 10 cts.; ⅛ ounce 35 cts.**
*1028* **FLESH PINK. Packet 10 cts.; ⅛ ounce 35 cts.**
*1029* **ROSE PINK. Packet 10 cts.; ⅛ ounce 35 cts.**
*1030* **PURPLE. Packet 10 cts.; ⅛ ounce 35 cts.**
*1032* **WHITE. Packet 10 cts.; ⅛ ounce 35 cts.**
*1033* **MIXED, ALL COLORS.** Very fine range of colors.

**Packet 10 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.; ounce $1.50**

*4125* **Earliest Blooming Aster Collection**

**The First Asters to Bloom**

**One packet each of the above 6 separate colors (value 60 cts.) for..... 50c**

*982* **AMERICAN BEAUTY.** One of the most popular Asters of recent introduction. A most lovely shade of bright, carmine rose, almost identical in color to the famous American Beauty Rose. The flowers are large, fully double, incurved and borne on long, strong stems, making them especially desirable for cutting. Make a grand display in the garden. Valuable for cutting for bouquets. Profuse bloomers.

**Packet 10 cts.; ⅛ ounce 45 cts.; ¼ ounce 75 cts.; ounce $2.50.**

982 Aster, American Beauty

*1118* **MAULE'S CHOICE VARIETIES MIXED.** Over 7 varieties of Asters, including all types of various colors

**Packet 5 cts.; ⅛ ounce 25 cts.; ¼ ounce 45 cts.**

## ASTERS

**are one of our leading specialties.**

**At least 90% of our customers order Aster Seed; a convincing proof of the popularity of this wonderful flower.**

*991* **PACIFIC BEAUTY ASTER.** Of the Crego type, with immense flowers, the petals of which are long, wide and gracefully curled. The color is a beautiful shade of rich lavender, which, combined with the unusually attractive appearance of the flowers, is sure to make this variety a very popular one.

**Packet 15 cts.; ⅛ ounce 50 cts.; ¼ ounce 85 cts.**

## *980* MAULE'S ANNIVERSARY MIXTURE OF ASTERS

Absolutely unequaled for an assortment of cut flowers throughout the blooming season. It is a mixture of only the choicest standard and the newest sorts that can be secured and blended to suit the most critical lover of this grand flower. Included are the Invincibles, the Royals, Maule's Giant Branchings, the Cregos, Maule's Earliest Blooming, Daybreaks, Astermums, Kings and many other American giant Asters not listed separately but grown especially for this mixture.

**Packet 15 cts.; ⅛ ounce 40 cts.; ¼ ounce 75 cts.**

*1076* **MORETON PINK ASTER.** Of the Giant Crego type, very double, with long twisted petals. The color is a deep cerise like the Paul Neyron Rose, the finest bright pink Aster of this type. An aristocratic flower greatly admired. The gracefully curled, wide petals are of unusually attractive appearance; combined with the exquisite coloring, it is needless to say, this is certain to be a very popular variety.

**Packet 15 cts.; ⅛ ounce 50 cts.; ¼ ounce 85 cts.**

## *4119* Maule's Brilliant Aster Collection

**We have selected four popular Asters for this collection. Each is a different color; they are magnificent in every respect and especially desirable for cutting.**

| | |
|---|---|
| Crego Giant Comet, White | Moreton Pink |
| Giant Astermum, Lavender | Giant Branching, Crimson |

**One packet each of these 4 named distinct sorts (value 55c)**

## For Only 25 Cents

*1012* **CRIMSON GIANT.** Has all the good qualities of Maule's Giant Branching type, but is of upright growth, with extra large, densely double flowers, few under 4 inches across, on stems 15 to 18 inches long; in color a very rich blood-crimson, making a brilliant bed or border plant, and very desirable for cut flowers.

**Packet 10 cts.; ⅛ ounce 45 cts.; ¼ ounce 75 cts.**

*1112* **SENSATION.** Dark rich garnet or ox blood red. Grow 18 to 20 inches high, well branched and covered with perfect flowers until the advent of frost. Entirely distinct, being the reddest of all red Asters.

**Packet 10 cts.; ⅛ ounce 50 cts.; ¼ ounce 85 cts.**

**Lend this Catalog to your neighbor**

1120 Aster, Single Flowering

*1120* **SINGLE FLOWERING, MIXED COLORS.**

Large, single, Daisy-like flowers on long, slender stems. Very free blooming and desirable for cutting. Flowers measure 2 to 3 inches in diameter.

**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**

## BALSAM (Lady's Slipper)

**Hardy Annual**

An old and favorite, quick growing annual, producing large, brilliantly colored flowers. Blooms are borne along the stem, among the leaves; frequently the whole upper part of the plant is a mass of color. Height 10 to 30 inches. The Balsam is of the easiest culture, and succeeds in any rich soil. It is well to sow the seeds thickly, in a temporary row, and then transplant to permanent quarters.

1127 Balsam, Maule's Double Superb Strain, Mixed

*1126* **SUPERB CAMELLIA FLOWERED, MIXED COLORS.** A choice strain of perfectly double Balsams producing masses of brightest flowers.

**Packet 10 cts.; ¼ ounce 25 cts.; ounce 75 cts.**

*1128* **DOUBLE TALL MIXED.** All the best colors; very fine mixture.

**Packet 5 cts.; ¼ ounce 25 cts.**

*1132* **DOUBLE DWARF MIXED.** Plants make perfect little bushes with flowers that are double and the colors very pretty and pleasing. Plants grow 10 inches high.

**Packet 10 cts.**

*1133* **SPOTTED ROSE FLOWERED.** A group of double Balsams with spotted flowers; many shades.

**Packet 10 cts.; ¼ ounce 25 cts.**

*1127* **MAULE'S DOUBLE SUPERB STRAIN, FINEST MIXED.** Unrivaled for large size, perfect form, robust habit and diversity of rich and delicate colors. Flowers often 2 inches across, borne in wonderful profusion, and more uniformly double than any other strain. The habit of growth is bushy and branching. The range of color includes white, rose, yellow, buff, pomegranate, red, scarlet, crimson, purple, lilac and violet. We offer all the best colors in this mixture.

**Packet 10 cts.; ¼ ounce 30 cts.; ounce $1.00**

**MAULE'S SEEDS**
**Once Grown Always Grown**

*1131* **GOLIATH MIXED, ALL COLORS.** New Balsam or Lady's Slipper of remarkably robust growth. The lower portion of the stem is well covered with side branches, giving the plant a sturdy bush form. All branches are filled with very large double flowers, producing a charming and beautiful effect. Many colors and shadings.

**Packet 10 cts.; ¼ ounce 25 cts.; ½ ounce 40 cts.; ounce 75 cts.**

1131 Balsam, Goliath Mixed, All Colors

1143 Bignonia, Grandiflora

1145 Bitter Sweet

## BIGNONIA (Trumpet Creeper)

**Hardy Perennial Climber**

*1143* **GRANDIFLORA.** One of the handsomest hard climbers, strong growing, bearing large clusters of orang red flowers, which always attract humming birds. Most grown on trees or walls. Useful for covering unsight places, stumps or wherever a flowering vine is desired, thoug it can be cut back and made almost self-supporting. Usu height 10 to 30 feet.

**Packet 10 cts.; 3 packets 25 cts.**

## *1145* BITTER SWEET (Wax Work)

**Hardy Perennial Climber**

A handsome, native twining shrub of rapid growth, elegan for clinging to walls, trees, etc., and one of the most desirab for shade. Has beautiful large leaves and bears yellow flow ers in May and June, which are followed in the autumn wit clusters of bright orange fruit. Often used for house decor tion during the winter.

**Packet 10 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.**

## BAPTISIA (False Indigo) ROOTS Hardy Perennial

*70B28* **AUSTRALIS.** Dark blue pea-shaped flowers. Blooms in June. Two feet high.

**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen**

1146 Blue Daisy

1151 Blue Lace Flower

## *1146* BLUE DAISY (Blue Marguerite)

**Half Hardy Perennial**

Plant grows about 1½ feet high, of branching habit, pro ducing an abundance of clear, sky blue flowers. Very prett for summer decoration in the garden, and equally desirab for winter blooming.

**Packet 10 cts.; ⅛ ounce 35 cts.; ¼ ounce 60 cts.**

## *1151* BLUE LACE FLOWER

**Hardy Annual**

The umbel-shaped flowers, 2 to 3 inches across, are of rare and desirable shade,—the most beautiful clear coerulea blue. The form is similar to those of Queen's Lace Handker chief or Wild Carrot. One of the most popular flowers of re cent introduction. Plants grow about two feet high and bea profusely from July till frost, from seed sown out-doors i early spring.

**Packet 10 cts.; ⅛ ounce 35 cts.; ¼ ounce 60 cts.**

# Sow MAULE'S Seeds— There are None Better

1139 Bocconia, Cordata

1147 Boltonia, Glastifolia

1155 Calceolaria



1165 Calliopsis, Tall Mixed

## BOCCONIA (Plume Poppy or Tree Celandine)

**Hardy Perennial**

*1139* **CORDATA.** Leaves are glaucous green, large lobed and heart-shaped with silvery under surface. During July and August it produces freely spikes 2 to 3 feet long of large panicles of creamy white flowers. Height 5 feet.

**Packet 10 cts.; ¼ ounce 25 cts.; ounce 75 cts.**

1148 Brachycome, Mixed Colors

**70B30 BOCCONIA, CORDATA ROOTS**

**Hardy Perennial**

**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen**

## BOLTONIA (False Chamomile)

**Hardy Perennial**

*1147* **GLASTIFOLIA.** Six feet high, with immense numbers of white flowers nearly 1 inch in diameter, resembling the hardy Aster. Blooms from July until September. One of our showiest native perennial plants.

**Packet 10 cts.**

## BRACHYCOME (Swan River Daisy)

**Hardy Annual**

*1148* **MIXED COLORS.** Very pretty; grows about 8 inches high, and produces its blue or white flowers freely during the summer. Suitable for edging, borders or pot culture.

**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**



1152 Butterfly Flower, Wisetonensis Mixed

## BUTTERFLY FLOWER (Poor Man's Orchid)

**Hardy Annual**

Blooms in lavish profusion. Colors are rich and varied. Very satisfactory for vases or bouquets. If the seed is sown in the autumn, admirable pot plants may be had for the house.

*1152* **WISETONENSIS MIXED.** A most valuable strain, bearing countless butterfly-like flowers in a bewildering range of color, from pure white through the various shades to pink, crimson and mauve. Flowers larger than in the ordinary type of this variety. **Packet 10 cts.; ⅛ ounce 35 cts.**

*1154* **MIXED.** Height 18 inches; many types. All colors.

**Packet 5 cts.; ¼ ounce 25 cts.; ounce 75 cts.**

## CALCEOLARIA (Pouch Flower)

**Half Hardy Perennial**

Highly ornamental greenhouse or window plants, producing richly colored pocket-like flowers in abundance in the spring. The colors include yellow, brown, maroon and even crimson. Beautifully blotched and spotted in varied colors.

*1155* **HYBRIDA FINE MIXED. Packet 25 cts.**

## CALLIOPSIS (Tickseed)

**Hardy Annual**

Calliopsis is easily grown and will thrive anywhere. It makes a quick growth, and produces beautiful foliage. It is one of our brightest and best summer bloomers. Gold and maroon of the most brilliant hues are the prevailing colors. Excellent for cutting and massing. By keeping the old flowers cut off, the blooming period can be lengthened until the autumn.

*1165* **TALL MIXED.** All the best types are found in the mixture, containing the most desirable sorts and colors. One of the most useful of our garden flowers.

**Packet 10 cts.; ¼ ounce 20 cts.; ounce 60 cts.**

*1168* **DWARF MIXED.** The dwarf and tall sorts do not appear well together in one mixture, so we are offering them separately. The dwarf strains are of uniform growth from 6 to 8 inches high; fine for borders and massings.

**Packet 10 cts.; ¼ ounce 25 cts.**

## CALENDULA (Cape or Pot Marigold)

**Hardy Annual**

12 to 18 inches high. Succeeds everywhere; blooms continuously from early summer until killed by frost. Particularly bright in late fall; valuable for cutting or for pot culture during the winter.

1161 Calendula, Double Mixed

*1160* **ORANGE KING.** A very select strain of this popular flower. Plants grow about 18 inches high and the double, dark orange-red blossoms produced average over 3 inches across under ordinary field cultivation. For the florists, this strain is a money-maker.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 40 cts.**

*1161* **MIXED.** All the double sorts in a grand mixture. Producing an abundance of blooms from early spring until frost. Excellent for cut flowers, the colors ranging through the various shades of orange and yellow.

**Packet 5 cts.; ½ ounce 15 cts.; ounce 25 cts.**




## CAMPANULA (Canterbury Bells)

### Hardy Biennial

Large, bell-shaped flowers are borne in the greatest profusion. Easily grown in ordinary gardens. Seed sown early in-doors will produce plants that usually bloom the first summer. As this type is biennial, seed should be sown each year to have flowering plants each season.

*1173* **CUP AND SAUCER, MIXED COLORS.** A distinct and exceedingly beautiful variety of Campanula which is quite an acquisition to this class of hardy biennials. The bell or trumpet of the flower grows extra large, is the same color as the flower, presenting the form of a cup and saucer. Colors are blue, rose, lilac, white, and striped which we offer only in mixture. The plants are of strong growth, and their beautiful blooms almost completely hide the foliage.

**Packet 10 cts.; ⅛ ounce 40 cts.; ¼ ounce 75 cts.**

*1174* **MEDIUM, SINGLE and DOUBLE MIXED.** Height, 2 feet; beautiful bell-shaped flowers of pink, white and blue in a grand mixture.

**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**

1174 Campanula, Medium Mixed

1175 Canary Bird Flower

### Hardy Perennial Campanula (Bellflower, Hare Bell)

Old-fashioned, hardy plants. Beautiful and constant bloomers, thriving best in light, rich soil. If sown early, some of the varieties will bloom the first season.

*1172* **CHOICEST MIXED.** Embraces all the single and double flowering sorts. Free flowering; mixed varieties and colors.

**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**

## *1175* CANARY BIRD FLOWER

### Hardy Annual Climber

A very attractive climber, growing about 10 feet, bearing hundreds of beautifully fringed, yellow, bird-like flowers, having a fancied resemblance to a bird with its wings half expanded. A pretty window or outdoor vine.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 40 cts.**




1186 Candytuft, Sempervirens



1183 Candytuft, Hyacinth Flowered



1180 Candytuft, Lavender

## CANDYTUFT

### Hardy Annual

Suitable for massing in beds, adapted for borders or edgings and fine for cutting. Sow early and make sowings for succession. Height 1 foot.

*1183* **HYACINTH FLOWERED.** An improved strain, producing immense trusses of pure white bloom, each plant having five or six pyramidal spikes. Fine for bedding and cutting. **Packet 10 cts.; ½ ounce 40 cts.; ounce 75 cts.**

*1180* **LAVENDER.** Exceedingly showy and effective variety, bearing large spikes of rosy lavender colored flowers.

**Packet 10 cts.; ½ ounce 35 cts.; ounce 60 cts.**

*1184* **DWARF, LITTLE PRINCE.** This charming compact little Candytuft grows only about 6 inches high, and is a variety of especial merit for edgings or borders. The massive spikes are pure white.

**Packet 10 cts.; ½ ounce 40 cts.; ounce 75 cts.**

1176 Candytuft, Giant Empress

1182 Candytuft, Rose Cardinal

*1176* **GIANT EMPRESS.** Exceedingly fine, large spikes of pure white flowers.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 40 cts.**

*1182* **ROSE CARDINAL.** A beautiful and very desirable variety, bearing spikes of brilliant, deep rosy-red flowers.

**Packet 10 cts.; ½ ounce 35 cts.; ounce 60 cts.**

*1185* **MIXED, ALL COLORS.** All shades and varieties.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 45 cts.**

### Hardy Perennial Candytuft

*1186* **SEMPERVIRENS.** Much used for rockeries, edgings or in cemeteries. Flowers white. Height 8 inches.

**Packet 15 cts.; ⅛ ounce 60 cts.; ¼ ounce $1.00.**

## CANNA (Indian Shot Plant)

**Hardy Annual**

ttain a height of 3 to 7 feet and may be grown singly or masses. Leaves green or brownish red; flowers, scarlet, nson, yellow, cream, pink, white, etc., variously marked l dotted. Roots of any favorites may be saved by digging m in the fall and storing them in-doors during the winter. annas are easily grown from seed. For best results pierce seed in one spot with a file and soak the seeds in warm ter until they show evidence of swelling. Then sow in dy loam, and when grown to the second leaf pot off singly il the proper season for planting out. Seed sown March h furnished plants which bloomed July 15th.

**For roots of Cannas, see pages 134 and 135 of this Book**

*1187* **LARGE FLOWERING FRENCH AND AMERICAN.** ot as tall as the old-fashioned sorts, but with flowers of eat beauty; everywhere popular. These seedlings vary in lor, ranging through all shades of yellow and orange to hest crimson, scarlet and vermilion. Some plain, some otted. Our mixture contains only the best.
**Packet 10 cts.; ounce 40 cts.; ¼ pound $1.25.**

*1188* **MIXED.** This grand mixture of Cannas with highly rnamental foliage produces clusters of brilliant blossoms ll summer and fall from spring sown seed. They are simply arvelous, showing colors and variegations ranging from al- ost white to brilliant scarlet and dark maroon, rosy pink, ellow, orange, buff, lemon, striped, bronzed, tinted and varie- ated. Saved from a large collection of named sorts.
**Packet 10 cts.; ounce 35 cts.; ¼ pound $1.00.**

## *1190* CARDINAL CLIMBER

**Hardy Annual Climber**

A splendid, new, brilliant climber of great value. A strong nd rapid grower, attaining a height of 20 to 30 feet with eautiful deeply laciniated leaves and just covered with in- ense cardinal red flowers from midsummer till frost. Flow- rs measure 1½ to 2 inches across and are borne in clusters f 5 to 7 blooms each. See illustration at top of next column.
**Packet 15 cts.; ⅛ ounce 40 cts.; ¼ ounce 70 cts.**

1190 Cardinal Climber

1191 Carnation, Chabaud's

## CARNATIONS

**Hardy Perennial**

Carnations have within recent decades developed into types of rare beauty and fragrance. No flowers are more lovely. Free flowering, easily grown and a favorite either in flower beds, borders or pots.

*1191* **CHABAUD'S PERPETUAL EARLY FLOWERING, MIXED COLORS.** Large flowers in all the beautiful shades. Blooms in 5 months after sowing and continues to flower profusely. Highly recommended for earliness and range of colors.
**Packet 15 cts.; ⅛ ounce 50 cts.; ¼ ounce 85 cts.**

*1192* **CARNATIONS AND PICOTEES, FINEST MIXED.** The flowers are edged, spotted or splashed with some other colors. One of the showiest strains for out-door culture.
**Packet 20 cts.; ⅛ ounce 60 cts.; ¼ ounce $1.00.**

**MAULE'S MAMMOTH FLOWERING MARGUERITE.** They may be treated as annuals, or wintered with slight protection out-of-doors. Easily grown and make the best of bedding plants, blooming the first summer, and if lifted in September and potted, they will flower in the house throughout the winter. Our strain is an improved one; producing large flowers which are spicy and fragrant.

*1193* **STRIPED SORTS. Packet 15 cts.; ⅛ ounce 50 cts.**
*1194* **ROSE. Packet 15 cts.; ⅛ ounce 50 cts.**
*1195* **WHITE. Packet 15 cts.; ⅛ ounce 50 cts.**
*1196* **SCARLET. Packet 15 cts.; ⅛ ounce 50 cts.**
*1197* **YELLOW. Packet 15 cts.; ⅛ ounce 60 cts.**
*1198* **FINEST MIXED.** All the most desirable colors.
**Packet 10 cts.; ⅛ ounce 40 cts.; ¼ ounce 65 cts.; ounce $2.25.**

### *4131* Marguerite Carnation Collection

**Bloom in 4 to 5 Months from Sowing the Seed**

**One packet each of the above 5 separate colors (value 75 cts.) for..... 50c**

**To quickly cover a porch, arbor or fence, the Cardinal Climber is unsurpassed**

# CELOSIA (Cockscomb)

**Hardy Annual**

This showy plant of many forms is of the easiest culture, and is one of the most brilliant and effective of the summer bloomers. Well adapted for beds or borders.

1202 Chinese Woolflower, Dark Pink

## CHINESE WOOLFLOWER (Celosia Childsi)

Plants grow 2 to 3 feet high, branching freely, each branch terminating with a large roundish head like a ball of silky wool. Each branch supports numerous laterals with small heads of bloom, so that a plant looks like a huge bouquet. Valuable for cutting, and often used in a dried state.

*1201* **CRIMSON WOOLFLOWER.** Rich, bright crimson, deepening to dark crimson-scarlet as flower ages.
**Packet 15 cts.; ⅛ ounce 50 cts.; ¼ ounce 85 cts.**

*1202* **DARK PINK WOOLFLOWER.** Beautiful pink.
**Packet 15 cts.; ⅛ ounce 50 cts.; ¼ ounce 85 cts.**

*1203* **YELLOW WOOLFLOWER.** A rich shade of yellow.
**Packet 10 cts.; ⅛ ounce 50 cts.; ¼ ounce 85 cts.**

*1210* **CHINESE WOOLFLOWER, MIXED COLORS.**
**Packet 15 cts.; ⅛ ounce 40 cts.; ¼ ounce 75 cts.**

### *4135* Chinese Woolflower Collection

**The Best of All Celosias for Cutting**

**One packet each of the above 3 separate colors (value 40 cts.) for..... 30c**

*1208* **SPICATA.** Plants grow 3 feet in height, branch freely, each stem terminating in a round, slender pointed spike of bloom. The flowers at first are a soft bright rose, changing to silver white, so that a fully developed spike resembles a slender silver plume with a bright carmine tip.
**Packet 10 cts.; ⅛ ounce 45 cts.**

Celosia, Cristata or Crested

1208 Celosia, Spicata

*1205* **CRISTATA ROSE.** Of the dwarf or crested type, with large, dark rose-colored, comb-like heads. **Packet 10 cts.**

*1206* **CRISTATA YELLOW.** Of the dwarf or crested type, producing large, compact yellow heads. **Packet 10 cts.**

*1204* **CRISTATA MIXED.** All the best crested cockscomb types. **Packet 10 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.**

1209 Celosia, Pride of Castle Gould

1213 Centaurea, Cyanus, Double Blue

*1209* **PRIDE OF CASTLE GOULD.** Of the plume or feathe type. The colors include shades of yellow, orange, scarlet red and crimson which we offer in a mixture.
**Packet 15 cts.; ⅛ ounce 50 cts.; ¼ ounce 85 cts.**

*1207* **THOMPSON'S MAGNIFICA, MIXED COLORS.** A choic strain of the feathered type. Colors range from clear yellov to dark blood red.
**Packet 10 cts.; ¼ ounce 30 cts.; ounce $1.00.**



1211 Centaurea, Imperialis

1212 Centaurea, Marguerite

## CENTAUREA, Cyanus (Corn Flower)

**Hardy Annual**

Valuable old-fashioned flowers, which grow in any situation, and bloom continuously. Excellent for cutting and well known to every flower lover. Although it is a hardy annual the plants usually re-seed themselves and you will find them coming up year after year.

*1213* **DOUBLE BLUE.** Extra large double blue flowers.
**Packet 10 cts.; ¼ ounce 25 cts.; ounce 75 cts.**

*1214* **DOUBLE ROSE PINK.** Clear rose pink; desirable.
**Packet 10 cts.; ¼ ounce 25 cts.; ounce 75 cts.**

*1216* **DOUBLE WHITE.** Densely double, pure white.
**Packet 10 cts.; ¼ ounce 25 cts.; ounce 75 cts.**

*1218* **DOUBLE MIXED.** A mixture of all colors.
**Packet 10 cts.; ¼ ounce 20 cts.; ounce 50 cts.**

### *4139* Centaurea, Cyanus Collection

**Improved Forms of Old Favorites**

**One packet each of the above 3 separate colors (value 30 cts.) for..... 20c**

## CENTAUREA, Imperialis (Sweet Sultans)

**Hardy Annual**

Will flower freely in early summer from spring sown seed forming strong bushy plants 2 to 3 feet high. They are especially valuable for cutting, being sweet scented.

*1212* **GIANT MARGUERITE.** Exceedingly beautiful. The immense white, fragrant blossoms are borne on long stems
**Packet 10 cts.; ¼ ounce 30 cts.; ounce $1.00.**

*1211* **IMPERIALIS MIXED.** A magnificent mixture of all colors, including rose, yellow, white, purple, lilac, mauve blue, etc., some flowers having a centre of another color.
**Packet 10 cts.; ¼ ounce 25 cts.; ounce 85 cts.**

**Half Hardy Perennial Centaurea (Dusty Miller)**

*1215* **GYMNOCARPA.** Finely cut silvery foliage; elegant for rockeries, vases or hanging baskets. Height 18 inches making it a valuable plant for edging beds.
**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**

# CHRYSANTHEMUM

**Hardy Annual**

The single annual Chrysanthemums are extremely showy
d effective. They are Daisy-like in shape, and are much
ed for cut flower purposes. The perennial sorts are both
ıgle and double. All are easily grown from seeds.

1231 Chrysanthemum, Baby Golden Glow

*1231* **BABY GOLDEN GLOW.** Golden Queen. A most charming annual growing about 15 to 18 inches high, bearing scores of bright yellow double flowers. The plants begin to bloom almost as soon as set in the open ground, affording an almost unlimited supply of cut flowers. One of the best bedders. Likened to Rudbeckia Golden Glow on account of color and profusion of bloom.
**Packet 10 cts.; ¼ ounce 25 cts.**

*1225* **BRIDAL ROBE.** Plants grow about 2 feet high; with
ıely cut foliage and produce pure white double flowers from
rly summer till frost. Desira-
e for cutting.
**acket 10 cts.; ⅛ ounce 30 cts.**

*1229* **NORTHERN STAR.** Pure
hite fringed petals with a ca-
ıry-yellow colored zone around
dark brown eye. These Daisy-
ke flowers, 3 inches across,
e extensively grown for cut
owers.
**acket 10 cts.; ¼ ounce 25 cts.**

*1227* **SINGLE FINEST MIXED.** Painted Daisies.
hese make a beautiful dis-
ay. The Daisy-like flowers
e handsomely marked, usu-
ly in bands or rings of
any colors.
**Packet 5 cts.; ¼ ounce 20 cts.; ounce 60 cts.**

*1233* **CORONARIUM FINEST DOUBLE MIXED.** Compact,
ushy growth 18 inches in
eight, flowers double, shading
rom light yellow to white.
hey bloom profusely from
arly summer until frost, and
hen grown in large beds their bright colors make a splendid
howing. **Packet 10 cts.; ¼ ounce 25 cts.**

1229 Chrysanthemum Northern Star
1233 Chrysanthemum Double Mixed

**Hardy Perennial Chrysanthemum**

*1223* **CHINESE AND JAPANESE, FINEST MIXED VARIETIES.** The late flowering Chrysanthemums, the glory of autumn, have long been considered our finest perennials. The color range is almost endless, though red, yellow, and white flowers predominate. Our Chinese and Japanese Chrysanthemum seed is saved from double flowers of the choicest strain, which may be expected to produce a large percentage of double flowers, the balance being very desirable singles especially suitable for cutting. This seed will produce blooming plants the first season. Very few people realize how easily they may be grown. Finest mixed varieties.
**Packet 25 cts.; 2 packets 45 cts.; 5 packets $1.00.**

1223 Chrysanthemum, Chinese and Japanese

1235 Cineraria, Dwarf Finest Mixed

1243 Cobaea, Scandens

# CINERARIA (Cape Aster)

**Half Hardy Perennial**

A favorite, handsome, free flowering greenhouse or window plant. Shades include blue, purple, crimson, maroon, etc.; some flowers showing a clear white eye. Individual flowers are often 2 or more inches across.

*1234* **TALL FINEST MIXED.** Large flowering varieties, unsurpassed for size and gorgeous colors. Height 1 foot.
**Packet 25 cts.; 3 packets 60 cts.**

*1235* **DWARF FINEST MIXED.** Compact, dwarf plants, less than 1 foot high. Large heads, large flowers in a wide range of beautiful colors.
**Packet 35 cts.; 2 packets 60 cts.**

# COBAEA (Cathedral Bells)

**Hardy Annual Climber**

A vigorous and rapid growing climber, attaining a height of 30 to 50 feet and bearing an abundance of large, bell-shaped flowers. In sowing the seeds place them edgewise, and merely cover with light soil; otherwise the seed will often fail to germinate. Makes a fine indoor winter vine.

*1242* **ALBA.** A white variety of Scandens. Beautiful. Valuable for covering trellises, arbors, old trees, etc., and will cling to any rough surface.
**Packet 10 cts.; ¼ ounce 50 cts.; ounce $1.75.**

*1243* **SCANDENS.** Large bell-shaped, rich purple flowers; 2 inches long, 1½ inches across. Free from insect pests.
**Packet 10 cts.; ¼ ounce 30 cts.; ounce $1.00.**

# CHRYSANTHEMUM ROOTS Hardy Perennial

**HARDY OLD-FASHIONED VARIETIES.** Bloom in October and November, when nearly all other outdoor flowers are gone. 3 to 4 feet high. Showy when in bloom, desirable for cutting. **SEPARATE COLORS:**
*70B46* **Pink,** *70B48* **Red,** *70B50* **White or** *70B52* **Yellow.**
**Any color, 30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen**

*70B54* **One root each of the 4 separate colors for only $1.00.**

1238 Clematis, Mixed Varieties

# CLEMATIS (Virgin's Bower)

**Hardy Perennial Climber**

Very beautiful climbers of the greatest utility for veranda, trellis, etc., adornment or for sloping banks, and useful for planting among rock work. Of strong, rapid growth.

*1236* **PANICULATA.** The vine attains a height of 20 to 30 feet and never troubled by insects. Bears a dense mass of small, star-like, white, fragrant flowers.
**Packet 10 cts.**

*1238* **MIXED.** All the best varieties in one grand mixture.
**Packet 15 cts.**

# COLEUS (Flame Nettle)

**Half Hardy Perennial**

Foliage plants of exceeding richness and beauty; indispensable for borders and bedding; excellent for greenhouse and window culture.

*1244* **BRIAR CREST MAMMOTH RAINBOW MIXED.** For years we have prided ourselves that our collection of Coleus was unsurpassed; but have kept right on breeding it up, until now, in variety of colors, shape of foliage, mammoth size, etc., we have secured a selection remarkably rich in color combinations. Highly ornamental as a pot plant, especially with its spikes of blue flowers in autumn.

**Packet 25 cts.; 2 packets 45 cts.; 5 packets $1.00**

*1245* **LARGE-LEAVED SUNSET SHADES.** A strain of Coleus remarkable for diversity and richness of color combinations. Leaves sometimes attain a length of 10 or 12 inches and a width of 6 or 8 inches. Foliage very ornamental, being curled, serrated, cut or fringed in a most delicate and varied way. The prevailing colors are indicated by the name, being a rich combination of all the tints in a gorgeous sunset. The handsomest foliage plants obtained so easily from seed, making fine specimen plants in two or three months.

**Packet 20 cts.; 1/16 ounce $1.00**

*1246* **CHOICEST HYBRIDS.** From the best named sorts.

**Packet 15 cts.; 1/16 ounce 75 cts.**

*1247* **FINEST MIXED.** Tall growing, with smaller leaves.

**Packet 10 cts.**

1245 Coleus, Large-Leaved Sunset Shades

## *70B60* COREOPSIS ROOTS Hardy Perennial

**HARVEST MOON.** Fine for cut flowers throughout the summer. Long-stemmed, rich, golden-yellow.

**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen**

1254 Coreopsis, Harvest Moon

# COREOPSIS

**Hardy Perennial**

The Coreopsis is one of the showiest of the yellow flowered hardy perennials. Culture easy; thrive anywhere.

*1254* **HARVEST MOON.** Producing large, long stemmed, rich golden-yellow flowers, in great profusion all summer.

**Packet 10 cts.; ¼ ounce 25 cts.; ounce 75 cts.**

1241 Cosmidium, Orange Crown Mixed

1268 Cyclamen, Giganteum

# COSMIDIUM

**Hardy Annual**

*1241* **ORANGE CROWN MIXED.** Forms dense bushes, abo 2 feet high, and produces throughout the summer beautif flowers in shades of orange and yellow to the darkest velve brown. Recommended for cutting, borders, flowering hedg and pot culture.

**Packet 10 cts.; ¼ ounce 30 cts.; ounce $1.00**

# CYCLAMEN (Alpine Violet)

**Half Hardy Perennial**

One of the choicest of all the greenhouse or window plant Foliage rich and beautiful; flowers bird-like and fragran Colors white, pink, crimson, etc Seed should be sown ar time during the winter, spring or autumn in light soil, co taining leaf mould.

*1267* **PERSICUM, CHOICE MIXED.** All the best colors.

**Packet 20 cts.; 2 packets 35 cts.; 100 seeds $1.00**

*1268* **GIGANTEUM.** The leaves beautifully marked wit showy silvery blotches make the plants with their larg flowers very attractive. All the most desirable colors.

**Packet 25 cts.; 100 seeds $1.75**

# CYPRESS VINE

**Hardy Annual Climber**

One of the very desirable and most handsome climbers Fern-like foliage; 15 feet. Vine bears masses of beautifu star-shaped flowers which, with its finely cut foliage, make it particularly desirable for training upon a light, ornamenta trellis.

*1271* **SCARLET. Packet 10 cts.; ½ ounce 30 cts.**
*1272* **WHITE. Packet 10 cts.; ½ ounce 30 cts.**
*1273* **MIXED. Packet 10 cts.; ½ ounce 25 cts.; ounce 40 cts**

Cosmos, Extra Early Mammoth Flowering

# Maule's Wonderful Cosmos

**Hardy Annual**

A tall, graceful, showy annual, enjoying the widest popularity. It grows 3 to 6 feet high. Bloom in mid-summer and autumn.

**EXTRA EARLY MAMMOTH FLOWERING.** The single flowers, borne in abundance on long and graceful stems, are 4 to 5 inches across. Seeds sown out of doors in early spring produce plants that will bloom in 60 to 70 days, and continue until killed by frosts. The earliest single flowering strain we know of, being two months ahead of all others, which will be appreciated by those in the northern states.

*1262* **PINK. Packet 10 cts.; ¼ ounce 30 cts.; ounce $1.00**
*1263* **CRIMSON. Packet 10 cts.; ¼ ounce 30 cts.; ounce $1.00**
*1264* **WHITE. Packet 10 cts.; ¼ ounce 30 cts.; ounce $1.00**
*1265* **EXTRA EARLY MAMMOTH FLOWERING, MIXED.**
**Packet 10 cts.; ¼ ounce 25 cts.; ½ ounce 40 cts.; ounce 75 cts.**

**LATE MAMMOTH FLOWERING.** The flowers are immense and of perfect form, with wide overlapping oval petals. The flower is borne on long stems, making them exceptionally desirable for cutting. Plant grows 4 to 6 feet high, and blooms in September and October.

*1256* **LATE MAMMOTH FLOWERING, ALL COLORS MIXED.**
**Packet 10 cts.; ¼ ounce 20 cts.; ounce 50 cts.**

### Maule's Special Mixture of Single and Double Cosmos

*1261* **ALL VARIETIES MIXED.** Early and late.
**Packet 15 cts.; ¼ ounce 50 cts.; ½ ounce 85 cts.**

## RAY-FLOWERING COSMOS

This is quite a unique departure from the ordinary Cosmos. The blooms are borne most freely with a greatly increased number of petals, but instead of having flat expanded petals, these are fluted in an irregular and most artistic manner. They are most valuable for cut-flowers, as they are easily arranged into loose and airy bouquets.

*1269* **CRIMSON RAY. Packet 10 cts.; ¼ ounce 25 cts.**
*1270* **WHITE RAY. Packet 10 cts.; ¼ ounce 25 cts.**



Cosmos, Ray Flowering

## Single and Double Cosmos Collection

See back cover for colored illustrations

*4142* **One packet each Pink, Crimson and White Extra Early Single Cosmos and 1 packet Pink Beauty Late Double Cosmos for 35c**

## Double Crested or Anemone Flowered Cosmos

A new type differing from the original Cosmos in the formation of the center of the flower, which develops a crown or crest, like an Anemone; the guard petals are the same in both types. We offer selected strains which come about 75% double.

## EXTRA EARLY DOUBLE CRESTED COSMOS

A new strain, highly prized everywhere and especially recommended for localities north of New York as it perfects its beautiful double flowers in about 70 days from the time seed is sown and continues to bloom until cut down by frost. Forms a perfect bush about 3 feet high.

*1248* **CRIMSON. Packet 20 cts.; ⅛ ounce 85 cts.**
*1249* **PINK. Packet 20 cts.; ⅛ ounce 85 cts.**
*1250* **WHITE. Packet 20 cts.; ⅛ ounce 85 cts.**

*4141* **Extra Early Double Crested Cosmos Collection**
**Last well when cut**
**One packet each of the above 3 separate colors (value 60c) ..... for 50c**

*1251* **EXTRA EARLY DOUBLE CRESTED, MIXED.**
A well balanced mixture of the three colors.
**Packet 15 cts.; ⅛ ounce 75 cts.; ¼ ounce $1.25**

## LATE DOUBLE CRESTED COSMOS

In the late type of double crested Cosmos, the flowers vary in their degree of doubleness, some having the Anemone center and others being perfectly double. Most artistic and beautiful in either form. Cut flowers have good keeping qualities.

*1260* **CRIMSON KING. Packet 15 cts.; ⅛ ounce 50 cts.**
*1258* **PINK BEAUTY. Packet 15 cts.; ⅛ ounce 50 cts.**
*1259* **WHITE QUEEN. Packet 15 cts.; ⅛ ounce 50 cts.**

*4143* **Late Double Crested Cosmos Collection**
**Profuse Bloomers on long stems**
**One packet each of the above 3 separate colors (value 45c) ..... for 35c**

*1266* **LATE DOUBLE CRESTED, FINEST MIXED.**
**Packet 15 cts.; ⅛ ounce 40 cts.; ¼ ounce 70 cts.**

Cosmos, Double Crested or Anemone Flowered

1274 Dahlia, Extra Choice Large Flowering Double Mixed

## DAHLIA

**Half Hardy Perennial**

Dahlia plants, from seed sown indoors in a shallow box in March or April and transplanted as soon as danger of frost is past, will bloom abundantly the first summer and give a magnificent display of bright colors late in the season. Seed offered below is saved from large flowering double Dahlias. As these flowers are hybrids, we cannot guarantee type; no two flowers will be exactly alike and some are likely to be single-flowering. Roots of any favorites may be saved, storing them in the house during the winter.

*1274* **EXTRA CHOICE LARGE FLOWERING, DOUBLE MIXED.** This seed is saved from choice specimens of the standard sorts, as well as the leading and best introductions that make their appearance each year. A choice mixture of show, cactus, decorative, peony and pompon varieties. Some singles may be expected.

**Packet 15 cts.; ⅛ ounce 60 cts.; ¼ ounce $1.00**

*1275* **DOUBLE CACTUS, MIXED.** Most popular Dahlia grown, petals pointed (see illustration), distinct and elegant. Seed is saved from the most select and perfectly double blooms and many double flowers may be expected, besides there is always the chance of some handsome new varieties being obtained.

**Packet 20 cts.; ⅛ ounce 75 cts.; ¼ ounce $1.25**

*1276* **DOUBLE EXTRA FINE MIXED.** This splendid assortment embraces many varieties.

**Packet 10 cts.; ⅛ ounce 50 cts.; ¼ ounce 85 cts.**



¼ Size

1275 Dahlia, Double Cactus Mixed

For roots of Dahlias, see pages 136 and 137 of this Book

## *1283* DAISY, THE SHASTA

**Hardy Perennial**

Most attractive in the perennial border; the flowers averaging 4 inches in diameter, are borne on long, stiff stems. It blooms freely from July for several months, and the flowers are desirable for cutting. The petals or rays are pure glistening white, with small golden yellow centres. If sown early, it will flower the same season. Height 2½ ft.

**Packet 10 cts.; ⅛ ounce 35 cts.**

*70B64* **SHASTA DAISY ROOTS** **Hardy Perennial.**

**50 cts. each; 3 for $1.25; 6 for $2.25; $4.25 per dozen**

## DAISY, ENGLISH (Bellis)

**Hardy Perennial**

A low growing, spring flowering plant easily raised from seed and in high favor for edgings and borders.

1280 Daisy, Longfellow

*1281* **GIANT FLOWERED WHITE.** Exceedingly large, pure white flowers, with flat petals. Almost as large as a good sized Aster.

**Packet 15 cts.; 1/16 ounce 50 cts.; ⅛ ounce 75 cts.**

*1280* **LONGFELLOW.** The large flowers of this handsome Daisy are of a rich dark rose, perfectly double and borne on long stiff stems. Of unusual merit and deserves to be largely cultivated; excellent for bouquets.

**Packet 10 cts.; ⅛ ounce 50 cts.**

*1282* **DOUBLE MIXED.** **Packet 10 cts.; ⅛ ounce 50 cts.**

## DAISY, AFRICAN GOLD

**Hardy Annual**

Extremely showy; growing 12 to 15 inches high and bearing flowers 2½ inches in diameter profusely the greater part of the summer and fall. Does best in a dry, sunny situation.

*1313* **AFRICAN GOLD DAISY.** Of a glossy terra-cotta orange with a dark disc surrounded by a black zone.

**Packet 10 cts.; ⅛ ounce 25 cts.**

*1314* **HYBRIDS MIXED.** From the purest white through the various shades of yellow and orange to rich salmon.

**Packet 10 cts.; ¼ ounce 35 cts.; ounce $1.25**

## DATURA (Trumpet Flower)

**Hardy Annual**

*1284* **WRIGHTII.** Magnificent, large trumpet shaped fragrant flowers, pure white at the centre shading into lilac and blue. Plant grows 3 feet high.

**Packet 10 cts**




1284 Datura, Wrightii

*1285* **GOLDEN QUEEN.** Height and extent of plant 3 feet. Flowers golden yellow.

**Packet 10 cts**

*1286* **DOUBLE WHITE.** Exquisitely double and pure white. Strong growing and ornamental. Height, 3 feet.

**Packet 10 cts**

1289 Delphinium, Mammoth Prize Exhibition Mixture

## DELPHINIUM (Hardy Larkspur)

**Hardy Perennial**

One of the most popular as well as the most beautiful perennial plants for garden decoration or cut-flower purposes. An old favorite, greatly improved.

A succession of flowers may be expected from spring to early autumn, especially if the spikes which have flowered early are cut down to the ground; fresh growth will then be produced which will give blossoms.

*1290* **BELLADONNA.** Blooms more freely and continuously than any hardy Larkspur grown. The turquoise-blue color of the bloom is not equalled for delicacy and beauty by any other flower; 3 feet high.

**Packet 20 cts.; 1/16 ounce 50 cts.; ⅛ ounce 75 cts.**

*1292* **BELLAMOSA.** Has the same free and continuous blooming qualities as Belladonna but the blooms are rich, deep blue. Just as desirable for cutting or garden decoration.

**Packet 20 cts.; 1/16 ounce 60 cts.; ⅛ ounce $1.00**

*1288* **GOLD MEDAL HYBRIDS.** A choice strain of mixed hybrids, the flowers varying from the palest to the darkest shades of blue.

**Packet 15 cts.; ⅛ ounce 60 cts.; ¼ ounce $1.00**

*289* **MAULE'S MAMMOTH PRIZE EXHIBITION MIXTURE.** We believe these to be the choicest strain of mixed hybrids in cultivation, both for size of bloom and spike, as well as rich and delicate colors. Immense spikes of the most beautiful flowers of every imaginable shade of blue, varying from the palest silvery-blue to the deepest indigo. The blooming season is long; in fact they will bloom from spring till fall.

**Packet 25 cts.; 1/16 ounce 85 cts.; ⅛ ounce $1.50**

### DELPHINIUM ROOTS Hardy Perennial

*70B66* **BELLADONNA (Light Blue).**

*70B68* **BELLAMOSA (Dark Blue).**

**Either variety, 30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen; 25 for $5.00**

*70B70* **GOLD MEDAL HYBRIDS, MIXED COLORS.**

**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen**

*70B72* **Mammoth Prize Exhibition Mixture.**

**50 cts. each; 3 for $1.25; 6 for $2.25; $4.25 per dozen**

## DIANTHUS (Pinks)

**Hardy Annual**

Dianthus are one of the most popular and satisfactory of our summer flowers. The plants soon become a mass of bloom and continue so until hard frost. Grow 12 to 15 inches high and literally covered with flowers of rich and varied colors.

*1307* **LUCIFER.** Double Fringed Pinks. Flowers of a beautiful orange scarlet color, nearly two inches across, on long stems, which makes it very valuable for cutting. Plant grows about 12 to 15 inches high. A fine bedder.

**Packet 10 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.**

1304 Dianthus, Snowball

1294 Dianthus, Heddewigii

*1304* **SNOWBALL.** Large, double white flowers, which are fine for cutting.

**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**

1296 Dianthus, Marvelous

*1294* **HEDDEWIGII.** Double flowers ranging from white to crimson, some laced or striped. All colors in a mixture.

**Packet 10 cts.; ¼ ounce 30 cts.**

*1296* **MARVELOUS.** The same as Dianthus Wonderful or Fringed Pink. A remarkable, distinct new Fringed Japanese Pink. The plants grow from 12 to 15 inches high, and produce large flowers 3 to 4 inches across, on stiff, upright stems. From a third to a half of the flower seems to consist of graceful fringes, turned and twisted in all directions, giving an appearance both pretty and unique. A wide color range.

**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**

*Dianthus are continued on page 100*

1293 Dianthus, Royal Pinks

1306 Dianthus, Mourning Cloak

*1293* **ROYAL PINKS.** Single flowering blossoms of a new shape, the petals being curled, waved and twisted, each covering half of another; beautifully fringed. The colors vary from white to intense red. We offer a fine mixture.
**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**

*1302* **SALMON KING.** The flowers are large, well doubled and nicely dentated, appearing in great numbers. The color is a brilliant salmon rose.
**Packet 10 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.**

*1306* **MOURNING CLOAK.** A double Dianthus of so dark a maroon as to be almost black. Every petal faintly bordered with white.
**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**

1310 Dianthus, Plumaris, Double and Single Mixed

### Hardy Perennial Dianthus
### (Grass, Border, Feather, Clove or Spice Pinks)

**PLUMARIS.** The flowers are large, borne in a great variety of colors and markings, with fringed edges; sweet scented, spicy fragrance and almost every color known is shown to some degree. They are excellent, hardy plants.

*1308* **DOUBLE MIXED.** Double and semi-double varieties.
**Packet 10 cts.; ⅛ ounce 40 cts.; ¼ ounce 75 cts.**

*1309* **SINGLE MIXED.** Splendid flowers, beautifully fringed.
**Packet 5 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**

*1310* **DOUBLE AND SINGLE MIXED.** A mixture of single, double and semi-double hardy varieties in many colors.
**Packet 10 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.**

1315 Digitalis, Giant Shirley

## DIGITALIS
(Foxglove)

### Hardy Perennial

Showy and especially useful among shrubbery and in half shady places, though it grows equally as well in open sunlight situations. Succeeds under almost all conditions. Flowers in June and July.

*1311* **GLOXINIAFLORA, MIXED.** Grows 3 to 5 feet high. Handsomely marked and finely spotted Gloxinia-like flowers.
**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**

*1315* **GIANT SHIRLEY, MIXED.** 5 to 7 feet high, with flower heads over 3 feet long, crowded with large blossoms ranging in color from white and shell-pink to deepest rose. Many handsomely dotted with crimson, maroon, or chocolate.
**Packet 15 cts.; ⅛ ounce 40 cts.; ¼ ounce 70 cts.**

Very few people are self-satisfied. Something new, different or improved is always wanted. Our flower seed list contains many varieties which you probably have never grown. Try as many new ones as space will permit. We are sure you will be pleased. Bulbs and roots are offered on pages 125 to 139, inclusive.

1326 Eschscholtzia, New Hybrids, Mixed

## ESCHSCHOLTZIA (California Poppy)

### Hardy Annual

Extremely handsome, profuse blooming, low and quick growing plants, with finely cut foliage and cheerful Poppy like blossoms. Sow the seed where the plants are to remain.

*1326* **NEW HYBRIDS MIXED.** Wonderful colors including soft pink, scarlet, chrome, coppery red, mauve, claret and other unusual shades. A most gorgeous sight when in full bloom, flowering profusely until late in the autumn. A distinct range of the most beautiful colors.
**Packet 10 cts.; ¼ ounce 35 cts.; ½ ounce 60 cts.**

*1321* **GOLDEN WEST.** The flowers are immense in size of a light canary yellow with an orange blotch at the base of each petal. **Packet 10 cts.; ¼ ounce 20 cts.; ounce 50 cts.**

*1325* **MIXED.** A wide range of beautiful colors.
**Packet 5 cts.; ½ ounce 25 cts.; ounce 40 cts.**

1328 Euphorbia, Heterophylla

9 Euphorbia, Variegata

## EUPHORBIA

**Hardy Annual**

The foliage is exceedingly ornamental; the plants are largely used in beds or borders.

*1328* **HETEROPHYLLA.** Fire on the Mountain. Resembles in habit and color the hothouse Poinsettia; of bush-like form with smooth, glossy, green leaves which become orange scarlet, and present a brilliant and attractive appearance. **Packet 10 cts.**

*1329* **VARIEGATA.** Snow on the Mountain. A showy border plant with foliage veined and margined with white; flowers white.

**Packet 10 cts.; ¼ ounce 25 cts.**

## FEVERFEW

**Hardy Annual**

*336* **IMPROVED DOUBLE WHITE.** Well known free wering annual plants, having double pure white flowers. foot high. **Packet 10 cts.; ¼ ounce 25 cts.**

337 Fuchsia, Choice Mixed Hybrids

## FUCHSIA

(Lady's Ear Drop)

**Half Hardy Perennial**

Shrubby plants, adapted to the house in winter and to the shaded open air border in the summer. Of easy culture from seed. One of the most beautiful and satisfactory of all the window plants. The flowers are delicate and graceful in form and rich in color. The shades include red, white, purple, etc., in various combinations. Seedlings will bloom freely in the year that seed is sown.

*1337* **CHOICE MIXED HYBRIDS.** The best collection of single and double sorts, embracing all the colors to be had in Fuchsias.

**Packet 25 cts.; 2 packets 45 cts.**

## EVERLASTING FLOWERS

**Hardy Annual**

*1331* **ALL VARIETIES MIXED.** A mixture of all the different varieties of everlasting flowers which can be dried and used for winter decoration.

**Packet 10 cts.; ¼ ounce 30 cts.**

## EVERLASTING PEA (Hardy Sweet Peas)

**Hardy Perennial Climber**

A showy, perennial climber, attaining a height of 6 to 8 feet when trained upon a trellis or arbor. Not fragrant.

*1332* **WHITE.** Beautiful large white flowers. **Packet 10 cts.**

*1333* **SPLENDENS.** Brilliant rosy-red flowers. **Packet 10 cts.**

*1334* **MIXED COLORS.** **Pkt. 10 cts.; ¼ oz. 30 cts.; ½ oz. 50 cts.**



## FERNS

**Half Hardy Perennial**

Ferns can be grown easily from seed. Fill a clean pot with fine earth. Put the pot in a saucer and immerse in boiling hot water to kill all weed seeds or insects in the soil. After the soil has cooled strew the fern seed over the top of the soil but do not cover it. Put a piece of glass on top of pot, and keep the saucer full of water. Never put water on top of soil. In a short time the soil will be covered with a green moss-like growth, and in a few weeks the little fern leaves will appear.

*1335* **CHOICEST MIXED.** From a fine collection. **Pkt. 25 cts.**

1338 Gaillardia, Lorenziana

1341 Gaillardia, Fine Mixed

## GAILLARDIA (Blanket Flower)

### Hardy Annual

Exceedingly beautiful, growing 1 to 2 feet high. The flowers are very showy and excellent for beds or for cutting. Bloom in remarkable profusion from early summer till November.

*1338* **LORENZIANA, MIXED.** Double flowers in rich shades of crimson, garnet, lemon, orange, etc. Very attractive.
**Packet 10 cts.; ¼ ounce 25 cts.**

### Hardy Perennial Gaillardia

The perennial Gaillardia is fine for cutting; should be in every hardy border as they take care of themselves, require no protection and will thrive in almost any soil or position. If seed is sown early, the plants will begin blooming in June and continue till frost.

*1341* **FINE MIXED.** Flowers of wonderfully large size, highly colored and many beautiful markings.
**Packet 10 cts.; ¼ ounce 30 cts.**

1355 Gladiolus, Large Flowering Hybrids

### *71B08* GAILLARDIA ROOTS

**Hardy Perennial**

Many beautiful colors.
**30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen**



1356 Globe Amaranth, Fine Mixed

## GLADIOLUS

### Half Hardy Perennial

Can be grown to bloom the first season from seed, producing good bulbs for the second year's blooming.

*1355* **LARGE FLOWERING HYBRIDS, FINEST MIXED.** Saved from the largest flowering varieties in a wide range of colors.
**Packet 15 cts.; ⅛ ounce 40 cts.**

**For bulbs of Gladiolus, see pages 138 and 139 of this Book**

## GLOBE AMARANTH (Gomphrena)

### Hardy Annual Everlasting

Clover-like flowers of white, purple, striped, etc., which should be cut just before they are fully ripe and hung heads downward to dry.

*1356* **FINE MIXED.** **Packet 10 cts.; ¼ ounce 25 cts.**

1348 Geranium, Zonale Mixed

## GERANIUM (Pelargonium)

### Half Hardy Perennial

Easily raised from seed which if sown early will produc plants that will flower the first year. Geraniums enjoy a almost universal popularity. They are very popular plant suitable for pot culture in the winter or for bedding purpose in the summer. They form nice, bushy plants, bearing cor tinuously many gorgeous flowers in variously brilliant color

*1348* **ZONALE MIXED.** Our seed is saved from only th best and largest flowers which are greatly improved and en larged, round, and of the most perfect form. The colors in clude shades of crimson and scarlet, pink, rose, salmon, blus white, etc., in mixture.
**Packet 20 cts.; 1/16 ounce 50 cts.**

1346 Geranium Finest Varieties Mixed



1358 Gloxinia, Choicest Hybri

*1346* **FINEST VARIETIES MIXED.** The seed for this mi ture has been saved from a very costly collection of bo double and single varieties; some with white variegat foliage; some with golden and bronze foliage, etc. A ve handsome strain which is unsurpassed.
**Packet 25 cts.; 3 packets 60 cts.**

*1344* **APPLE SCENTED.** This favorite with sweet scent leaves can best be grown from seed.
**Packet 20 cts.; 3 packets 50 cts.**

*1345* **LADY WASHINGTON.** Also called Pelargonium Pansy Geranium. Seed saved from the finest sorts.
**Packet 25 cts.; 3 packets 60 cts.**

*1347* **DOUBLE MIXED.** A large percentage will bear doul flowers. All colors. **Packet 25 cts.; 3 packets 60 cts.**

## GLOXINIA

### Half Hardy Perennial

A superb house plant of dwarf habit, producing large, b shaped flowers of brilliant colors and delicate markings.

*1358* **CHOICEST HYBRIDS.** Mixed sorts. **Packet 25 cts**

Gourds, Ornamental

1371 Gypsophila, Paniculata

## GOURDS, Ornamental

**Hardy Annual Climber**

These are of various shapes and colors; some large, some small. All are hard shelled, and will keep for years. Grow 20 to 30 feet high. Excellent for covering porches, walls, outbuildings and waste places. The small Gourds are excellent toys for children, while the larger ones may be used as bowls, dippers, etc.

*1366* **SMALL VARIETIES. Packet 5 cts.; ounce 30 cts.**
*1367* **LARGE VARIETIES. Packet 5 cts.; ounce 35 cts.**

## GYPSOPHILA (Baby's Breath)

**Hardy Annual**

Free flowering plants, the flowers of which are in great demand for cutting or combining with other flowers. Several sowings should be made during the season to keep up a supply.

*1368* **ELEGANS ALBA GRANDIFLORA.** An improved, large flowering pure white form of the popular annual "Baby's Breath." In great demand.
**Packet, 10 cts.; ½ ounce, 20 cts.; ounce, 30 cts.**

*1370* **ROSE.** A pretty rose pink, equally as valuable for cutting as the white, either alone or with other flowers.
**Packet 10 cts.; ½ ounce 25 cts.; ounce 40 cts.**

**Hardy Perennial Gypsophila**

Of the easiest culture, succeeding in open, rather dry places. Used very much in bouquets. Will bloom the first year if seed is sown early.

*1371* **PANICULATA.** Misty white panicles of flowers; fine for bouquets.
**Packet 10 cts.; ¼ ounce 25 cts.; ounce 75 cts.**

## *71B22* GYPSOPHILA PANICULATA ROOTS

**Hardy Perennial**

**30 cts. each.; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen**

1374 Helichrysum, Double Mixed

## HELENIUM (Sneezewort)

**Hardy Perennial**

Of the easiest culture, succeeding in any soil, and giving an enormous crop of flowers in late summer and autumn.

*1360* **AUTUMNALE SUPERBUM.** Broad heads of deep, golden-yellow flowers. Grow 5 to 6 feet high.
**Packet 15 cts.; 1/16 ounce 35 cts.**

## HELICHRYSUM

or Straw Flowers

**Hardy Annual Everlasting**

Highly prized for winter bouquets. Large, full double flowers, of various colors from white and bright yellow to scarlet, shaded and tipped. If you wish to dry the flowers, gather them when partially unfolded and hang with their heads downward in a cool dark place.

*1372* **FIREBALL.** Vivid crimson. **Pkt. 10 cts.; ⅛ oz. 25 cts.**
*1377* **GOLDEN BALL.** Rich yellow. **Pkt. 10 cts.; ⅛ oz. 25 cts.**
*1378* **ROSE QUEEN.** Bright rose. **Pkt. 10 cts.; ⅛ oz. 25 cts.**
*1379* **SNOWBALL.** Pure white. **Pkt. 10 cts.; ⅛ oz. 25 cts.**

## HELICHRYSUM COLLECTION

**See back cover for colored illustration**

*4147* One packet each of above 4 named Helichrysums (value 40 cts.) ..... for **35c**

*1373* **DWARF DOUBLE MIXED. Pkt. 10 cts.; ¼ oz. 30 cts.**
*1374* **TALL DOUBLE MIXED. Packet 10 cts.; ¼ oz. 25 cts.**

1375 Heliotrope, Lemoine's Giant Hybrids

## HELIOTROPE (Cherry Pie)

**Half Hardy Perennial**

The flowers are borne in graceful clusters and are very fragrant; blooms the whole season. It grows quickly and easily from seed, doing best in a rich soil. A splendid bedding or house plant.

*1375* **LEMOINE'S GIANT HYBRIDS.** One of the best strains known among Heliotropes, bearing flowers of immense size and of richest beauty and fragrance. The colors range through all the shades of blue, from violet to indigo. The great trusses or floral heads are sometimes a foot across, and magnificent in appearance. The plants grow about 2 feet high.
**Packet 15 cts.; ⅛ ounce 50 cts.; ¼ ounce 75 cts.**

*1380* **CHOICE MIXED.** Many shades and varieties in a grand mixture. All types and colors.
**Packet 10 cts.; ⅛ ounce 40 cts.; ¼ ounce 60 cts.**

## HIBISCUS (Improved Giant-Flowering Mallow)

**Hardy Perennial**

*1382* **HARDY MARVEL, MIXED COLORS.** Showy, ornamental shrub, growing to a large size and blooming the first year from spring-sown seed. Hardy as an oak and will thrive in any soil. The flowers often measuring 8 to 10 inches across, are gorgeous in colors, and bloom in great profusion from late July to frost. Our mixture of colors range from pure white through all shades of pink and red.
**Packet 10 cts.; ¼ ounce 30 cts.**

## HIBISCUS, HARDY MARVEL ROOTS

**Hardy Perennial**

*71B44* **White**
*71B40* **Pink**
*71B42* **Red**

**Any Color, 40 cts. each; 3 for $1.10; 6 for $2.00; $3.75 per dozen**

1385 Hollyhock, Everblooming



1391 Hollyhock, Allegheny

# HOLLYHOCK

## Hardy Annual

*1385* **EVERBLOOMING, ALL COLORS MIXED.** Seeds planted indoors early will bloom in July, and seeds sown in the open garden in May will produce flowers in August. The floral shapes and size differ; some are 5 inches across. The color range is wonderful. We offer a splendid mixture of all colors. Plants are vigorous growers, and with slight protection will live over the winter and flower again the next year.

**Packet 10 cts.; ¼ ounce 30 cts.; ounce $1.00**

## Hardy Perennial Hollyhock

This old-fashioned flower reaches a height of 6 feet or more, and on account of its stately growth is unexcelled for planting along fences or buildings, or for background effects.

*1391* **ALLEGHENY.** (Mammoth Fringed.) The flowers, which are 3 to 5 inches in diameter, and either double or half double, are finely fringed, cut and curled. The colors vary from palest pink to ruby red, which we offer in mixture.

**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**

1390 Hollyhock, Double Mixed

1396 Hollyhock, Single Mixed

## Double Flowering Hollyhock

We have an exceptionally choice strain noted for their beautiful double flowers and brilliant color.

*1392* **NEWPORT PINK.** The finest pure pink, double flowered Hollyhock ever introduced. A distinct new color.

**Packet 15 cts.; ⅛ ounce 40 cts.; ¼ ounce 75 cts.**

*1386* **DOUBLE WHITE. Packet 10 cts.; ⅛ ounce 30 cts.**
*1387* **DOUBLE YELLOW. Packet 10 cts.; ⅛ ounce 30 cts.**
*1388* **DOUBLE ROSE. Packet 10 cts.; ⅛ ounce 30 cts.**
*1389* **DOUBLE SCARLET. Packet 10 cts.; ⅛ ounce 30 cts.**
*1390* **DOUBLE FINE MIXED, ALL COLORS.** Beautiful.

**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**

## HOLLYHOCK ROOTS Hardy Perennial

**DOUBLE FLOWERING, Separate colors:**
71B56 White, 71B58 Yellow, 71B52 Rose,
71B54 Scarlet, or 71B50 Newport Pink.
**Any color, 30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen**

## Single Flowering Hollyhocks

*1396* **SINGLE MIXED COLORS.** This mixture includes a great variety of colors.

**Packet 10 cts.; ⅛ ounce 25 cts.**

1400 Ice Plant

1404 Ipomoea, Grandiflora

# *1400* ICE PLANT

## Hardy Annual Trailer

A useful pretty little trailer for baskets and particularl suited to dry sunny positions on banks, rockeries, etc., inches or less high. Leaves covered with crystal-like dro which glisten like ice. Flowers white.

**Packet 10 cts.; ¼ ounce 25 cts.**

# IPOMOEA (Moonflower)

## Hardy Annual Climber

Beautiful outdoor climber of luxurious rapid growth f covering verandas and arbors, or for screening unsightly ol jects. Easily grown.

*1403* **SETOSA.** A great climber, making a growth of 30 50 feet. Grape-like leaves nearly a foot wide. Rose colore flowers with a five-pointed star of satiny pink are 3 inch across and freely borne in large clusters.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 40 cts.**

*1404* **GRANDIFLORA.** (The Giant Flowering White Moo flower.) Blossoms pure white, sweet scented and sometim 5 or even 6 inches across. Early to bloom. Buds open in t afternoon and remain open until well into the following da and all day in cloudy weather.

**Packet 10 cts.; ¼ ounce 20 cts.; ½ ounce 30 cts.; ounce 50 ct**

*1405* **HEAVENLY BLUE.** Flowers 4 inches across, of t most exquisite shade of deep azure blue, shading to white the centre. Very pretty, grows about 15 feet high.

**Packet 10 cts.; ¼ ounce 40 cts.**

*1409* **MIXED ALL SORTS.** The above sorts in a mixtu

**Packet 10 cts.; ½ ounce 30 cts.; ounce 50 cts.**

**For Morning Glories, see page 107**

1408 Japanese Hop, Variegated

1411 Japanese Iris, Mixed

# JAPANESE HOP (Humulus)

## Hardy Annual Climber

*1408* **VARIEGATED.** A charming climber, attaining growth of 20 to 25 feet in a few weeks. The leaves are bea tifully marked with white, yellowish green and dark gre

**Packet 10 cts.; ¼ ounce 25 cts.; ounce 75 cts.**

# JAPANESE IRIS (Flowering Flag)

## Hardy Perennial

*1411* **MIXED COLORS.** Seed is saved from a large coll tion of enormous flowers, embracing all colors. **Packet 10 c**

**For roots of different Iris, see pages 128 and 130**

## *1412* JAPANESE KUDZU VINE

(Jack and the Bean Stalk)

**Hardy Perennial Climber**

Blossoms are like Wistaria, but larger in size and with better clusters. The color is of a pleasing shade of purple. The foliage is luxuriant, somewhat like the leaf of a bean. The plant is extremely rapid and dense in growth, making the Japanese Kudzu or "Jack and the Bean Stalk" vine of great value where a quickly produced shade is wanted. From established roots, this vine will attain a length of 40 to 50 feet in one season. It will even flourish where nothing else will grow. It is perctly hardy, increasing in size and beauty year after year. n ornamental and desirable climber.

**Packet 10 cts.; ¼ ounce 25 cts.; ounce 75 cts.**

1413 Jerusalem Cherry

1418 Lantana, Hybrids Mixed

## *1413* JERUSALEM CHERRY

**Half Hardy Perennial**

Forms a dwarf, branching plant, with small, oval-shaped aves, and a great profusion of handsome, bright scarlet bers. Height, 1 foot. Useful for winter decoration.

**Packet 10 cts.; ¼ ounce 30 cts.**

## *1414* JOB'S TEARS

**Hardy Annual Grass**

A pretty, ornamental grass, with broad, corn-like leaves nd hard shining seeds of peculiar appearance, giving the lant its name. The seed is frequently used as an oldashioned remedy for sore throat, goiter and teething babies. hey are strung on a linen thread and worn around the neck s a chain.

**Packet 5 cts.; ounce 25 cts.; ¼ pound 60 cts.**

## LANTANA

**Half Hardy Perennial**

Shrubby plant, 1 to 3 feet high, bearing Verbena-like pink, ellow, orange or white flowers having an agreeable aroatic odor.

*1418* **FINEST HYBRIDS MIXED.**

**Packet 10 cts.; ¼ ounce 25 cts.**

## *1425* LAVENDER

**Hardy Perennial**

Bears long spikes of fragrant, blue flowers which when ried impart an agreeable perfume to clothing.

**Packet 10 cts.; ¼ ounce 30 cts.**



## *1416* KOCHIA (Summer Cypress, Burning Bush)

**Hardy Annual**

Kochia grows 2 to 2½ feet high and resembles a closely clipped ornamental evergreen. The globe-shaped or pyramidal bushes are close and compact, and of a pleasing light green color. In early autumn the whole bush becomes carmine or blood red. Elegant foliage plant.

**Packet 10 cts.; ¼ ounce 20 cts.; ½ ounce 35 cts.; ounce 60 cts.**

*4149*

### Tall Double Stock Flowered Larkspur Collection

**Well known and greatly improved in recent years. Not excelled by any other annual for cutting or garden decoration. Easily and quickly grown.**

(See inside back cover.)

**One packet each of Dark Blue, Light Blue, Carmine and White (value 45c) for**

**35c**

1424 Larkspur, Double Stock Flowered Mixed Colors

## LARKSPUR

**Hardy Annual**

**TALL DOUBLE STOCK FLOWERED.** The flowers are borne in great profusion and last well when cut. One of the best-known garden flowers. The fine spikes of bloom are exceedingly beautiful.

*1419* **DARK BLUE. Packet 10 cts.; ¼ ounce 30 cts.**

*1420* **EXQUISITE.** The color of this charming new Larkspur is a beautiful soft pink; highly prized for cut flower and garden use.

**Packet 15 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.**

*1421* **LUSTROUS CARMINE. Packet 15 cts.; ⅛ ounce 25 cts.**

*1422* **LIGHT BLUE. Packet 10 cts.; ¼ ounce 30 cts.**

*1423* **PURE WHITE. Packet 10 cts.; ¼ ounce 30 cts.**

*1424* **FINEST MIXED COLORS.** Rich mixture of all colors.

**Packet 10 cts.; ¼ ounce 30 cts.; ounce 90 cts.**

**See inside back cover for colored illustrations of Stock Flowered Larkspurs**

1427 Lemon Verbena

1432 Lobelia, Mixed Varieties

## *1427* LEMON VERBENA

**Half Hardy Perennial**

Grown for the exquisite fragrance of its leaves. Easily grown in pots or beds, bears small white flowers.

**Packet 15 cts.**

## LOBELIA

**Hardy Annual**

Lobelias bloom very quickly from seed and the small bushes are fairly sheeted with flowers throughout the season. Very desirable for edgings, borders or pot culture.

*1430* **CRYSTAL PALACE COMPACTA.** Rich, deep blue with dark foliage. The finest for bedding.

**Packet 10 cts.; ⅛ ounce 50 cts.**

*1432* **MIXED VARIETIES.** All the best sorts in a mixture.

**Packet 10 cts.; ⅛ ounce 40 cts.; ¼ ounce 75 cts.**

Lupinus, Mixed

1458 Marvel of Peru, Mixed

## LUPINUS (Lupine)

**Hardy Annual**

Lupinus are extremely decorative in the garden and valuable for cutting. Some varieties are tall while others are dwarf; attractive.

*1444* **ANNUAL MIXED.** 1 to 2 feet high, with upright racemes of variously colored, pea-shaped flowers. Easily grown from seed. Valuable for mixed flower beds and borders. **Packet 10 cts.; ounce 25 cts.**

**Hardy Perennial Lupinus**

*1445* **PERENNIAL MIXED.** Free flowering, succeeding in any good garden soil and blooming in May and June; 3 feet high. Mixed, a great variety of colors.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 40 cts.**

## MARVEL OF PERU (Four O'Clock)

**Hardy Annual**

Well-known, produces large, Convolvulus-like flowers; white, yellow, crimson, striped, etc.

*1457* **TOM THUMB VARIETIES MIXED.** Dwarf, compact, bushy plants with golden variegated foliage and many brilliant colored blooms.

**Packet 10 cts.; ½ ounce 25 cts.; ounce 40 cts.**

*1458* **HYBRID FINE MIXED.** Height of plant about 2 feet, bearing hundreds of flowers from early summer until frost of crimson, violet, yellow and white; many varieties have two or more of these colors spotted, splashed or flaked on the one flower. A good mixture.

**Packet 5 cts.; ounce 25 cts.**

1456 Marigold, Tall African Double Mixed

## MARIGOLD (Tagetes)

**Hardy Annual**

Free-flowering plants of easy culture. The tall African varieties produce large flowers while the French varieties are smaller, some having single and others double flowers.

### DOUBLE TALL AFRICAN (Two and a half feet high)

*1453* **LEMON BALL.** Double, lemon colored.

**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**

*1454* **ORANGE BALL.** Rich golden orange, very showy.

**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**

*1456* **TALL AFRICAN, DOUBLE MIXED.** The best color only selected from the finest double flowers.

**Packet 10 cts.; ¼ ounce 30 cts.; ounce 90 cts.**

### DOUBLE DWARF AFRICAN

*1448* **PRIDE OF THE GARDEN.** Dwarf, compact plant about 15 inches high, bearing immense double, golden yellow quilled flowers.

**Packet 10 cts.; ¼ ounce 30 cts.; ounce 90 cts.**

### DWARF FRENCH MARIGOLDS (One foot high)

French Marigolds are dwarf, with single or double flowers some flowers being striped or spotted. The plants are very profuse bloomers; elegant for borders or massing.

*1450* **GOLDEN BALL.** A remarkably showy, dwarf, double Marigold with brilliant, golden yellow flowers.

**Packet 10 cts.; ¼ ounce 30 cts.; ounce $1.00**

*1451* **LEGION OF HONOR. ("Little Brownie.")** Rich golden yellow single flowers marked with brown. Elegant for bed or borders.

**Packet 10 cts.; ¼ ounce 25 cts.; ounce 75 cts.**

*1452* **DWARF FRENCH, DOUBLE MIXED.** Only the best varieties in this mixture.

**Packet 10 cts.; ¼ ounce 25 cts.; ounce 75 cts.**

# MIGNONETTE

(Reseda)

**Hardy Annual**

No garden is complete without ignonette, the fragrance of hich makes it indispensable for ouquets.

*1465* **RED GOLIATH.** One of ie grandest Mignonettes ever troduced, remarkable for color, ze, fragrance and profusion of loom. The flower spikes are imense, measuring 6 to 8 inches ng, of a fiery-red color.

**acket 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 45 cts.**

*1473* **SWEET SCENTED.** hough small flowered, this va- ety is very sweetly scented.

**acket 5 cts.; ¼ ounce 15 cts.**

*1472* **DEFIANCE.** Nearly ouble the size of the most pop- lar varieties. The flowers are yramidal in shape, reddish olored and highly perfumed. he foliage is rich and slightly umpled.

**acket 10 cts.; ¼ ounce 25 cts.; ounce 75 cts.**

*1474* **FINEST MIXED.** Many arieties in this mixture.

**Packet 5 cts.; ¼ ounce 20 cts.; ounce 60 cts.**

1472 Mignonette, Defiance

# MORNING GLORY

**Hardy Annual Climber**

Rapid growers; invaluable for covering trellises, arbors nd porches. Foliage is very dense and color range of flowers wide.

*1484* **MAMMOTH JAPANESE, MIKADO.** A giant type, with eculiar and handsome colors, shapes and markings. It is a evelopment or evolution from the highest form of Japanese lorning Glory, and represents the acme of beauty thus far ecured in this graceful and favorite flower. The colors are xceedingly rich, and the flowers 4 to 5 inches across.

**Packet 10 cts.; ¼ ounce 30 cts.**

*1483* **ROCHESTER.** Grows 12 to 20 feet; leaves 8 to 10 nches in size. The splendid flowers are 4 to 5 inches across, f a deep violet blue shading to azure and edged with white. Borne in clusters of 3 to 5.

**Packet 10 cts.; ½ ounce 30 cts.; ounce 50 cts.**

**For Ipomoeas, see page 104 of this Book**

*1486* **IMPERIAL JAPANESE SINGLE MIXED.** Our single mixed has a wide and truly remarkable range of markings, unexcelled by any other strain. The shades and colors are various—white, pink, lilac, rose, bronze, garnet, crimson, etc. There is leaf variation that cannot fail to please. Many of their leaves are richly marbled and variegated white and green which add to their beauty. Easily grown, and quick to bloom; sometimes in three weeks.

**Pkt. 10 cts.; ½ oz. 20 cts.; oz. 30 cts.**

1486 Morning Glory, Imperial Japanese, Single Mixed

*1485* **IMPERIAL JAPANESE DOUBLE MIXED.** This is one of the most beautiful of all the famous Japanese Morning Glories and produces a large percentage of beautiful double flowers which are characterized by peculiar colors, shapes and markings; some colorings beyond description. The vine is a rapid grower and in itself makes an ideal ornament for fence, portico or trellis, even before flowering. It produces flowers in remarkable abundance and of enormous size. Another curious feature of this sort is that the leaves vary in form, size and markings. The self or solid colors of the flowers range from snow white to black purple, while there is an endless number of flowers spotted, flaked, marbled, striped, splashed, etc., and margined in combinations that would be thought impossible until seen. The single flowers produced are large and handsome.

**Packet 10 cts.; ¼ ounce 40 cts.; ½ ounce 75 cts.**

1485 Morning Glory, Imperial Japanese, Double Mixed

*72B22* **LIATRIS ROOTS Hardy Perennial**

Popularly known as **Kansas Gay Feather.** Long, narrow spikes of rich purple flowers in July and August. 5 feet high. Beautiful and odd.

**30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen**

# NASTURTIUMS

### Hardy Annual

Nasturtiums prefer a good, well-drained soil; if soil is too rich they are inclined to produce more leaves and less flowers. The seed pods can be gathered while green for pickling. Besides the ordinary-leaved sorts we are offering the Ivy-leaved, and the variegated-leaved varieties. Our mixtures are the finest obtainable anywhere.

## Tall or Climbing Nasturtiums

Well adapted for ornamental purposes. They should have sticks or other supports, or may be trained over rock-work, trellises, fences, arbors, porches, or allowed to ramble over the ground where they will bloom profusely from early summer until frost. Grow 10 to 12 feet high.

### *1501* Tall Variegated or Silver Leaved, Mixed

The plant has a most striking aspect, as each leaf is variegated in a distinctly different degree with silver, yellow, white and green, so that no two are alike. The flowers embrace a fine assortment of colors.

**Packet 10 cts.; ounce 15 cts.; ¼ pound 40 cts.**

### *1535* Tall Climbing, Choice Mixed

A very good mixture of all colors known among Nasturtiums, from creamy white to the darkest red, this mixture cannot fail to please.

**Packet 5 cts.; ounce 15 cts.; ¼ pound 40 cts.**

### *1517* Lobbianum Climbing, Mixed Colors

Flowers of various colors in this mixture produce a grand display.

**Packet 5 cts.; ounce 15 cts.; ¼ pound 50 cts.**

1536 Nasturtium, Hybrids of Madame Gunter

### *1541* Tall Ivy Leaved, Mixed Colors

Beautiful dark green foliage which has a decided resemblance to the foliage of the English Ivy. Flowers are of a distinct form, the petals being narrow and stand apart. A beautiful mixture of many colors.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 50 cts.**

### *1536* Tall Hybrids of Madame Gunter, Mixed

A climbing class. Foliage especially handsome. Vine thrifty and floriferous. The tints include red, salmon, rose yellow, etc., in many combinations. Some flowers are self colored (only one color); some mottled, blotched or margined

**Packet 10 cts; ounce 20 cts.; ¼ pound 60 cts.**

### *1564* Maule's Tall Peerless Mixture

This mixture comprises only the best large flowered Tall or Climbing Nasturtiums, included in which is everything essential to a full range of color, marking and floral shape, as well as Variegated and Ivy-leaved sorts.

**Packet 10 cts.; ounce 30 cts.; 2 ounces 50 cts.; ¼ pound 75 cts.**

1558 Nasturtium, Dwarf or Tom Thumb Mixed

## Dwarf, Bedding or Tom Thumb Nasturtiums

The Dwarf or Tom Thumb Nasturtiums are among our most popular plant They resist heat and drought, grow vigorously and furnish an endless profusion flowers a few weeks after sown until frost. The plants form little mounds 1 foo high and are very suitable for bedding purposes, borders or rockeries.

### *1543* Dwarf Ivy Leaved, Mixed Colors

Beautiful, dark green Ivy-like foliage; the mixture contains a remarkable rang of colors on pretty, compact plants. Distinct and pretty.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 50 cts.**

### *1559* Dwarf Variegated or Silver Leaved Mixed

These grand dwarf Nasturtiums are ideal for bedding, as the foliage which i veined and variegated in silver, green, yellow and cream is exceedingly showy an attractive; the flowers are of various colors.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 45 cts.**

### *1563* Dwarf Giants of California, Mixed

These giant flowering Nasturtiums, of marvelous beauty, are of the Tom Thum or Dwarf type, as to plant, but extra large as to flower. Mixed colors.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 60 cts.**

## Four Popular Named Dwarf Nasturtiums

**Illustrated in colors on inside back cover**

*1544* **GOLDEN KING.** Rich glowing orange yellow.
**Packet 10 cts.; ounce 25 cts.; ¼ pound 75 cts.**

*1545* **KING THEODORE.** Velvety crimson flowers contrasting well with th deep bluish-green foliage.
**Packet 10 cts.; ounce 25 cts.; ¼ pound 75 cts.**

*1546* **PEARL.** Light lemon-yellow shading to a faint primrose.
**Packet 10 cts.; ounce 25 cts.; ¼ pound 75 cts.**

*1547* **VESUVIUS.** Salmon-rose beautifully veined salmon-orange.
**Packet 10 cts.; ounce 25 cts.; ¼ pound 75 cts.**

*4153* **One packet each of the above 4 named Dwarf Nasturtiums (value 40c) ..... for 35c**

### *1558* Dwarf or Tom Thumb, Finest Mixed

We have especially selected all the leading and best flowering varieties use in this mixture to produce the finest assortment of colors.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 45 cts.**

### *1565* Maule's Champion Dwarf Mixture

This grand mixture of all desirable Dwarf or Tom Thumb Nasturtiums wi give a larger variety of colors in proportion than any other Nasturtium mixtur It is made up of all the separate Dwarf named sorts, as well as many super seedlings of exquisite colors and shades, including the best Variegated-leaved an Ivy-leaved varieties. It is the best dwarf mixture possible to produce.

**Packet 10 cts.; ounce 30 cts.; 2 ounces 50 cts.; ¼ pound 75 cts.**



1482 Momordica, Charantia

## MOMORDICA (Balsam Apple and Pear)

**Hardy Annual Climber**

Very curious annual climbers with ornamental foliage; 10 to 12 feet. The large, golden yellow fruit is warted and roughened and is attractive in appearance. It is made into a healing liniment and salve.

*1481* **BALSAMINA.** Apple-shaped; green striped when young.
**Packet 10 cts.; ounce 50 cts.**

*1482* **CHARANTIA.** Pear-shaped; green changing to red.
**Packet 10 cts.; ounce 50 cts.**



1491 Myosotis, Royal Blue

1481 Momordica, Balsamina

## MYOSOTIS (Forget-me-not)

**Hardy Perennial**

This well-known flower is one of the daintiest and most delicate of all favorites. Quite hardy. It succeeds best in rich, moist soils. Excellent for borders and flowers, extremely early. Effective in masses.

*1491* **ROYAL BLUE.** This splendid Forget-me-not assumes an upright shape, reaching a height of 6 to 12 inches. Flowers large and the finest and most effective deep blue variety.
**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**

*1492* **ALPESTRIS.** Dwarf, blue, flowering the first year and forming round, compact bushes covered with flowers.
**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**

## ORNAMENTAL GRASSES

**Hardy Annual**

*1582* **MIXED.** Ornamental grasses serve two purposes. They make the mixed flower bed or border attractive during the summer and they may be gathered when in full bloom and hung up in a dark, dry place with heads downward to dry, and in this dried state are much used in winter bouquets.
**Packet 10 cts.; 3 packets 25 cts.**

1577 Nigella, Miss Jekyll

## NIGELLA

(Love in the Mist)

**Hardy Annual**

A compact, free flowering border or bedding plant, with finely cut feathery foliage and curious seed pods.

*1577* **MISS JEKYLL.** A large, free flowering variety of this well known garden annual. In the finely cut fernlike foliage nestle hundreds of lovely double bright blue flowers, 1½ inches across. Fine for cutting. Height of plant 1 to 2 feet.
**Packet 10 cts.; ¼ ounce 25 cts.**

*1575* **HISPANICA, MIXED.** Blue and white flowers.
**Packet 10 cts.; ¼ ounce 20 cts.**

**LOOK**

**on inside back and back covers for colored illustrations of our most popular, easily grown outdoor flowers. 35c will buy 4 varieties of your favorite flower; 60c will buy 8 varieties or for $1.00 you get all 16 varieties.**

1574 Nicotiana, Sanderae Hybrids

## NICOTIANA (Flowering Tobacco)

**Hardy Annual**

Profuse flowering; highly ornamental and desirable plants with handsome foliage and delightfully sweet scented flowers. Elegant for massing, backgrounds, centre of beds or in shrubbery.

*1572* **AFFINIS.** Large white, sweet-smelling flowers; open morning and evening; 3 feet high. They flower continually from early summer till frost.
**Packet 10 cts.; ¼ ounce 25 cts.**

*1574* **SANDERÆ HYBRIDS.** Large flowers, at least 2 inches across, remains open all day, and the plant is literally ablaze with the brilliant hued flowers of various colors.
**Packet 10 cts.; ¼ ounce 30 cts.**

## Beautify Your Home

**and increase the value of your property**

What a pathetic sight it is to see a would-be home with bare unkempt surroundings when a few packets of flower seeds would provide enough plants to make it attractive.

Grow some annuals for flowers this summer; sow seeds of your favorite perennials for next year's blooms and many years thereafter. Cultural directions are printed on each package of Maule's seeds.

**For bulbs of Oxalis, see page 126 of this Book**

1583 Oxalis, Mixed

1584 Pampas Grass

## OXALIS

**Half Hardy Perennial**

*1583* **MIXED.** Beautiful, bright little plants, with attractive leaves and flowers. Half trailing in habit. Suitable for hanging baskets, vases and edgings. Pink, yellow and white mixed. **Packet 15 cts.; 2 packets 25 cts.**

## *1584* PAMPAS GRASS

**Half Hardy Perennial**

Tall growing and very stately. Beautiful. Native of South America. One of the most effective ornamental grasses. Its silvery white plumes are produced on stems 8 to 10 feet high.
**Packet 10 cts.; 3 packets 25 cts.**

# Maule's Giant Pansies (Heartsease) Hardy Biennial

FOR many years, in fact ever since we have been in business, we have given particular attention to Pansy seeds, until we really think our strains of Pansies are as good as can be found anywhere in the world. Pansies demand good soil, thriving best in a cool, moist but well drained position. Do not plant Pansies in the shade of a tree or building, as this causes straggly plants with very few blooms. Seeds sown in April or May will produce blooming plants the last of June, which will continue flowering until the end of the season. For early spring blooming, sow seeds in August and give plants protection during the winter. We know that the results obtained from our Pansy seeds have been so remarkable that this is the reason the demand for this beautiful and popular flower increases with us so much every year.

## *1600* Maule's Giant Phenomenal

**The wonderful size, colors and veinings of this large Pansy are unsurpassable**

After years of close acquaintance with Phenomenal Pansy, since we introduced it to the American public, we again cordially commend it. It is as unique as it is large and beautiful. Thousands of our friends now know and admire them. The strain originated in France, consisting of the largest, choicest, and most "phenomenal" specimens that could be selected. Phenomenal Pansy exhibits those captivating wine red shades that are so rare among flowers.

**Packet 20 cts.; 1/16 ounce 60 cts.; ⅛ ounce $1.00; ¼ ounce $1.75**

1595 Pansy, Giant Masterpiece

## *1608* Giant Dark Blue

Large well-formed flowers of the darkest blue.
**Packet 10 cts.; ⅛ ounce 50 cts.; ¼ ounce 85 cts.**

## *1619* Giant Ruby King

Ruby shades. **Packet 10 cts.; ⅛ ounce 50 cts.**

## *1623* Giant Golden Yellow

Pure gold. **Packet 10 cts.; ⅛ ounce 50 cts.**

## *1631* Giant Snow Queen

Pure white. **Packet 10 cts.; ⅛ ounce 50 cts.**

## *1602* Giant Trimardeau, Finest Mixed

A beautiful class. Vigorous and compact growers, with flower uniformly of the largest size. Various colors, including all the delicate shades, hues and pencilings.

**Packet 15 cts.; ⅛ ounce 50 cts.; ¼ ounce 85 cts.; ounce $3.25**

## *4155* Maule's Popular 50-Cent Giant Pansy Collection

**The Pansies in this collection have been selected for their size and beauty and embrace a charming range and contrast of colors. All are described on this page.**

*1600* **GIANT PHENOMENAL.**
*1608* **GIANT DARK BLUE.**
*1619* **GIANT RUBY KING.**
*1623* **GIANT GOLDEN YELLOW.**
*1631* **GIANT SNOW QUEEN.**

**One packet each of the above 5 most desirable Pansies (value 60c).....for 50c**

## *1595* Giant Masterpiece

The petals are waved or folded; large and round. Rich dark velvety shades, with usually a light colored edge or border. One of the prettiest of all varieties.

**Packet 15 cts.; 1/16 ounce 60 cts.; ⅛ ounce $1.00**

1614 Maule's Prize Mixed Giant Pansies

## *1614* Maule's Prize Mixed Giant Pansies

**A carefully prepared mixture of all the richest, handsomest and largest Pansies known, in a full range of colors.**

Look for blossoms 2½ to 3½ inches across, of perfect texture, embracing an endless variety of colors. Year by year we watch the production of American and European specialists and secure everything truly meritorious for incorporation into our Prize Mixture.

Pansy seed is a very high priced commodity, and it is next to impossible for the average flower lover to buy all the new sorts on the market. All the types that are really desirable will be found in Maule's Prize Mixture, which is largely grown for exhibition.

**Packet 25 cts.; 1/16 ounce 85 cts.; ⅛ ounce $1.50; ¼ ounce $2.75; ½ ounce $5.25; ounce $10.00**

## *1598* Giant Madame Perret

Comprised of all shades of wine red, from the light red, white edged bright red to the deep purple of splendid magnificence. Every blossom exhibits the soft wine-red color, in varying degree, either faint or intense.

**Packet 15 cts.; 1/16 ounce 35 cts.; ⅛ ounce 60 cts.; ¼ ounce $1.00**

## *1603* Giant President McKinley

Almost black, with yellow margin; 2½ to 3 inches in diameter. The blotches are really dark reddish brown, exceedingly rich.

**Packet 15 cts.; 1/16 ounce 60 cts.; ⅛ ounce $1.00**

## *1606* Bugnot's Giant Superb Blotched

The predominating colors to be found in these Giant Pansies are shades of red, bronze, reddish cardinal, and reddish-brown. Petals handsomely blotched and bordered with light colors.

**Packet 15 cts.; 1/16 ounce 45 cts.; ⅛ ounce 75 cts.**

## *1612* Giant King of the Blacks

Glossy black. **Packet 10 cts.; ⅛ ounce 50 cts.**

1598 Pansy, Giant Madame Perret

# MAULE'S BEDDING PANSIES

Valuable for bedding or borders where a mass of color is wanted. Flowers are not of the largest type, but bloom profusely throughout the season.

## *1615* Orchid-Flowered

The ground color is mostly light, while the petals are marked with large brown or golden blotches. The colorings include shades of pink, rose, orange, lilac and chamois.

**Packet 15 cts.; 1/16 ounce 45 cts.; ⅛ ounce 75 cts.**

## *1633* Choice Mixed

A mixture of all varieties, giving a remarkably fine display of colors. The flowers are not of the largest type, but plants are of strong, sturdy growth and profuse bloomers.

**Packet 10 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.**

## *1634* Extra Fine Mixed

All the costly European varieties of the finest type are included in this grand mixture. The size of the flower has been somewhat sacrificed to obtain the most gorgeous colors.

**Packet 10 cts.; ⅛ ounce 40 cts.; ¼ ounce 75 cts.; ounce $2.75**

1630 Pansy, Early Flowering Hardy

## *1630* Early Flowering Hardy, Mixed Colors

These Pansies are of great value, owing to the extreme hardiness of the plants and their extraordinarily early blooming time, producing their flowers 4 to 6 weeks earlier than any other variety of Pansies. Full grown plants will winter over in the open ground with but a slight protection of leaves, litter, etc., in very cold latitudes, and will begin flowering, so-to-say, under the snow in February and March, when other Pansies are only forming buds. These delicately perfumed Pansies are of good size and will continue to bloom in great profusion until late summer.

**Packet 15 cts.; 1/16 ounce 45 cts.; ⅛ ounce 75 cts.**

**See opposite page for other varieties of Pansies which we can supply.**

# Maule's Showy Petunias



1635 Rosy Morn

1637 Rose of Heaven

1647 Howard's Star

### Hardy Annual

No annual flower is more widely used than the Petunia. It begins to bloom early, and lasts the whole season, until killed by frost. Petunias succeed best in rich soil and a sunny location. While most varieties are of the trailing habit, some are quite erect.

*1646* **BELLE ETOILE.** Beautiful, large-flowered, striped and blotched Petunias which are exceptionally fine for bedding, baskets, vases, etc.
**Packet 10 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.**

*1642* **GENERAL DODDS.** Velvety dark red, a scarce color among Petunias. Compact bushes.
**Packet 10 cts.; ⅛ ounce 50 cts.; ¼ ounce 85 cts.**

*1649* **SINGLE LARGE FLOWERED.** Very large flowers 3 to 4 inches across, blotched and veined in the most grotesque and beautiful combinations, but not fringed. Mixed colors.
**Packet 25 cts.; 2 packets 45 cts.; 5 packets $1.00**

*1648* **BEST HYBRIDS, MIXED PETUNIAS.** A fine mixture of the best single Petunias, including striped, blotched and mottled sorts.
**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.; ounce $1.25**

## Dwarf Bedding Petunias

Dwarf, compact plants with medium size flowers abundantly produced from early summer until fall. Splendid for porch boxes, pots or beds erect growing.

*1635* **ROSY MORN.** One of the most popular Petunias and especially fine. Soft carmine pink with white throat, a handsome coloring.
**Packet 10 cts.; 1/16 ounce 35 cts.; ⅛ ounce 60 cts.; ¼ ounce $1.00**

*1637* **ROSE OF HEAVEN.** Rich and brilliant deep rose flowers. Of compact, erect, very dwarf habit and free flowering. Adapted for all purposes.
**Packet 10 cts.; 1/16 ounce 30 cts.; ⅛ ounce 50 cts.; ¼ ounce 85 cts.**

*1639* **VIOLACEA.** Flowers are of a beautiful steel blue or deep violet with no trace of magenta.
**Packet 10 cts.; 1/16 ounce 30 cts.; ⅛ ounce 50 cts.; ¼ ounce 85 cts.**

*1640* **DWARF BEDDING MIXED.** A beautiful mixture of all dwarf erect growing Petunias. A wonderful array of colors. Very fine in masses.
**Packet 10 cts.; ⅛ ounce 45 cts.; ¼ ounce 75 cts.**

### *4157* BEDDING PETUNIA COLLECTION

**One packet each of Burpee's Blue, Rosy Morn, Balcony White and Howard's Star, as illustrated in colors on back cover (value 65c) for..... 35c**

*1647* **HOWARD'S STAR.** Flowers are 2 to 2½ inches in diameter, of fine texture, with more or less veining. Ground color a crimson maroon. In the center of many flowers is a five-rayed star of light blush pink or white, while some are beautifully striped or blotched. Height of plant 1½ to 2 feet.
**Packet 10 cts.; ⅛ ounce 50 cts.; ¼ ounce 85 cts.**

*1663* **BURPEE'S BLUE.** This is an outstanding new Petunia altogether different from other so-called "Blues" introduced heretofore. Burpee's Blue is a rich, clear ultramarine-blue free from any purplish cast or pink tint. The flowers measure 2½ to 3½ inches in diameter. They are borne with the greatest freedom on strong and vigorous plants.
Burpee's New Blue Petunia is a wonderful variety for bedding or for growing in window or porch boxes; a unique color, greatly admired.
**Packet 25 cts.; 1/16 ounce $1.00; ⅛ ounce $1.75**

## Balcony Petunias

The flowers of this type average 3 inches across and are a sheet of bloom from early summer until hard frost. Being of semi-trailing habit, Balcony Petunias are especially adapted for vases, window boxes and no less desirable for bedding purposes.

*1641* **BALCONY BLUE. Packet 20 cts.; 1/16 oz. 60 cts.; ⅛ oz. $1.00.**
*1643* **BALCONY CRIMSON. Packet 20 cts.; 1/16 oz. 60 cts.; ⅛ oz. $1.00.**
*1644* **BALCONY ROSE. Packet 20 cts.; 1/16 oz. 60 cts.; ⅛ oz. $1.00.**
*1659* **BALCONY WHITE. Packet 20 cts.; 1/16 oz. 60 cts.; ⅛ oz. $1.00.**
*1660* **BALCONY, MIXED COLORS.** The above colors in a mixture.
**Packet 20 cts.; 1/16 ounce 50 cts.; ⅛ ounce 85 cts.; ¼ ounce $1.50**

### Balcony Petunia Collection

**A mass of bloom throughout the summer until frost**

*4159* **One packet each of the 4 separate colors of Balcony Petunias (value 80c) .....for 65c**

1644 Balcony Rose

1659 Balcony White

*638* **SELECTED RUFFLED GIANTS.** Considered by many the handsomest Petunia in the world, not only on account of great size, but because of its rich colors and markings d its fringed or notched petals. The blooms are exquisitely fled on the edges. Some flowers are 5 inches across. The ts are rich and varied, curiously veined and penciled.

**Packet 25 cts.; 2 packets 45 cts.; 5 packets $1.00**

*645* **SINGLE FRINGED VARIETIES.** The flowers are ormous, with ruffled or fringed edges. The colors are many d exceedingly rich.

**Packet 25 cts.; 2 packets 45 cts.; 5 packets $1.00**

*636* **DOUBLE EXTRA LARGE FLOWERING, MIXED.** uble Extra Large Flowering Petunias are without doubt finest ever offered to the public. For years we have made a cialty of this strain, constantly improving it by selection. e seed which we save from our double flowering Petunias duces a high percentage of double flowers, the remainder ng choice, large single flowers of extra fine quality. The aker seedlings should be carefully saved as they usually duce the finest double flowers.

**Packet 30 cts.; 2 packets 50 cts.; 5 packets $1.00**

1590 Pentstemon, Mixed

1661 Physostegia, Virginica

## PENTSTEMON (Beard Tongue)

**Hardy Perennial**

*1590* **MIXED.** It grows 2 to 3 feet high, producing long spikes of white, pink, scarlet, blue, etc., spotted and marked flowers. If sown early they will bloom the first year. The graceful spikes are bedecked with flowers from July till frost.

**Packet 10 cts.; ⅛ ounce 30 cts.**

## PHYSOSTEGIA (False Dragon Head)

**Hardy Perennial**

*1661* **VIRGINICA.** Forms dense bushes 3 to 4 feet high, bearing during the summer months spikes of tubular, delicate pink flowers, somewhat resembling a gigantic Heather.

**Packet 10 cts.; ⅛ ounce 40 cts.; ¼ ounce 75 cts.**

1662 Platycodon, Mariesi

1709 Primula, Chinensis, Mixed

## PLATYCODON (Japanese Bell Flower)

**Hardy Perennial**

A low growing bushy plant, 1 to 2 feet high, producing very showy flowers from July until frost. Easily raised from seed.

*1662* **MARIESI.** Large, open, bell-shaped flowers of a rich violet blue. Very handsome.

**Packet 10 cts.; ⅛ ounce 50 cts.**

## PLATYCODON ROOTS Hardy Perennial

*73B68* **MARIESI BLUE** *73B70* **MARIESI WHITE**

**25 cts. each; 2 for 45 cts.; 6 for $1.20; $2.25 per dozen**

## PRIMULA (Primrose)

**Half Hardy Perennial**

*1699* **OBCONICA, FINEST MIXED, ALL COLORS.** Of the easiest culture in window or conservatory; flowering profusely and continually with little care.

**Packet 20 cts.; 3 packets 50 cts.; 7 packets $1.00**

**PRIMULA CHINENSIS.** Also called Chinese Primrose. Profuse bloomers and among the finest and most popular of the winter and spring flowering window or greenhouse plants, doing well in cool rooms. Plants are sturdy and robust; the flowers cut and fringed.

*1705* **BLUE.** A violet blue. **Packet 25 cts.; 3 pkts. 60 cts.**
*1706* **CRIMSON.** A rich color. **Packet 25 cts.; 3 pkts. 60 cts.**
*1707* **ROSE.** A delicate shade. **Packet 25 cts.; 3 pkts. 60 cts.**
*1708* **WHITE.** Pure white. **Packet 25 cts.; 3 pkts. 60 cts.**
*1709* **FINEST MIXED.** All shades and colors, finely fringed.

**Packet 20 cts.; 3 packets 50 cts.; 7 packets $1.00**

1696 Portulaca, Single Large Flowered Mixed

## PORTULACA (Rose Moss or Sun Plant)

### Hardy Annual

A favorite for edgings, rock-work, etc. Will grow and bloom profusely in a dry, hot, sunny location, where almost any other plant would die. Blooms profusely from early summer until autumn. Only 6 inches high.

*1696* **SINGLE LARGE FLOWERED MIXED, ALL COLORS.** Many striped and variegated sorts will be found in this mixture.

**Packet 5 cts.; ¼ ounce 25 cts.; ounce 75 cts.**

*1697* **DOUBLE LARGE FLOWERING MIXED.** Brilliant shades, including white, yellow, salmon and carmine. Seed saved from perfect double flowers will, at times, produce some singles.

**Packet 10 cts.; ⅛ ounce 50 cts.; ¼ ounce 85 cts.**

1654 Phlox Drummondii, Large Flowering, Finest Mixed

## PHLOX DRUMMONDII (Texan Pride)

### Hardy Annual

The annual and perennial Phloxes are not rivaled among garden flowers in brilliancy of bloom. They are strong growing, healthy plants, with pretty foliage, and belong in every garden, being one of the most brilliant and at the same time one of the easiest and most satisfactory plants which can be readily grown from seed. The fine blooms, produced in large trusses, furnish a grand display in the garden and are very effective for table decoration.

**MAULE'S LARGE FLOWERING.** The seeds for this large flowering strain of ours are saved from only the largest individual flowers and heads of the finest Phlox grown. They come into bloom quickly from the seed, and flower a long period, until cut down by frost.

*1650* **ROSE. Packet 10 cts.; ⅛ ounce 30 cts.**
*1651* **SCARLET. Packet 10 cts.; ⅛ ounce 30 cts.**
*1652* **WHITE. Packet 10 cts.; ⅛ ounce 30 cts.**
*1654* **FINEST MIXED, LARGE FLOWERING.** All colors.

**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 45 cts.; ounce $1.50**

*1655* **GRANDIFLORA MIXED PHLOX.** Large flowered v rieties in a superb mixture of the choicest shades and colo which include pure white, deep and showy red, rose wi white eye and other shades, excellent for vases, pot plan hanging baskets, etc., or for bedding.

**Packet 10 cts.; ⅛ ounce 20 cts.; ¼ ounce 35 cts.; ounce $1.**

1658 Phlox, Star of Quedlinburg

*1658* **STAR OF QUEDLI BURG, FINEST MIXED.** Lar flowers, with curiously point and toothed blossoms, maki them appear to have a star-li form, the effect of which is r markable. The flowers are various shades, embracing the colors to be found in t other varieties of Phlox.

**Packet 10 cts.; ⅛ ounce 30 ct ¼ ounce 50 cts.; ounce $1.7**

### Hardy Perennial Phlox

Of late years beds and clum of these beautiful Phloxes a becoming more popular ever where. Plants grow 2 to 3 fe high and bear flowers of ma colors. One of the most sat factory perennials.

**For Hardy Phlox Roots, see page 128**

*1653* **HARDY PERENNIAL PHLOX, ALL COLORS MIXE**

This seed is saved from a very fine collection of all colo and gives excellent results. They are perfectly hardy, ne no protection, and will flourish in any soil.

**Packet 25 cts.; ⅛ ounce 60 cts.; ¼ ounce $1.00**

# POPPY

**Hardy Annual**

Showy and easily cultivated. A favorite everywhere. Flowers of various sizes, shapes and colors, both single and double. Always conspicuous and brilliant.

*1673* **DOUBLE CARNATION, MIXED COLORS.** Produces large Carnation-like flowers, most excellent for massing or borders, flowers being very double. One of the most beautiful varieties, and we offer a very fine range of colors in our mixture. **Packet 10 cts.; ½ ounce 20 cts.; ounce 35 cts.**

*1680* **KING EDWARD.** Scarlet shaded crimson red, each petal marked with a large black blotch for half its length from the base. **Packet 5 cts.; ¼ ounce 25 cts.**

*1682* **TULIP POPPY.** Beautiful flowers of vivid scarlet, which are formed like a Tulip.
**Packet 10 cts.; ¼ ounce 25 cts.**

*1674* **AMERICAN FLAG.** Flowers very large and double, snow white bordered with scarlet.
**Packet 5 cts.; ½ ounce 25 cts.**

*1676* **DOUBLE DWARF PEONY FLOWERED.** Flowers of enormous size, perfectly double, resembling a Peony, and ranging through many shades. **Packet 5 cts.; ½ ounce 25 cts.**

**FEATHER BALL POPPY.** 2 feet tall. It is a free bloomer. The flowers when fully expanded look like a ball of feathers. Flowers are large, globular and fringed.

*1685* **WHITE. Packet 10 cts.; ¼ ounce 25 cts.**
*1686* **PINK. Packet 10 cts.; ¼ ounce 25 cts.**
*1687* **SCARLET. Packet 10 cts.; ¼ ounce 25 cts.**
*1688* **MIXED COLORS. Packet 10 cts.; ½ ounce 25 cts.**

*1672* **IMPROVED SHIRLEY, MIXED COLORS.** An unusually choice strain embracing a wide range of colors, such as salmon, scarlet, blush, carmine, white, white with rose edge, white splashed crimson and some are striped, edged, dotted, etc. Tissue-paper-like appearance.
**Packet 10 cts.; ½ ounce 35 cts.; ounce 60 cts.**

1679 Poppy, Admiral

*1675* **AMERICAN LEGION.** This new Shirley Poppy is a dazzling orange scarlet with yellow anthers. Plants are of very erect growth and the flowers very large.
**Packet 10 cts.; ¼ ounce 25 cts.**

*1670* **WILD ROSE PINK SHIRLEY.** A bright but soft wild rose pink, a color which appeals to everyone.
**Packet 10 cts.; ¼ ounce 30 cts.**

*1690* **FLANDERS.** Vivid scarlet red—the well-known Poppy of Flanders field. Particularly showy when grown in masses.
**Packet 10 cts.; ¼ ounce 25 cts.**

*1679* **ADMIRAL.** Large, round flowers of glistening white, with a broad band of bright brilliant scarlet around the top of each petal.
**Packet 10 cts.; ¼ ounce 25 cts.**

## Hardy Perennial Poppy

Oriental Poppies are one of the showiest flowers in the garden in early spring. Flower stems grow 2½ feet high. Foliage disappears in July and August.

*1664* **ORIENTAL PERENNIAL HYBRIDS, MIXED.** Flowers of gorgeous brilliancy. Colors range from soft flesh and rose to brilliant dazzling scarlet.
**Pkt. 10 cts.; ⅛ oz. 30 cts.**

*1665* **HARDY PERENNIAL.** A mixture of Oriental and Iceland Poppies.
**Pkt. 10 cts.; ⅛ oz. 30 cts.**

### Iceland Poppies

Of graceful habit, with bright green foliage formed in tufts, from which arise slender stems about a foot high bearing brilliant flowers the entire season if seed pods are not allowed to form.

*1667* **NEW HYBRIDS ICELAND, MIXED COLORS.** Containing all the new colors from sulphur yellow through the many shades of orange to salmon rose.
**Pkt. 10 cts.; ⅛ oz. 30 cts. ¼ ounce 50 cts.**

1664 Poppy, Oriental Perennial Hybrids

1711 Pyrethrum, Roseum, Single

1710 Purple Feather Grass

# PYRETHRUM

**Hardy Perennial**

Handsome, herbaceous garden plants about 2 feet high, bearing Daisy-like or Aster-like flowers, 3 or 4 inches across, ranging in colors from light pink to deep red with yellow centres. Blooms in May and June and again in the fall; one of the best cut flowers.

*1711* **ROSEUM, SINGLE MIXED. Pkt. 10 cts.; ⅛ oz. 40 cts.**
*1712* **ROSEUM, DOUBLE MIXED. Pkt. 15 cts.; 1/16 oz. 75 cts.**

## PYRETHRUM ROOTS Hardy Perennial

*73B82* **ROSEUM, SINGLE AND DOUBLE, MIXED COLORS.**

**30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen**

# *1710* PURPLE FEATHER GRASS

**Tender Perennial**

A very beautiful and popular ornamental house or border plant of easy culture. As useful for hall or table adornment as a palm, and having the advantage of rapid growth. The graceful, narrow, recurving leaves are over-topped by elegant feathery plumes a foot long. Heads borne from July until frost, and the whole plant is eventually veiled in a purple cloud.

**Packet 10 cts.; ⅛ ounce 35 cts.**

1714 Ricinus, Zanzibarensis Mixed

**SOW MAULE'S WILD FLOWER GARDEN MIXTURE in out-of-the-way places, back lots, fence corners, etc. Scatter the seed thinly on the surface and rake in.**

(See page 124 for description and prices.)

# RICINUS (Castor Oil Bean)

**Hardy Annual**

A stately, strong-growing and highly ornamental tree-like annual plant; 6 to 14 feet high. Very effective as a foliage plant. Highly desirable for centres of beds or for backgrounds. By planting Ricinus beans on the borders of gardens, moles may be kept away, as they will leave as soon as they get a scent of the plant.

*1713* **RED SPIRE.** Rich bronzy-green leaves with prominent red ribs and veins. Plant grows 6 feet high and produces numerous flower spikes or seed-pods of a brilliant rosy-crimson, most effective and ornamental.

**Packet 10 cts.; ounce 40 cts.; ¼ pound $1.00.**

*1714* **ZANZIBARENSIS.** The tallest growing Ricinus, 10 to 14 feet high, variously colored leaves, sometimes 2 feet across.

**Packet 10 cts.; ounce 25 cts.; ¼ pound 75 cts.**

*1715* **MIXED.** All the best plain and fancy varieties in a grand mixture.

**Packet 10 cts.; ounce 20 cts.; ¼ pound 60 cts.**

1722 Salvia, Drooping Spikes

# SALVIA (Scarlet Sage)

**Hardy Annual**

Salvias are favorite bedding plants bearing long spikes o flowers profusely during the whole summer until frost; als grown as pot plants during the winter.

*1722* **DROOPING SPIKES.** The very best Salvia obtainable The flowers are produced so abundantly as to bend th branches and give them a leaning habit, hence the name o Drooping Spikes. It is a magnificent bloomer; desirable fo lawn or garden whether planted in solid beds or in borders

**Packet 15 cts.; ⅛ ounce 60 cts.; ¼ ounce $1.00**

*1724* **AMERICA OR GLOBE OF FIRE.** The earliest, frees and most continuous blooming of all Salvias, being of uni form growth not exceeding 15 inches in height, with spike of brilliant scarlet flowers borne well above the foliage. Par ticularly suited for pots, beds or borders.

**Packet 20 cts.; ⅛ ounce 75 cts.; ¼ ounce $1.25**

1723 Salvia, Bonfire

1738 Saponaria, Vaccaria

*1723* **BONFIRE.** One of the finest for bedding. Compact oval bushes, 2 feet in height, with long spikes of scarle flowers standing clear above the foliage, which completel cover the plant. A very popular variety for beds and border where a dwarfer red variety than Drooping Spikes is re quired. Very extensively grown.

**Packet 10 cts.; ⅛ ounce 50 cts.; ¼ ounce 90 cts.**

*1727* **FARINACEA.** (The Silver Sage.) Tall silver laven der or blue spikes rise in great numbers above the foliage A handsome bedding plant for groups, borders or massing With a slight covering during the winter, this variety i hardy in many localities, but it is best to treat it as a annual.

**Packet 10 cts.; ⅛ ounce 50 cts.; ¼ ounce 85 cts.**

*1733* **MIXED, ALL SORTS.** We have received so many re quests for Salvia seeds mixed, that we are offering a mixtur of the scarlet, carmine, salmon and purple.

**Packet 15 cts.; ⅛ ounce 50 cts.**

# SAPONARIA

**Hardy Annual**

*1738* **VACCARIA.** Satiny pink flowers somewhat like a enlarged Gypsophila, valuable for cutting and largely use for mixing with other flowers. Grows about two feet high Make several sowings for a succession of bloom. Easil grown; free flowering.

**Packet 10 cts.; ½ ounce 20 cts.; ounce 30 cts.**

1721 Salpiglossis, Emperor

1742 Scabiosa, Mixed Double

## SALPIGLOSSIS (Painted Tongue)

**Hardy Annual**

Height, 24 to 30 inches high, bearing many Gloxinia-like flowers 2 to 2½ inches across, with odd and beautiful velvety markings; the colors red, blue, yellow, pink, etc., in various shades are pencilled and veined with golden yellow or other colors. Easily grown, flower profusely and are fine for cutting as well as being showy in beds or borders.

*1720* **HYBRIDS MIXED.** Exquisitely veined and marbled.
**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**

*1721* **EMPEROR MIXED.** Improved large flowering strain of the richest colors. Very showy.
**Packet 10 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.**

## SCABIOSA

(Mourning Bride, Sweet Scabious, Pincushion Flower, etc.)

**Hardy Annual**

No garden is complete without Scabiosas, especially where cut flowers are wanted. They begin blooming in July and continue until frost.

*1742* **MIXED, LARGE FLOWERED DOUBLE.** Flowers borne on long, erect stems, and double clear to the centre in colors of nearly white to purple maroon.
**Packet 10 cts.; ¼ ounce 25 cts.; ounce 60 cts.**

**Lend this Catalog to your neighbor**

1759 Stokesia, Cyanea Mixed

## STOKESIA

(Cornflower Aster)

**Hardy Perennial**

*1759* **CYANEA MIXED COLORS.** 2 feet high. Beautiful Corn-flower-like blossoms, valuable for cutting. Lavender-blue and white, mixed.
**Packet 15 cts.; ⅛ ounce 35 cts.; ¼ ounce 60 cts.**

1752 Stocks, Cut and Come Again, Finest Mixed

**TRY a few flowers you have never grown before. There may be some flowers listed in this book that you don't know, but are worthy of a place in your garden.**

1762 Sunflower, Double Chrysanthemum-Flowered

## SUNFLOWER (Helianthus)

**Hardy Annual**

Of easy culture, and the newer sorts are among the most ornamental and effective of all garden annuals. The single flowering sorts are indispensable for cutting. Bloom early and continue until frost.

*1762* **CHRYSANTHEMUM - FLOWERED.** Fine, perfectly double golden flowers, resembling Japanese Chrysanthemums; 6 to 10 inches in diameter. Plants grow 5 to 6 feet high.
**Packet 10 cts.; ½ ounce 30 cts.; ounce 50 cts.**

*1763* **GLOBE OF GOLD.** (Dahlia Sunflower, Golden Quilled Sunflower.) A double Sunflower, attaining a height of but little over 3 feet. Each branch carries a beautiful globe-shaped flower of richest golden yellow.
**Packet 10 cts.; ounce 30 cts.; 2 ounces 50 cts.**

*1764* **MINIATURE MIXED.** (Cut and Come Again.) Finely formed single flowers of graceful appearance, many with petals beautifully twisted like those of a Cactus Dahlia. Of many colors, pale yellow, golden yellow and creamy white predominating.
**Packet 10 cts.; ¼ ounce 25 cts.**

*1766* **RED.** Some of the flowers are of a chestnut red color, others are red, tipped yellow, while others are yellow washed with red. Grows to a height of 6 feet.
**Packet 10 cts.; ounce 50 cts.**

*1767* **PURPUREUS HYBRIDS.** In this class of Sunflowers the original yellow has almost completely disappeared. Shades of the most delicate pink to the deepest purple are predominant in this mixture. 3 to 4 feet high.
**Packet 10 cts.; ¼ ounce 30 cts.**

## *1744* SMILAX

**Half Hardy Perennial Climber**

A popular indoor climber. Leaves are a deep, glossy green. Habit of growth extremely graceful. Easily grown from seed.
**Packet 10 cts.; ¼ ounce 25 cts.**

## STOCKS (Gilliflower)

**Hardy Annual**

Nothing can excel Stocks for profusion of bloom, beauty and fragrance. The flowers are large and double, and excellent for bedding or pot culture. The plants bloom freely and continuously till frost.

**CUT AND COME AGAIN, PERPETUAL BRANCHING.** Produces numerous side branches, each bearing delightfully fragrant double flowers. Seed started indoors in March or April should produce plants that will begin to bloom in mid-summer and continue until frost.

*1746* **BRILLIANT.** Beautiful spikes of blood red flowers.
**Packet 10 cts.; ⅛ ounce 60 cts.; ¼ ounce $1.00**

*1747* **CREOLE.** Creamy yellow flowers freely produced.
**Packet 10 cts.; ⅛ ounce 60 cts.; ¼ ounce $1.00**

*1748* **LA FRANCE.** Enormous heads of beautiful rose.
**Packet 10 cts.; ⅛ ounce 60 cts.; ¼ ounce $1.00**

*1750* **PRINCESS ALICE.** Large spikes of beautiful pure white flowers.
**Packet 10 cts.; ⅛ ounce 60 cts.; ¼ ounce $1.00**

*1751* **SAPPHIRE.** Dark blue. Very fine and distinct color.
**Packet 10 cts.; ⅛ ounce 60 cts.; ¼ ounce $1.00**

*1752* **FINEST MIXED, CUT AND COME AGAIN.** The above colors and many other soft and distinct shades.
**Packet 10 cts.; ⅛ ounce 50 cts.; ¼ ounce 85 cts.**

### Cut and Come Again Stocks Collection

**Sweet scented flowers produced profusely**

*4165* **One packet each of above 5 separate colors (value 50c) for ..... 40c**

# Summer Flowering Giant Spencer Sweet Peas

Under the best conditions, Spencer Sweet Peas grow 6 to 10 feet high, and for full development should stand at least 6 inches apart. The flowers measure 2 to 2½ inches across, are beautifully waved and are generally borne in threes or fours on long, strong stems.

## 3 of the Greatest New Spencer Sweet Peas for 1927

Three new varieties, each as fascinatingly attractive as it is novel. Two distinctively new colors, and a brilliantly bright dark blue.

Large, well-formed blossoms and long stems are special features of all these handsome, vigorous growing specialties. They are sure to create a sensation among Sweet Pea lovers.




### *1855* DELIGHTFUL

**A rich terra cotta cerise suffused orange or scarlet red. A color never before produced—the most appealing, in its glowing beauty, of all the richer toned varieties; bright and shining even on dull days, intensified in hot sunshine and startlingly brilliant under artificial light.**

**Packet (15 seeds) 25 cts.**

### *1856* GLADNESS

**A soft coral pink, intensified by a suffusion of a somewhat deeper shade toward the base of the standard and wings. A distinct new sweet-pea color, which might be called a geranium pink—the softest and daintiest of all pinks—with its exquisite delicacy still further enhanced by a lemon keel.**

**Packet (15 seeds) 25 cts.**

### *1857* ROYAL BLUE

**A true Royal Blue, but full of life and brilliancy instead of dull and uninspiriting, as is the case with existing varieties; undoubtedly the brightest of all sweet pea dark blues. A flower of great substance and enchanting beauty, extremely prolific in fours.**

**Packet (15 seeds) 25 cts.**

### Collection of the 3 Greatest New Spencer Sweet Peas

*4179* By special arrangement with the originators, we are able to offer the Maule customers these great novelties (value 75c) at the reduced price of all 3 packets .....for **50c**

### *4173* Maule's 4 Extra Choice Giant Spencer Sweet Peas (value 40c) for 35 cts.

Illustrated in Colors on Inside Back Cover

*1923* **HAWLMARK PINK.** The standard is rich rose-pink flushed salmon; wings are bright rose pink. Free flowering.
**Packet 10 cts.; ½ ounce 20 cts.; ounce 30 cts.; ¼ pound 75 cts.**

*1880* **KING WHITE.** The best and largest pure white. Plants are strong growing and freely produce four flowered stems.
**Packet 10 cts.; ½ ounce 20 cts.; ounce 30 cts.; ¼ pound 75 cts.**

*1905* **ROYAL SCOT.** A deep cerise closely approaching a true scarlet. The finest of its color yet introduced.
**Packet 10 cts.; ½ ounce 20 cts.; ounce 30 cts.; ¼ pound 75 cts.**

*1914* **WEDGEWOOD.** The color is a most beautiful unique shade of Wedgewood blue, without any harsh purple shading.
**Packet 10 cts.; ½ ounce 25 cts.; ounce 35 cts.; ¼ pound 90 cts.**

# 12 of the Best Giant Spencer Sweet Peas

1853 Sweet Pea, Constance Hinton Spencer

**Sow Sweet Pea Seeds as Early in the Spring as the Soil Can Be Worked**

*1850* **CHERUB.** A deep rich cream, edged bright rose. One of the most attractive of the picoteed varieties. Very large.
**Packet 10 cts.; ½ ounce 25 cts.; ounce 35 cts.; ¼ pound $1.00**

*1853* **CONSTANCE HINTON.** The best black-seeded white-flowered Spencer; flowers large and of true form.
**Packet 10 cts.; ½ ounce 20 cts.; ounce 30 cts.; ¼ pound 75 cts.**

*1858* **CRIMSON KING.** Surpasses all other crimson sweet peas. It is a flower of mammoth size and artistic proportions. A rich true crimson.
**Packet 10 cts.; ½ ounce 30 cts.; ounce 45 cts.; ¼ pound $1.35**

*1864* **HAWLMARK CERISE.** Glowing rose-cerise on cream ground. Large flowers on long stems are freely borne in fours.
**Packet 10 cts.; ½ ounce 30 cts.; ounce 45 cts.; ¼ pound $1.25**

*1860* **HAWLMARK SALMON-PINK.** A rich deep pink, attractively tinted with salmon and orange. The plants produce flowers of the largest size.
**Packet 10 cts.; ½ ounce 25 cts.; ounce 35 cts.; ¼ pound 90 cts.**

*1884* **MATCHLESS.** A new cream variety with frilled and waved standard and wings. The blooms are of extra large size and are borne freely.
**Packet 10 cts.; ½ ounce 25 cts.; ounce 35 cts.; ¼ pound 90 cts.**

*1903* **ORCHID, IMPROVED.** Beautiful deep lavender throughout, slightly suffused pink on both standard and wings. Large and wavy.
**Packet 10 cts.; ½ ounce 20 cts.; ounce 30 cts.; ¼ pound 75 cts.**

*1921* **PICTURE.** The largest flowered of all, a blended cream and pink shades having a deeper flush on the wings.
**Packet 10 cts.; ½ ounce 20 cts.; ounce 30 cts.; ¼ pound 75 cts.**

*1868* **RAVENSWING.** Intense blackish-maroon—the darkest of all Sweet Peas. Large, perfectly waved flowers.
**Packet 10 cts.; ½ ounce 20 cts.; ounce 30 cts.; ¼ pound 75 cts.**

*1907* **SENSATION.** A really worthwhile addition to the orange-scarlet class. The flowers are of immense size and excellent form. They are borne freely. The color is a dazzling scarlet of a startling richness.
**Packet 10 cts.; ½ ounce 25 cts.; ounce 35 cts.; ¼ pound $1.00**

*1908* **SUNSET.** A beautiful flower of rich rose with a glowing yellow suffusion at the base. Strong and free flowering.
**Packet 10 cts.; ½ ounce 25 cts.; ounce 35 cts.; ¼ pound 90 cts.**

*1924* **TANGERINE.** Deep orange, almost approaching the color of a tangerine orange. Large flowers, beautifully waved, and well placed.
**Packet 15 cts.; ½ ounce 25 cts.; ounce 40 cts.; ¼ pound $1.25**

*4177*
**One packet each of the above 12 Best Giant Spencer Sweet Peas (value $1.25) for only**
**$1.00**

# Seven of the Newer Giant Spencer Sweet Peas

*4175* One packet each of the following 7 Newer Giant Spencer Sweet Peas (value 70c).....for only **50c**

*1926* **CHARITY.** Rich brilliant crimson. Large well-waved flowers.
**Packet 10 cts.; ½ ounce 20 cts.; ounce 30 cts.; ¼ pound 75 cts.**

*1854* **COMMANDER GODSALL.** An attractive shade of deep violet-blue; large, waved and fluted flowers of heavy substance.
**Packet 10 cts.; ½ ounce 20 cts.; ounce 30 cts.; ¼ pound 75 cts.**

*1920* **DAISYBUD.** A harmonious combination of apple-blossom tints with a touch of carmine pink. Extra large.
**Packet 10 cts.; ½ ounce 25 cts.; ounce 35 cts.; ¼ pound $1.00**

*1865* **FIERY CROSS.** Brilliant orange scarlet of the largest size.
**Packet 10 cts.; ½ ounce 25 cts.; ounce 35 cts.; ¼ pound $1.00**

*1888* **MARGARET ATLEE.** Glowing rose-pink on cream ground.
**Packet 10 cts.; ½ ounce 20 cts.; ounce 30 cts.; ¼ pound 75 cts.**

*1925* **MRS. C. P. TOMLIN.** Scarlet with just a touch of fiery red.
**Packet 10 cts.; ½ ounce 20 cts.; ounce 30 cts.; ¼ pound 75 cts.**

*1869* **SPARKLER.** A charming combination of rose and cream, the standard being bright rose; the wings a lovely shade of rosy cream. Of the largest size, well waved.
**Packet 10 cts.; ½ ounce 20 cts.; ounce 30 cts.; ¼ pound 75 cts.**

1920 Sweet Pea, Daisybud Spencer

## *1922* Maule's Best Giant Summer Flowering Spencer Sweet Pea Mixture

**This mixture has been made with extraordinary care by us from the finest named, true, large summer-flowering Spencer varieties introduced to date, and in such quantities as to produce a well balanced and finely proportioned color effect. All dull and undesirable colors have been omitted, making this mixture the best ever offered, and it would be impossible to get any better at any price.**

**Packet 10 cts.; ½ ounce 20 cts.; ounce 30 cts.; ¼ pound 75 cts.; ½ pound $1.40; pound $2.50**

Early Flowering Spencer and Grandiflora Sweet Peas are offered on page 120

# Early Flowering Spencer Sweet Peas

A new race of Spencer Sweet Peas, having the same large flowers of the regular Spencer type but coming into bloom one or two weeks earlier, and if the flowers are kept picked, this type will continue to bloom as long as the Summer-flowering Spencers offered on pages 118 and 119. Valuable for out-door culture, especially in the extreme South or very warm climates, and largely used for forcing under glass for Winter and early Spring flowering.

## Six of the Finest Early Flowering Spencer Sweet Peas

*4169* One packet each of the following 6 Finest Early Spencer Sweet Peas (value 90c) ..... for **50c**

*1813* **BLUE BIRD.** A charming shade of blue, somewhat similar to the summer-flowering Wedgewood but more of a true self, especially as the flower ages.
**Packet 15 cts.; ½ ounce 45 cts.; ounce 80 cts.; ¼ pound $2.40**

*1832* **GLITTERS.** The standard is a bright fiery orange, and the wings most beautifully shaded with deep orange. It fairly glitters in richness, brightness and live fire effect. Of the finest form.
**Packet 15 cts.; ½ ounce 35 cts.; ounce 60 cts.; ¼ pound $1.80**

*1816* **KING.** The finest early-flowering crimson, of great size, perfect form, and borne in fours on long stems.
**Packet 15 cts.; ½ ounce 35 cts.; ounce 60 cts.; ¼ pound $1.80**

*1836* **LAVENDER KING.** A rich, true deep lavender throughout. A favorite color with many sweet pea lovers.
**Packet 15 cts.; ½ ounce 30 cts.; ounce 50 cts.; ¼ pound $1.50**

*1825* **ROSE QUEEN.** A most pleasing shade of rich pink with a suffusion of rose. The flowers are large, well waved and freely borne on long stems.
**Packet 15 cts.; ½ ounce 30 cts.; ounce 50 cts.; ¼ pound $1.50**

*1838* **SNOWSTORM.** The finest of all early flowering white Spencers. Flowers are extra large, fine form. Usually borne in fours.
**Packet 15 cts.; ½ ounce 35 cts.; ounce 60 cts.; ¼ pound $1.80**

1838 Sweet Pea, Early Snowstorm Spencer

## *1844* Maule's Early Flowering Spencer Mixed Sweet Peas

**This special mixture is a carefully composed blend of the finest of the Early Flowering Spencer Sweet Peas. Very free-flowering with many four-flowered sprays on long stems. Included are the above choice varieties and others to insure an extensive range of colors.**

**Packet 10 cts.; ½ ounce 25 cts.; ounce 35 cts.; ¼ pound 90 cts.; ½ pound $1.65; pound $3.00**

**Summer Flowering Giant Spencer Sweet Peas are offered on pages 118 and 119**

1780 Sweet Pea Choice Grandiflora Mixture

## 1877—Fifty Years in Business—1927

**The Maule seed business is 50 years old and to celebrate our Golden Anniversary, we are giving away, on all orders of $1.00 or over one packet each of the two great novelties (value 50c) as illustrated in colors on front cover.**

# Choice Grandiflora Sweet Peas

This class of Sweet Peas is the well-known ordinary type, the flowers of which are not as large as Spencers; neither are they waved or frilled. We offer these only in mixture.

## *1780* Maule's Choice Grandiflora Sweet Pea Mixture

**A delightful mixture, showing a wide range of colors and shades in well balanced proportions**

**Packet 5 cts.; ounce 15 cts.; ¼ pound 45 cts.; ½ pound 75 cts.; pound $1.25**

1940 Sweet William, Maule's Special Mixture

## SWEET WILLIAM (London Tufts)

**Hardy Perennial**

Well known, free blooming, old-fashioned favorites, now greatly improved. They produce masses of lovely, brilliant flowers through a long period, making a splendid effect in beds. 1½ feet high.

*1934* **PINK BEAUTY.** Exquisite shade of salmon pink.
**Packet 10 cts.; ⅛ ounce 25 cts.**

*1935* **SCARLET BEAUTY.** Rich, deep scarlet; a bed or border of this remarkable color is very striking.
**Packet 10 cts.; ⅛ ounce 25 cts.**

*1936* **DOUBLE MIXED.** A selection of the best double flowers in all shades and markings. Large flower heads.
**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**

*1938* **SINGLE MIXED.** The flowers are large, of handsome form and embrace a great variety of extremely rich colors.
**Packet 5 cts.; ¼ ounce 25 cts.; ½ ounce 40 cts.**

*1940* **MAULE'S SPECIAL MIXTURE.** We have made up this mixture of the best double and single flowering sorts of various colors.
**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**

1928 Sweet William, Annual Mixed

### Hardy Annual Sweet William

This new type begins to bloom in early summer from spring sown seed. Habit of plant the same as the perennial varieties, produces fine heads of bloom of various colors, white, crimson, rose pink, etc., many of which are broadly edged with white. Plants are hardy, producing larger blooms each season thereafter and lasting for years.

*1928* **HARDY ANNUAL FINEST MIXED.** The finest colors.
**Packet 10 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.**

## *1743* SCARLET RUNNER BEAN

**Hardy Annual Climber**

Strong, rapid grower, making a very quick dense shade; used for ornamenting porches, verandas and trellises. It bears brilliant scarlet pea-like flowers followed by bean pods which may be eaten green or shelled. A vine serving two purposes.
**Packet 10 cts.; ½ pound 25 cts.; pound 45 cts.**

## THUNBERGIA (Black Eyed Susan)

**Hardy Annual Climber**

*1942* **FINE MIXED.** Rapid growing vine preferring a warm, sunny situation. Excellent for vases, trellises, rustic work or greenhouse decoration. Flowers buff, orange, white, etc.; height 5 feet.
**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**

1946 Tritoma, Hybrida Express

1950 Umbrella Plant

## TRITOMA (Red Hot Poker, Torch Flower)

**Hardy Perennial**

Raising Tritomas from seed is very interesting and easily done. If seed is sown early indoors and plants set out in early spring they will bloom in July or August. The scarlet and yellow flower spikes are attractive either in the hardy border or for cutting. Height 3 feet.

*1946* **HYBRIDA EXPRESS.** Very early flowering.
**Packet 15 cts.; ⅛ ounce 50 cts.**

## *1950* UMBRELLA PLANT OR PALM

**Half Hardy Perennial**

Can easily be grown in water or damp places. Showy in pots, and desirable in the aquarium. An excellent house plant. Has long stems with narrow green leaves, umbrella shaped.
**Packet 15 cts.; 2 packets 25 cts.**

1952 Valeriana, Mixed

## VALERIANA

(Hardy Heliotrope)

**Hardy Perennial**

*1952* **MIXED COLORS.** A showy border plant, producing large corymbs of red or white flowers suitable for bouquets or decorations. The fragrant flowers are borne on stems 2 feet high.
**Packet 10 cts.; ⅛ ounce 25 cts.**

## WALLFLOWER

**Hardy Annual**

Bears long spikes or heads of exquisitely fragrant flowers through the summer from spring sown seed. It is very ornamental in the border or in forming groups. Colors are yellow, brownish, purple, etc.

*2020* **SINGLE MIXED.**
**Packet 10 cts.; ¼ ounce 25 cts.**

# VERBENA Hardy Annual

Indispensable for bedding purposes, borders and window boxes. Borne profusely from June until frost.



1978 Verbena, Maule's Mammoth Show, All Colors Mixed

**MAULE'S MAMMOTH SHOW.** The latest development in Verbenas; the flowers are of mammoth size, the plants are compact growing, bearing immense trusses, the individual florets measuring an inch and over in diameter. Unexcelled for size, beauty and richness of color.

*1953* **ROSE PINK, MAMMOTH SHOW.** Pure rose pink with large white eye.
**Packet 15 cts.; ⅛ ounce 50 cts.; ¼ ounce 85 cts.**

*1954* **VIOLET, MAMMOTH SHOW.** Deep violet with white eye. **Packet 15 cts.; ⅛ ounce 45 cts.; ¼ ounce 75 cts.**

*1955* **WHITE, MAMMOTH SHOW.** Pure white.
**Packet 15 cts.; ⅛ ounce 50 cts.; ¼ ounce 85 cts.**

*1956* **LUCIFER, MAMMOTH SHOW.** The flowers are an intense, deep cardinal-scarlet.
**Packet 15 cts.; ⅛ ounce 45 cts.; ¼ ounce 75 cts.**

*1978* **MAMMOTH SHOW, ALL COLORS MIXED.** Absolutely all the finest colored Verbenas ever offered in a mixture.
**Packet 15 cts.; ⅛ ounce 45 cts.; ¼ ounce 75 cts.**

## Maule's Mammoth Show Verbena Collection

**Well adapted for beds, borders or porch boxes**

*4182* One packet each of above 4 separate colors of Mammoth Verbenas (value 60c).....for **50c**

**EXTRA LARGE FLOWERING VERBENA.** Flowers are not quite as large as our Mammoth Show type. There are many beautiful shades and markings.

*1960* **PINK. Packet 10 cts.; ⅛ ounce 35 cts.**
*1962* **PURPLE. Packet 10 cts.; ⅛ ounce 35 cts.**
*1964* **SCARLET. Packet 10 cts.; ⅛ ounce 35 cts.**
*1966* **WHITE. Packet 10 cts.; ⅛ ounce 35 cts.**
*1967* **YELLOW. Packet 15 cts.; ⅛ ounce 40 cts.**
*1968* **FINEST MIXED.** Containing all the colors in mixture.
**Packet 10 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.**

1992 Vinca, Mixed Colors

2006 Viola (Violet), Odorato

# VINCA (Periwinkle or Old Maid)

**Half Hardy Perennial**

Very free-blooming and handsome bushy plants, with glossy foliage and round single flowers, 1½ inches across. Blooms the first season from seed. In a sunny situation they bloom all summer; in the fall, if taken up and potted, they will bloom in-doors through the winter.

*1992* **MIXED.** White, pink, and white with a pink centre.
**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**

# VIOLA (Sweet Scented Violet)

**Hardy Perennial**

The popular, fragrant sort, blooming very early in the spring. It will bloom earlier if protected during extremely severe weather.

*2006* **ODORATO.** Rich blue; large flowers. **Packet 10 cts.**
*2008* **FINE MIXED VIOLETS.** Blue and white flowers.
**Packet 10 cts.; ⅛ ounce 50 cts.**

2002 Viola, Improved Tufted Pansies, Fine Mixed

# VIOLA (Improved Tufted Pansy)

**Hardy Perennial**

The Tufted Pansy is rapidly coming to the front. They are very free flowering and unsurpassed for bedding purposes.

*2002* **IMPROVED TUFTED PANSY FINE MIXED.** All colors including blue, black, rose, purple, lavender, maroon, silvery-gray, crimson, orange, white, lemon, etc., in a grand mixture.
**Packet 10 cts.; ⅛ ounce 40 cts.; ¼ ounce 75 cts.**
(See pages 110 and 111 for Maule's Giant Pansies.)

# XERANTHEMUM

**Hardy Annual Everlasting**

*2030* **MIXED COLORS.** Beautiful, free blooming, rose, white and purple flowers, highly prized for winter bouquets.
**Packet 5 cts.; ¼ ounce 30 cts.**

# Maule's Gorgeous Zinnias

**(Youth and Old Age) Hardy Annual**

Zinnias begin to bloom early in the summer and continue profusely until frost, requiring no attention and succeeding almost anywhere. A general favorite enjoying a wide popularity, very desirable for garden use and especially useful for cutting, having good keeping qualities.

2054 Zinnia, Giant Double Flowering, Mixed Colors

## GIANT DOUBLE FLOWERING ZINNIAS

In this strain of Zinnias we have a flower of perfect form, round, full, double and immense in size. The individual plants form large bushes and bear above the foliage numerous flowers on long, stiff stems, which makes them valuable for cutting and will render them a favorite wherever tried. The plants grow 2½ to 3 feet high, while the flowers often measure 5 to 6 inches across. A favorite strain.

*2041* **BURNT ORANGE. Packet 10 cts.; ⅛ ounce 30 cts.**

*2042* **CRIMSON. Packet 10 cts.; ⅛ oz. 30 cts.; ¼ oz. 50 cts.**

*2043* **LEMON QUEEN.** Petals are light canary on the upper and cerise on the under side, the two shades blending as the flower develops making a variety of lemon tints.
**Packet 10 cts.; ⅛ ounce 40 cts.; ¼ ounce 75 cts.**

*2044* **PURPLE. Packet 10 cts.; ⅛ oz. 30 cts.; ¼ oz. 50 cts.**

*2045* **ROSE QUEEN.** A splendid color addition to this Giant Flowering type. Tyrian rose with deep rose-red centre; a deep rose when in full bloom. A very attractive color.
**Packet 10 cts.; ⅛ ounce 40 cts.; ¼ ounce 75 cts.**

*2046* **SCARLET. Pkt. 10 cts.; ⅛ oz. 30 cts.; ¼ oz. 50 cts.**

*2047* **FLESH COLOR. Packet 10 cts.; ⅛ ounce 30 cts.**

*2048* **WHITE. Packet 10 cts.; ⅛ oz. 30 cts.; ¼ oz. 50 cts.**

*2049* **DEEP SALMON ROSE.** Another new color very popular for cut-flower use.
**Packet 10 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.**

*2050* **GOLDEN YELLOW. Pkt. 10c.; ⅛ oz. 30 cts.; ¼ oz. 50c.**

*2051* **LIGHT SALMON PINK.** Very popular for cutting.
**Packet 10 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.**

*2052* **SULPHUR YELLOW.**
**Packet 10 cts.; ⅛ ounce 30 cts.; ¼ ounce 50 cts.**

*2053* **ORANGE KING.** So called because the color compares favorably with the Orange King Calendula. A very striking shade, petals decidedly imbricated.
**Packet 10 cts.; ⅛ ounce 40 cts.; ¼ ounce 75 cts.**

*2054* **GIANT DOUBLE FLOWERING MIXED COLORS.** The above and many others mixed.
**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.; ounce $1.25**

### Maule's Giant Double Zinnia Collection

**The colored illustrations on back cover give but a faint idea of the beauty of these gorgeous flowers.**

*4185* One packet each of Scarlet, Golden Yellow, Salmon Rose and White Giant Zinnias (value 40c).....for **35c**

## MAMMOTH DAHLIA FLOWERED ZINNIAS

The latest development in this wonderful flower which is gaining in popularity far beyond expectations. The flowers have a close resemblance to Decorative Dahlias, often measuring 3 to 4 inches in depth and averaging 6 inches across. The petals are broad and closely imbricated.

*2055* **CRIMSON MONARCH.** The largest and best red; flowers immense and of fine form. Holds its color well on plants and when cut.
**Packet 25 cts.; 1/16 ounce 60 cts.; ⅛ ounce $1.00**

*2056* **CANARY BIRD.** A delicate shade of primrose. Very large, holding its color well until out of bloom. A free bloomer.
**Packet 25 cts.; 1/16 ounce 60 cts.; ⅛ ounce $1.00**

*2057* **EXQUISITE.** Light rose with centre a deep rose; by far the most pleasing color for cutting. Truly Dahlia-flowered as regards form and size.
**Packet 25 cts.; 1/16 ounce 60 cts.; ⅛ ounce $1.00**

*2059* **GOLDEN STATE.** Yellow in the bud, turning to an attractive orange when in full bloom. A very desirable flower.
**Packet 25 cts.; 1/16 ounce 60 cts.; ⅛ ounce $1.00**

*2061* **ORIOLE.** An immense orange and gold bicolor, changing slightly as it ages, but at all times worthy of the beautiful bird for which it is named. Plants are very vigorous and produce many flowers.
**Packet 25 cts.; 1/16 ounce 60 cts.; ⅛ ounce $1.00**

*2063* **POLAR BEAR.** A very large pure white of true Dahlia-flowered form and size; best white yet seen in Zinnias.
**Packet 25 cts.; 1/16 ounce 60 cts.; ⅛ ounce $1.00**

*2065* **DAHLIA-FLOWERED, ALL COLORS MIXED.** A superb mixture of the better varieties; a wonderful display of the largest and most attractive flowers in many colors.
**Packet 15 cts.; ⅛ ounce 50 cts.; ¼ ounce 85 cts.; ounce $3.00**

### Maule's Dahlia-Flowered Zinnia Collection

**The largest of all Zinnias**

*4195* One packet each of the above 6 named Dahlia-Flowered Zinnias (value $1.50).....for **95c**

2065 Zinnia, Maule's Mammoth Dahlia-Flowered, Mixed Colors

## Double Quilled or Cactus Flowered Zinnia

Flowers average 4 to 5 inches in diameter. Distinct in form from all other Zinnias; the petals being so quilled that they become almost tubular, somewhat resembling a Cactus Dahlia.

*2066* **VICTORY, MIXED COLORS.** Colors range through varying shades of yellow, pink, orange rose and rose scarlet to crimson, mostly in russet, orange and other autumn tints.
**Packet 15 cts.; ⅛ ounce 40 cts.; ¼ ounce 75 cts.**

## Double Picotee Zinnia

Beautiful double flowers, in color from white to scarlet, each petal being distinctly marked on the edges with various dark colors, different from the body of the flower. Very attractive as bedders or cut-flowers.

*2070* **PICOTEE, ALL COLORS MIXED.** Unique and showy.
**Packet 15 cts.; ⅛ ounce 40 cts.; ¼ ounce 75 cts.**

## Curled and Crested Zinnia

Petals twisted, curled and crested in the most fantastic manner.

*2036* **CURLED AND CRESTED, MIXED COLORS.** The colors include practically all shades found in Zinnias. We offer a grand mixture.
**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 40 cts.**

## *2080* Tall Double Mixed

Embracing all the variously colored double varieties, making an elegant mixture for groups, beds, borders, etc.
**Packet 5 cts.; ¼ ounce 30 cts.; ounce $1.00**

## Improved Large-Flowering Dwarf Double Zinnias

Largely used for bedding, borders and cut-flower use. Forms bushy, compact plants not over 2 feet high. Bears large, perfect, double flowers from early summer to late autumn.

*2032* **BRIGHT SCARLET.** Bright and fiery; very striking.
**Packet 10 cts.; ¼ ounce 25 cts.; ounce 85 cts.**

*2035* **DARK SCARLET.** Rich and showy; a popular shade.
**Packet 10 cts.; ¼ ounce 25 cts.; ounce 85 cts.**

*2037* **GOLDEN YELLOW.** Golden orange; beautiful.
**Packet 10 cts.; ¼ ounce 25 cts.; ounce 85 cts.**

*2038* **SALMON ROSE.** The most popular color for cutting.
**Packet 10 cts.; ⅛ ounce 25 cts.; ¼ ounce 35 cts.**

*2039* **WHITE.** Pure white. Dainty and largely used.
**Packet 10 cts.; ¼ ounce 25 cts.; ounce 85 cts.**

*2040* **IMPROVED DWARF DOUBLE, ALL COLORS MIXED.**
**Packet 10 cts.; ¼ ounce 25 cts.; ounce 75 cts.**

## Maule's Dwarf Double Flowering Zinnia Collection

**Very satisfactory type for borders or cutting**

*4187* One packet each of above named 5 separate colors of Dwarf Double Zinnias (value 50c).....for **40c**

2026 Wistaria, Mixed Colors

2034 Zea Japonica, Quadri-color

## WISTARIA

**Hardy Perennial Climber**

*2026* **MIXED COLORS.** A vine of great value on arbors, trees or buildings. Bears great panicles of purple or white blossoms in profusion in spring. One of the most satisfactory of the hardy climbers. **Packet 10 cts.**

## ZEA JAPONICA (Rainbow Corn)

**Hardy Annual**

*2034* **QUADRI-COLOR PERFECTA.** An ornamental grass or variegated leaf corn or maize, with leaves striped yellow, green, pink and rose. Grows about 5 feet high.
**Packet 10 cts.; ounce 25 cts.**

# *2024* Maule's Wild Flower Garden Mixture

A mixture of the easiest and surest growing flower seeds, (no climbers) mostly annuals, but included are perennials, everlasting and ornamental grasses, that can be sown broadcast. With little or no care the results are both surprising and charming and on account of the various seasons of bloom, flowers can be had from early summer till frost, many of which will be fine for cutting. Desirable for children's garden.

**Packet 10 cts.; ounce 30 cts.; ¼ pound $1.00; pound $3.00; 2 pounds $5.00, postpaid**

# Maule's Flowering Bulbs, Roots, Etc.

Everyone succeeds in growing plants from Maule's bulbs and roots. With but little care, excellent results may be obtained. After flowering, many bulbs or roots, if given a period of rest, may be re-planted, when the previous year's display will be repeated. This of course applies to varieties that are not hardy. The hardy roots of Lilies, Iris, Peonies, etc., when once planted will live outdoors for years without being disturbed. A good supply of bulbs or roots may be obtained at a very moderate cost, for the first cost is practically the only expense.

With every order for bulbs or roots a copy of our booklet, **"Practical Hints on Bulb Culture,"** will be enclosed, **free.** It contains many helpful suggestions on the culture of bulbs and roots. By following the simple directions given, everyone should succeed in growing beautiful plants.

### 70B42 Elliottiana Yellow Calla Lily

Flowers of a rich, lustrous golden yellow, often measuring 4 to 5 inches across. The foliage is glossy, rich, dark green, marked and spotted with many white dots. A very beautiful, showy pot plant Not hardy.

**35 cts. each; 3 for $1.00; 6 for $1.90; $3.75 per dozen, postpaid**

## 74B99 Surprise Collection

**75 Bulbs for Only $2.00**

**All Properly Labeled For Delivery After May 1**

The supply of some of our Bulbs is exhausted before our selling season is over, while large quantities of other varieties are left on hand, for it is practically impossible to sell out all.

Rather than replant these "left-over" bulbs, we will put them up in "Surprise Collections," 75 bulbs in each collection, and offer the collection for **only $2.00,** postpaid.

These collections will be entirely of **our selection,** from varieties of which we have a surplus. All bulbs will be of first-class quality, properly labeled. **Orders will be filled in rotation as received, after May 1.** The first orders will get the best selection, although all orders will receive more than twice the catalog value.

It is to your advantage to order this collection **Early.** At such a low price, no collection of surplus bulbs will be made up for less than $2.00.



**Order Bulbs and Roots by Variety Number**

### 70B40 White Calla Lily

**(The Well-Known Lily of the Nile)**

One of the best plants for blooming in the open during the summer, and unequalled in the winter as a house plant. A very highly ornamental desirable plant of easy culture, producing numerous large white flowers. Not hardy.

**30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen, postpaid**

### 70B62 Crinum, Kirkii

Large clusters of Lily-like fragrant flowers, the petals of which are white, with a deep reddish purple stripe through the centre of each. Succeeds in pot or open ground. Not hardy.

**45 cts. each; 2 for 80 cts., postpaid**

### 73B94 Giant White Spider Lily

This magnificent Lily bears many tall flower stalks, each surmounted by large, pure white flowers highly prized on account of their delicate fragrance and chasteness. Adapted for pot culture or planting out-doors. Not hardy.

**20 cts. each; 3 for 50 cts.; 6 for 90 cts.; $1.75 per dozen, postpaid**

### 72B06 Ismene, Calentha Grandiflora

(Peruvian Daffodil.) Flowers snowy white, with green throat. Six broad petals with delicate frilled edges and incurved yellow anthers; of novel and unique form. A superior pot or open ground plant. Not hardy.

**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen, postpaid**

### Atamasco or Fairy Lily

Beautiful, dwarf plant, bearing Lily-like flowers somewhat similar to Amaryllis. Three to six bulbs make a fine pot plant during the summer or winter. Not hardy.

**70B14 ROSEA.** Clear rosy-pink.
**20 cts. each; 3 for 50 cts.; 6 for 90 cts.; $1.75 per dozen, postpaid**

**70B16 WHITE.** Beautiful white.
**10 cts. each; 3 for 25 cts.; 6 for 40 cts.; 75 cts. per dozen, postpaid**

## 70B36 Caladium, Esculentum

(Elephant's Ear)

A handsome plant of tropical aspect, bearing leaves sometimes a yard in expanse. Effective as a single plant on a lawn or in groups. Not hardy.

**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen, postpaid**

## 70B58 Cooperia, Pedunculata

The Atamasco-like flowers are pure white tinged with red on the outside; have a delicate fragrance. Plant in masses for effect. They bloom repeatedly throughout the season. Not hardy.

**10 cts. each; 3 for 25 cts.; 6 for 45 cts.; 85 cts. per dozen, postpaid**

## 71B60 Hyacinthus, Candicans

A wonderfully showy plant that blooms in the early summer. Practically hardy. Flower spikes are 3 to 4 feet high and bear from 20 to 30 large, white, bell-shaped flowers. Effective either singly or in groups.

**20 cts. each; 3 for 50 cts.; 6 for 90 cts.; $1.75 per dozen, postpaid**

## 70B38 Caladium, Fancy Leaved

No other summer foliage plant equals the Fancy Leaved Caladium in rich and gorgeous, yet soft coloring. Not hardy. Thrives in pot or box or shady situation. The root should be set in sandy loam.

**40 cts. each; 2 for 75 cts.; 6 for $2.00; $3.75 per dozen, postpaid**

## Oxalis

For borders and baskets. Set the bulbs about 3 inches apart, and the foliage will produce an unbroken mass, richly adorned with flowers. Not hardy.

**72B66 PINK.** Shamrock foliage.
**72B64 PURE WHITE.**
**72B62 LASIANDRIA PINK.** Cut foliage.
**72B68 MIXED COLORS.**

**Any of the above Oxalis 25 cts. per dozen; 25 for 45 cts.; 50 for 85 cts.; 100 for $1.50, postpaid**



## 72B52 Madeira or Mignonette Vine

This is an old favorite climbing vine, of rapid growth, with fleshy, heart-shaped, light green leaves and clusters of pure white, fragrant flowers. A free and constant bloomer. Suitable for trellis, porch, etc. Not hardy.

**15 cts. each; 3 for 40 cts.; 6 for 75 cts.; $1.40 per dozen, postpaid**



## 70B55 Cinnamon Vine

The handsome foliage is dark green, thick and glossy and free from insects, while numbers of white blossoms emit a delightful cinnamon-like odor. We know of no other vine that will more quickly and satisfactorily cover an arbor, trellis, wall or fence for shade or screen purposes. It will thrive anywhere, and when once established will grow for years. Grows 15 to 25 feet high.

**10 cts. each; 3 for 25 cts.; 6 for 45 cts.; 85 cts. per dozen, postpaid**

## 74B18 Tuberose, Excelsior Dwarf Double Pearl

24 to 30 inches high. Does not require staking as the stems are dwarf and stiffly erect with long spikes. Flowers large, full double, pure white and extremely sweet. Not hardy.

**10 cts. each; 3 for 25 cts.; 6 for 40 cts.; 75 cts. per dozen; 25 for $1.25; 50 for $2.25; $4.25 per 100, postpaid**

# AMARYLLIS

The Amaryllis is one of the best plants adapted to house culture, producing one or two spikes which are crowned with from three to six large trumpet-shaped flowers. The pot may be plunged in the soil out-doors during the summer or the bulb may be set in the open ground when the weather has become quite warm. Not hardy.

70B04 Amaryllis, Giant American Hybrid

## 70B04 Giant American Hybrid

Enormous flowers ranging in color from pure white marked with rose, red and crimson to the richest self-colored scarlet, crimson, bright red and almost maroon. We can supply strong bulbs in mixed colors only.

**75 cts. each; 3 for $2.00; 6 for $3.75; $7.25 per dozen, postpaid**

## 70B05 Johnsonii

Very large flowers, often measuring 6 to 8 inches across, of a rich, deep velvety crimson; each petal having a broad white stripe contrasting beautifully with the deep red color.

**65 cts. each; 3 for $1.85; 6 for $3.50; $6.75 per dozen, postpaid**

## 70B02 Equestris

Also known as Barbadoes Lily or Gloriosa Lily. A splendid type with flowers 4 to 5 inches across. The color is a brilliant orange scarlet, with exquisite green and white throat.

**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen, postpaid**

# Maule's Hardy Garden Lilies

No class of flowers could be more permanently attractive than the Hardy Garden Lilies. They are perfectly hardy; thrive ll in any garden where there is good drainage and will bloom more profusely each succeeding year.



## 72B26 Lilium, Auratum

(The Golden Rayed Lily of Japan)

One of the finest Lilies in cultivation. Flowers e large and highly scented. A reliable pot or arden plant. The white flowers, dotted with ocolate-crimson and striped with a golden nd through the centre of each petal, are pecially attractive. Blooms in July and Au-ust. 3 to 5 feet high. Of easy culture in any ell-drained garden soil.

**40 cts. each; 2 for 75 cts.; 6 for $2.00; $3.75 per dozen, postpaid**

## 72B24 Lilium, Album

Large white flowers with a greenish band through the center of each petal which are beautifully recurved. Of neat, graceful habit, delightfully sweet, and one of the finest for house or garden culture. Blooms out-doors in August and September. Grows 2 to 4 feet high.

**50 cts. each.; 2 for 90 cts.; 6 for $2.50; $4.75 per dozen, postpaid**

## 72B30 Lilium, Henryi

(The Yellow Speciosum.)

The flower stalks, 3 to 5 feet high, carry 5 to 8 large flowers each, the color, a rich apricot-yellow, lightly spotted with brown. Exceedingly beautiful and free flowering. Blooms out-doors in August and September.

**65 cts. each; 3 for $1.85; 6 for $3.50; $6.75 per dozen, postpaid**

## 72B34 Lilium, Roseum

Beautifully recurved petals of rosy-white, heavily spotted with rich crimson. Very desirable in every respect. A large clump makes a wonderful effect. Blooms out-doors in August and September; grows 3 to 4 feet high.

**30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen, postpaid**

**72B36 Collection**

**One bulb each of Maule's 6 named Hardy Garden Lilies (value $2.90) for only**

**$2.50**

**postpaid**

## 72B32 Lilium, Regale

(The Regal or Royal Lily)

Flowers are white, slightly suffused with pink, and having a beautiful ade of canary-yellow at the base of petals, and extending part way up e trumpet. Delightfully perfumed, reminding one of the Jasmine. Blooms ut-doors early in July. 3 to 4 feet high. Absolutely hardy, excellent for orcing.

**75 cts. each; 3 for $2.00; 6 for $3.75; $7.25 per dozen, postpaid**

## 72B28 Double Tiger Lily

Bright orange-red, spotted with black. Very showy, double flowers, 4 to feet high. Blooms during August and September. Easily grown, perfectly ardy.

**30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen, postpaid**



72B32 Lilium, Regale (Regal or Royal Lily)

# TALL BEARDED IRIS

**Fleur de lis or Flags**

The Iris is one of the finest, if not the finest of our hardy plants. Not particular as to soil or location, but asking only that the sun shine on it, it produces spikes of bloom that are marvelous in their delicacy of structure and colorings.

**(The standards are the upright petals, the falls are the drooping petals)**

**71B62 Alcazar.** The standard is a light bluish violet overlaid with a bright sheen of bronze. The falls are deep purple with white bronze-veined throat. A very attractive variety with large flowers of good texture.
**35 cts. each; 3 for $1.00; 6 for $1.90; $3.75 per dozen, postpaid**

**71B64 Archeveque.** Standards deep purple-violet; falls deep velvety-violet. A very handsome Iris, exquisite in every way.
**30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen, postpaid**

**71B66 Brooksiana.** Charming flowers of neat form, self colored delicate rose-lilac, without veining. Beautiful in masses.
**25 cts. each; 3 for 65 cts.; 6 for $1.20; $2.25 per dozen, postpaid**

**71B70 Fairy.** White, delicately bordered and suffused pale blue. The tallest standard variety giving a white effect. Very sweet scented.
**25 cts. each; 3 for 65 cts.; 6 for $1.20; $2.25 per dozen, postpaid**

**71B72 Helga.** Lemon-yellow with pearl shading. Huge flower; free blooming, of beautiful form.
**25 cts. each; 3 for 65 cts.; 6 for $1.20; $2.25 per dozen, postpaid**

**71B84 Nuee D'Orage.** Standards slatey grey; falls bronze and purple. Large flowers of great substance.
**25 cts. each; 3 for 65 cts.; 6 for $1.20; $2.25 per dozen, postpaid**

**71B90 Pallida Dalmatica.** A queen among flowers, grand and stately. Standards lavender, falls clear deep lavender. Flowers large and extra fine.
**35 cts. each; 3 for $1.00; 6 for $1.90; $3.75 per dozen, postpaid**

**72B00 Collection** — One root each of the above 7 named Tall Bearded Iris (value $2.00) for ..... **$1.75** Postpaid

71B66 Tall Bearded Iris, Brooksiana

## 71B98 Choice Mixture of Tall Bearded Iris

Many varieties in a wide color range.
**15 cts. each; 3 for 35 cts.; 6 for 60 cts.; $1.00 per dozen; 25 for $1.75; 50 for $3.25, postpaid**

# MAULE'S HARDY PERENNIAL PHLOX

Perennial Phlox succeeds in almost any soil, but, of course, extra care in preparing and enriching the soil and watering plants in dry weather will result in better plants and flowers. If the first spikes of bloom which usually appear in July and August, are removed as soon as over, the plants will produce a second supply of flowers, continuing the display until late in the autumn. They are perfectly hardy, becoming larger and more beautiful each year.

73B48 Hardy Perennial Phlox, Mrs. Wm. Jenkins

**73B34 Beacon.** Brilliant cherry-red flowers of immense size. The vivid coloring of flowers, the strong, sturdy habit of plant makes this variety a desirable one.

**73B42 Europa.** White with large crimson-carmine eye. An easy grower and a free bloomer with large flower heads.

**73B44 Jules Sandeau.** Grown extensively where a variety of dwarf habit is wanted. In size the individual flowers and flower-heads and free-blooming character are equal to the taller growing varieties. The color of the flowers is a pure pink.

**73B46 La Vague.** Immense heads of pure mauve with an emphatic carmine eye. An improvement over older varieties of similar color.

**73B48 Mrs. William Jenkins.** Large, well-rounded flower-heads composed of mammoth size, snow-white blooms. Mrs. William Jenkins is by far the best of all white varieties of Hardy Phlox.

**73B50 Professor Virchow.** A strong grower and profuse bloomer with large massive flower-heads. The individual blooms are large, well expanded, and set closely together, making a solid ball. The color is a bright carmine overlaid with rich orange-scarlet.

**73B54 Rynstrom.** Carmine-rose color of the same shade as Paul Neyron Rose. The general effect is soft rose-pink. Splendid for massing. Large flower.

**73B56 Thor.** A beautiful lively shade of deep salmon pink, suffused and overlaid with a scarlet glow; has aniline-red eye. Attractive.

**Any of the above 8 named Perennial Phlox, 30 cts. each; 3 for 80 cts.; 6 for $1.50; 12 for $2.75, postpaid**

**73B60 Collection** — One root each of the above 8 named Hardy Perennial Phlox (value $2.40).....for only **$1.75** Postpaid

## Hibiscus, Hardy Marvel

**(Improved Giant-Flowering Mallow)**

Showy, ornamental shrub with handsome green foliage, bearing in profusion throughout the summer large bright flowers measuring 8 to 10 inches across. Perfectly hardy and especially suited for garden effect.

**71B40 Pink 71B42 Red 71B44 White**

**Any color, 40 cts. each; 3 for $1.10; 6 for $2.00; $3.75 per dozen, postpaid**

## 70B56 Clematis, Davidiana

Shrubby plant, 2½ feet high with bright green foliage, producing during August and September deliciously fragrant, tubular, bell-shaped, deep lavender-blue flowers, perfectly hardy.

**75 cts. each; 3 for $2.00; 6 for $3.75, postpaid**

## 71B30 Hemerocallis, Dr. Regel

**(Orange Yellow Day Lily)**

Blooms in May and again in early fall. No flower has a more glorious color; the lily-like single blossoms are of the richest orange yellow and deliciously fragrant. Perfectly hardy.

**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen, postpaid**

## 71B34 Hemerocallis Kwanso Fl. Pl.

**(Double Golden Crown Lily)**

Large, golden-orange double flowers with darker shadings, each flower having a carmine ring toward the center. It is perfectly hardy and should be in every hardy border. Requires but little attention, blooming freely during July and August. Will grow anywhere; attains a height of 4 to 5 feet.

**35 cts. each; 3 for $1.00; 6 for $1.90; $3.75 per dozen, postpaid**

## Platycodon

**(Dwarf Japanese Bell Flower)**

**73B68 MARIESI BLUE.** A low growing, bushy plant, producing bell-shaped flowers of a lovely violet blue, almost rivaling the splendid Jackmanii Clematis. Perfectly hardy, producing handsome branching spikes 1 to 2 feet high, which furnish large, showy flowers continuously from July until frost.

**73B70 MARIESI ALBA.** White flowered form of the above. A profuse bloomer.

**Either of the above colors, 25 cts. each; 2 for 45 cts.; 6 for $1.20; $2.25 per dozen, postpaid**

## 70B76 Dielytra, Spectabilis

**(Bleeding Heart)**

One of the earliest blooming hardy plants, bearing long racemes of graceful, heart-shaped pink flowers with white inner petals. The finely cut foliage makes plant attractive even when not in bloom. Valuable for planting in semi-shade. An old-fashioned favorite.

**75 cts. each; 2 for $1.25; 6 for $3.50, postpaid**

## 70B74 Dielytra, Eximia

**(Plumy Bleeding Heart)**

Dwarf-growing, about 15 inches high, with beautiful, finely cut foliage and showy racemes of pretty pink flowers from April till August. A fine border plant; perfectly hardy.

**35 cts. each; 3 for $1.00; 6 for $1.90; $3.75 per dozen, postpaid**

## 74B08 Statice, Latifolia

**(Great Sea Lavender)**

A valuable hardy perennial plant either for the border or rockery, with tufts of leathery leaves and immense candelabra-like heads, frequently 1½ feet high and 2 feet across, of purplish-blue minute flowers during July and August. These, if cut and dried, last in perfect condition for months.

**30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen, postpaid**

## 73B86 Rudbeckia, Golden Glow

Perfectly hardy. Attains a height of about 6 feet, and produces from July till September a wealth of double golden-yellow flowers 2 to 3 inches across. Fine for cutting. Well known and very popular.

**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen, postpaid**

74B08 Statice, Latifolia

## 74B12 Tritoma Seedlings

(Red Hot Poker, Torch Flower)

Bloom from August to October, with spikes 3 to 4 feet high, and heads of bloom from the palest lemon-yellow to deepest burnt orange. Succeeds in any ordinary garden soil. Hardy if given protection.

**35 cts. each; 3 for $1.00; 6 for $1.90; $3.75 per dozen, postpaid**

## Anemone, Japonica

(Japanese Windflower)

These beautiful flowers offer an agreeable surprise to those having a bed of them for the first time. They grow rapidly, bloom profusely from early in August until cut down by frost. Excellent for cutting, lasting for several days. Grow 2 to 3 feet high. Perfectly hardy if covered with leaves or short manure during the winter. Can be used for solid beds or as a border plant, or clumps planted in the hardy border.

**70B08 ALBA.** Purest white, with yellow center.

**70B10 QUEEN CHARLOTTE.** Abundant semi-double flowers broad and perfectly formed "La France" pink.

**70B12 WHIRLWIND.** Excellent double white flowers.

**Any of the above Anemones 35 cts. each; 3 for $1.00; 6 for $1.90; $3.75 per dozen, postpaid**

## 74B24 Veronica, Longifolia Subsessilis

(Japanese Speedwell)

One of the handsomest blue-flowering plants. Perfectly hardy. Spikes completely studded with beautiful blue flowers from July to September. Height, 2 feet; fine for cutting.

**35 cts. each; 3 for $1.00; 6 for $1.90; $3.75 per dozen, postpaid**

74B24 Veronica, Longifolia Subsessilis

## 74B06 Spirea, Filipendula (Dropwort)

Elegant border plants with numerous feathery plumes of white flowers on stems 15 inches high. Blooms in June and July; attractive fern-like foliage. Perfectly hardy. Succeeds in all locations but prefers rich, moist soil.

**35 cts. each; 3 for $1.00; 6 for $1.90; $3.75 per dozen, postpaid**

73B88 Rudbeckia, Purpurea

72B02 Japanese Iris, Mixed

## 72B02 Japanese Iris, Mixed

Japanese Iris are perfectly hardy and will succeed in almost any soil or position. They begin flowering about the middle of June and continue for five or six weeks. The flowers are enormous and fine for cutting. We offer all colors mixed.

**20 cts. each; 3 for 50 cts.; 6 for 90 cts.; $1.50 per dozen, postpaid**

## 73B88 Rudbeckia, Purpurea

(Giant Purple Cone-flower)

Peculiar reddish-purple flowers, with a very large, brown cone-shaped center. Blooms from July to October. 3 feet high. Perfectly hardy.

**30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen, postpaid**

72B58 Nymphaea, Odorata

## 72B58 Nymphaea, Odorata or Water Lily

**(The Well-Known Native White Pond Lily)**

**Roots are ready for delivery from May 1 to June 1. Place your order early, and we will send them when ready.**

Flowers pure white and fragrant; widely popular. It is only necessary to set the roots in the mud, where the water is sluggish in the stream, after which the plant will require no further attention. Perfectly hardy, living in ponds or streams all winter. Where a stream or pond is not easy of access, roots can be grown in a tub, removing the tub to the cellar over winter.

**50 cts. each; 3 for $1.25; 6 for $2.25; $4.25 per dozen, postpaid**

## 70B32 Buddleia, Variabilis Magnifica

**(Everblooming Butterfly Bush or Summer Lilac)**

The above names are applied to this plant because the flowers resemble those of the Lilac and attract butterflies in large numbers, particularly the large and gorgeously colored ones which swarm about it as though vying with it in brilliancy of color. The long, graceful stems terminate in tapering panicles of beautiful lilac-colored flowers that are of miniature size and borne by the hundreds on a flower head which is frequently 12 to 15 inches long. Begins to bloom in July and continues till severe frost. Succeeds everywhere; flowers freely the first year. Really a shrub, but the top usually freezes back and new growth starts from the root like other perennials. If tops do not freeze back, the plant should be severely pruned each spring before growth starts.

**Strong, field-grown roots, 75 cts. each; 3 for $2.00; 6 for $3.75; $7.00 per doz., postpaid**

70B32 Buddleia or Butterfly Bush

70B60 Coreopsis, Harvest Moon

## 70B60 COREOPSIS, Harvest Moon

One of the best hardy plants. Large bright yellow flowers are produced in great profusion all summer long. Culture easy; thrive anywhere. Very showy.

**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen, postpaid**

## 74B32 YUCCA, Filamentosa

(Adam's Needle)

Among hardy plants there is nothing more effective and striking for isolated positions on the lawn or on dry banks where few other plants thrive. Its broad, swordlike, evergreen foliage and immense branching spikes of drooping, creamy white flowers, rising to a height of 6 feet, render it a bold and handsome subject.

**50 cts. each; 2 for 90 cts.; 6 for $2.50; $4.75 per dozen, postpaid**

74B32 Yucca, Filamentosa

## 70B06 ANCHUSA, Opal

(Alkanet)

For producing a mass effect of brilliant blue, the Anchusas cannot be surpassed. nts grow 3 to 4 feet high, producing a solid sheet of soft turquoise-blue. They ould be treated as biennials, as the old plants exhaust themselves at the end of two three years. They reproduce themselves, however, from self-sown seed. The bloom- season can be extended for several weeks by cutting the spikes as soon as the wers fade, thus preventing seeding.

**35 cts. each; 3 for $1.00; 6 for $1.75; $3.25 per dozen, postpaid**

70B82 Everlasting Peas, Pink Beauty

## EVERLASTING PEAS

(Hardy Sweet Peas)

A showy, perennial climber, attaining a height of 6 to 8 feet when trained upon a trellis or arbor. Not fragrant. They are extremely showy and fine cut flowers.

**70B82 PINK BEAUTY.** Large racemes of pleasing deep rose.

**70B84 RED.** The well known red Everlasting Pea.

**70B86 WHITE PEARL.** A great improvement on the older white variety, the stems bearing 12 to 15 flowers each.

**Any variety of Everlasting Peas: 35 cts. each; 3 for $1.00; 6 for $1.90; $3.75 per dozen, postpaid**

70B24 Hardy Aster, Climax

## HARDY ASTERS

(Michaelmas Daisies)

These stand unrivaled for their brilliant shades of color and extreme profusion of bloom during the autumn months. They are invaluable for the border and for cut flowers. Very hardy and easily grown, succeeding in almost any soil or situation.

**70B22 FELTHAM BLUE.** Light aniline blue. 2½ feet high. Very free flowering.

**70B24 NOVI-BELGI CLIMAX.** One of the best and showiest, with large pyramidal spikes of large light lavender-blue flowers; very free blooming; 5 feet.

**Either variety of Hardy Asters: 35 cts. each; 2 for 65 cts.; 6 for $1.85; $3.50 per dozen, postpaid**

B64 Shasta Daisy, Etoile d'Or

## 71B22 GYPSOPHILA, Paniculata Compacta

(Baby's Breath)

Very branching or spreading, slender plants, with scant foliage when in bloom. Of easiest culture in open, rather dry places. Desirable where a mass of delicate, misty bloom will fill in a bare place. Blooms in August and September. Forms a symmetrical mass 2 to 3 feet in height and as much through, of minute white flowers having a beautiful gauze-like appearance. Perfectly hardy.

**30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen, postpaid**

## 72B38 LYCHNIS, Chalcedonica

(Jerusalem Cross)

One of the brightest plants in a garden. Flower heads are of vivid scarlet; blooms in June and July; 2 to 3 feet high. Perfectly hardy.

**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen, postpaid**

## 70B64 SHASTA DAISY, Etoile d'Or

Most attractive in the perennial border, the flowers averaging 4 inches in diameter, borne on long, stiff stems. It blooms freely from July for several months. The als or rays are pure glistening white, with small golden yellow centers. Height, feet, robust and free flowering. These flowers have been greatly improved in size l form, the slender stems springing from the base of the plant, and is most attractive her in the perennial border or as a cut flower.

**50 cts. each; 3 for $1.25; 6 for $2.25; $4.25 per dozen, postpaid**

71B22 Gypsophila, Paniculata Compacta

**A choice list of Cannas will be found offered on pages 134 and 135**

## HOLLYHOCK, Double Flowering

This old-fashioned flower reaches a height of 6 feet or more, and on account of its stately growth is unexcelled for planting along fences of buildings, or for background effects. They are perfectly hardy and once planted they will literally take care of themselves, but will repay by their gorgeous and lavish bloom all the attention bestowed upon them. It is a plant of strong, vigorous growth with elegant camelia-like flowers that form perfect rosettes of the most lovely shades of color.

**71B50 NEWPORT PINK; 71B56 WHITE; 71B52 ROSE; 71B54 SCARLET; 71B58 YELLOW.**

**Any color, 30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen, postpaid**

**71B59 Collection** — One root each of the 5 separate colors of Double Hollyhocks . . . . . for **$1.25** postpaid

71B50 Double Hollyhock, Newport Pink

70B18 Aquilegia, Long Spurred

## 70B18 AQUILEGIA (Columbine)

### Long Spurred Hybrids, Mixed Colors

Not particular as to soil or location, although they prefer a sandy loam and a moist but well drained, sunny position, and usually make themselves at home in the open garden, permanent beds or borders or edges of shrubbery. Blooms during May and June when flowers are scarce. Plants grow 2 to 3 feet high. Perfectly hardy. The flowers of this new strain are quite distinct, having broader petals and longer spurs. Shades of blue, orange, scarlet, yellow, white, mauve, pink, etc., will be found in this mixture.

**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen, postpaid**

71B08 Gaillardia, Mixed Colors

## 71B08 GAILLARDIA (Blanket Flower)

### Mixed Colors

Exceedingly beautiful, growing 1 to 2 feet high. The flowers are very showy and excellent for beds or for cutting. Should be in every hardy border as they take care of themselves, require no protection and will thrive in almost any soil or position. One of the most desirable hardy plants in cultivation; blooms from June till frost. Highly colored flowers.

**30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen, postpaid**

## 72B22 LIATRIS, Pycnostachya

Popularly known as Kansas Gay Feather. Long narrow spikes of rich purple flowers in July and August. 5 feet high. Beautiful and odd.

**30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen, postpaid**

## 70B28 BAPTISIA, Australis

(False Indigo)

Dark blue pea-shaped flowers. Blooms in June. Two feet high. Perfectly hardy.

**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen, postpaid**

70B30 Bocconia, Cordata

## 70B30 BOCCONIA, Cordata (Plume Poppy)

A noble, hardy perennial, beautiful in foliage and flower, and adapted for planting in the shrubbery borders, center of beds, and in bold groups in any position. It will grow in any soil or situation, attaining 6 to 8 feet in height. Flowers are creamy-white in terminal panicles during July and August.

**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen, postpaid**

## CHRYSANTHEMUMS

### Hardy Old-Fashioned Varieties

Bloom in October and November, when nearly all other outdoor flowers are gone. 3 to 4 feet high. Showy when in bloom, desirable for cutting.

**70B46 Pink, 70B48 Red, 70B50 White, or 70B52 Yellow, Any color, 30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen, postpaid**

**70B54 Collection—One root each of the 4 separate colors for only $1.00, postpaid**

73B82 Pyrethrum, All Colors Mixed

## 73B82 PYRETHRUM, All Colors Mixed

(Persian Daisy)

Handsome, herbaceous garden plants about 2 feet high, bearing Daisy-like or Aster-like flowers, 3 or 4 inches across, ranging in colors from light pink to deep red. Blooms in May and June and again in the fall. Pyrethrums are so simply and easily cultivated that they may be recommended to all who possess a garden. Flowers are bright and elegantly borne on long stems; most convenient for decoration. In form, the double varieties are somewhat aster or chrysanthemum-like, and as their chief beauty is in the months of May and June, they may well be called Spring Chrysanthemums, possessing the advantage over the Chrysanthemums of being able to withstand the severest Winter without protection. The single-flowered varieties are variable colored Marguerites and possess a wide range of color, very popular. Thrive in any good soil.

**30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen, postpaid**

## 74B22 VALERIANA, Coccinea

(Hardy Heliotrope)

A showy perennial border plant producing large heads of old-rose flowers on stems 2 feet high. Blooms from June to October.

**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen, postpaid**

# MAULE'S FRAGRANT PEONIES

## THE NATIONAL FLOWER FOR MEMORIAL DAY

Peonies are too well known to require description. They are perfectly hardy, will thrive in almost any location and ...en once planted will increase in size and beauty each year. We offer six of the choicest varieties, worthy of a place in ... garden. All are fragrant.

72B96 Peony, Festiva Maxima—the Finest White

### 72B88 Duchess De Nemours — Excels as a Cut Flower

Guard petals are white, centre lemon-yellow which gradually fades to white. Very large, sweetly fragrant, early and profuse bloomer.

**60 cts. each; 3 for $1.70; $6.50 per dozen, postpaid**

### 72B90 Edulis Superba — The Memorial Day Peony

Extremely early, rarely failing to be in bloom for Memorial day. A beautiful, brilliant mauve-pink with silvery reflex. Very large blooms on strong, upright stems.

**60 cts. each; 3 for $1.70; $6.50 per dozen, postpaid**

### 72B94 Felix Crousse — One of the Best Red Varieties

Large globular-shaped bloom of brilliant, dazzling red with ruby-flamed centre. Strong, vigorous grower, free bloomer and one of the most popular and very foremost red Peonies for general planting.

**$1.00 each; 2 for $1.75; $10.00 per dozen, postpaid**

### 72B96 Festiva Maxima — The Finest White Peony

Enormous full, double blooms of wondrous beauty. Color pure white with a few centre petals usually flecked with crimson spots. Very early, surpassingly fragrant and should be in every collection of Peonies.

**75 cts. each; 3 for $2.00; $7.50 per dozen, postpaid**

### 73B00 Mad. De Verneville — Very Chaste and Charming

Sulphur white, broad guard petals, centre rosy-white when first open, fading to pure white with an occasional edging and flecks of carmine. Blooms early and profusely; exceedingly fine, full Anemone shaped flower with sweet, rose-like fragrance.

**75 cts. each; 3 for $2.00; $7.50 per dozen, postpaid**

### 73B08 Mons. Jules Elie — Largest and Finest of All Pinks

Very full blooms of glossy, pale lilac-rose, deeper at base of petals, entire flower overlaid with a silvery sheen. With good culture this variety produces a flower of unusual size and beauty; imbricated, massive and imposing—the king of all Peonies.

**$1.25 each; 3 for $3.50; $13.00 per dozen, postpaid**

## SPECIAL PEONY OFFERS

**73B25 COLLECTION** — One root each of Edulis Superba (pink), Felix Crousse (red), and Festiva Maxima (white), value $2.35 ..... for **$2.00** postpaid

**73B27 COLLECTION** — One root each of Maule's six named Gorgeous Peonies (value $4.95) ..... for only **$4.00** postpaid

### 70B44 CENTAUREA, Montana

(Perennial Corn Flower)

Large violet-blue flowers from July to September. Height 2 feet. Easily ...own; excellent for cutting.

**30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen, postpaid**

# DELPHINIUM

(Hardy Perennial Larkspur)

The culture of Delphiniums is exceedingly simple. They thrive in almost ...y position, a rich friable loam suits them finely; but any soil, even hot ...d sandy, if well watered and manured, will give excellent results. A succession of flowers may be expected from spring to early autumn, ...pecially if the spikes which have flowered early are cut down to the ...round; fresh growth will then be produced which will give blossoms.

### 70B66 Belladonna

The turquoise-blue color of the bloom is not equalled for delicacy and ...eauty by any other flower. Plants grow about 3 feet high.

**... cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen; 25 for $5.00, postpaid**

### 70B68 Bellamosa

Has the same free and continuous blooming qualities as Belladonna, but ...e blooms are rich, deep blue. Just as desirable for cutting or garden ...ecoration.

**... cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen; 25 for $5.00, postpaid**

### 70B70 Gold Medal Hybrids

A choice strain of mixed hybrids, the flowers being of every shade of ...ue. Flowers and spikes are large; desirable for cutting or garden deco...tion.

**... cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen; 25 for $4.50, postpaid**

### 70B72 Mammoth Prize Exhibition

Immense spikes of the most beautiful flowers in both single and double ...rms, of every imaginable shade of blue, varying from the palest silvery-...ue to the deepest indigo, with many intermediary pastel tones of mauve, ...ink and lavender blendings. We believe these to be the choicest strain of ...ixed hybrids in cultivation, both for size of bloom and spike, as well as ...ch and delicate colors.

**... cts. each; 3 for $1.25; 6 for $2.25; $4.25 per dozen; 25 for $8.00, postpaid**

70B72 Delphinium, Mammoth Prize Exhibition

A choice list of Prize-Winning Dahlias is offered on pages 136 and 137

# Maule's Large Flowering Cannas

For bedding purposes, Cannas stand at the head of the list. No more satisfactory plant could be found; they succeed all parts of the country, in any kind of soil, but will, of course, do better in rich soil, and if freely watered at all times. recent years, Cannas have been constantly improved. The newer types have flowers six to eight inches across, in gre clusters of varied and rich colors, borne continuously all summer. We send out dormant roots in strong divisions from fie grown clumps. The height given for each Canna may vary with climate and care.

## Maule's Six Extra Choice Cannas

### 75B19 Dragon

3 feet. Green foliage. A remarkably rich color, best described as deep ox-blood. A free-blooming variety, with large massive blooms.
**30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen, postpaid**

### 75B36 Gladiator

5 feet. Green foliage. Cheerful flowers of bright golden yellow, spotted and marked with scarlet. It is a strong grower and an excellent bloomer; always attracts attention.
**20 cts. each; 3 for 50 cts.; 6 for 90 cts.; $1.75 per dozen, postpaid**

### 75B60 Mrs. Alfred F. Conard

4 feet. Green foliage. One of the most popular pink Cannas ever introduced. The color of the blooms is exquisite salmon-pink; flowers are of the largest size and produced in abundance on robust, upright stalks.
**35 cts. each; 3 for $1.00; 6 for $1.90; $3.75 per dozen, postpaid**

### 75B71 Orange Bedder

4 feet. Green foliage. Bright orange with just enough scarlet suffusion to intensify the dazzling mass of color. Attractive and beautiful variety.
**20 cts. each; 3 for 50 cts.; 6 for 90 cts.; $1.75 per dozen, postpaid**

### 75B85 Wyoming

7 feet. Purple foliage. A beautiful orange shade. The flowers are borne well above the luxuriant growth of foliage.
**20 cts. each; 3 for 50 cts.; 6 for 90 cts.; $1.75 per dozen, postpaid**

### 75B89 Yellow King Humbert

4 feet. Green foliage. Tall stately flowers of deep rich yellow softly blotched with bright red, sometimes flowers of scarlet or scarlet striped are produced. The flowers are large.
**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen, postpaid**

**75B94 Collection** — One root each of the above 6 named Extra Choice Cannas (value $1.50) ..... for **$1.15** postpaid

75B46 Canna, Hungaria—the Ideal Pink for Bedding

## Six Showy and Desirable Cannas

### 75B12 Cheerfulness

3½ feet. Green foliage. Large trusses of deep orange flowers edged with a golden border and flaked with carmine-crimson. Blooms early and continues until frost.
**20 cts. each; 3 for 50 cts.; 6 for 90 cts.; $1.75 per dozen, postpaid**

### 75B22 Dr. E. Ackerknecht

4 feet. Bronze foliage. An unusually pretty shade of carmine-lake suffused with deep carmine. Showy in beds.
**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen, postpaid**

### 75B39 Gladioflora

This is a bright variety, with bold and well-shaped blooms on massive and heavy stems. A rich bright crimson changing to carmine-rose edged with a distinct border of gold.
**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen, postpaid**

### 75B68 Olympic

4½ feet. Green foliage. Very showy, strong-growing variety. The flowers are large and form massive heads which stand out sharply from the rich dark green foliage. The color of the flowers is best described as rich oriental red, shading lighter toward the center of the petals, and showing carmine markings in the throat.
**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen, postpaid**

### 75B79 Rosea Gigantea

4 feet. Green foliage. Very rich yet soft rose, almost a coral carmine. It is a wonderful bloomer, quite attractive.
**30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen, postpaid**

### 75B82 Wintzer's Colossal

5 feet. Green foliage. Bright scarlet flowers frequently measuring eight inches in diameter. Very effective.
**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen, postpaid**

**75B96 Collection** — One root each of the above 6 named Showy and Desirable Cannas (value $1.50) ..... for **$1.10** postpaid

## Five Grand Bedding Cannas

### 75B33 Gaiety

4 to 5 feet. Green foliage. One of the earliest and free flowering varieties, holding its bright reddish orange bloor well above the foliage. To this fascinating color add a gold yellow border and center and you have a variety of marvelo beauty.
**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen, postpa**

### 75B42 Golden Gate

4 feet. Green foliage. Flowers of good size and substanc a fine golden yellow slightly splashed with red. Large flow spikes. A free bloomer, showy and attractive.
**20 cts. each; 3 for 50 cts.; 6 for 90 cts.; $1.75 per dozen, postpa**

### 75B46 Hungaria

3½ feet. Green foliage. Blush pink with satiny sheen n unlike the color of a Paul Neyron Rose. The plant is a fre early and continuous bloomer. It is the ideal pink beddir Canna.
**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen, postpa**

### 75B57 Meteor

5 feet. Green foliage. One of the best deep blood-r colored cannas for bedding. Flowers and trusses of t largest size.
**30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen, postpa**

### 75B64 Nokomis

4 feet. Unusually effective crimson carmine trusses of lar flowers surmount vigorous stalks of green bronze foliage.
**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen, postpa**

**75B98 Collection** — One root each of the above 5 named Grand Bedding Cannas (value $1.25) ..... for **$1.00** postpaid

# Maule's Large Flowering Cannas, Continued

Do not grow Cannas that are commonly found in every garden! Those offered on this page are of exceptional t, far surpassing all others in coloring and size and we can recommend them most highly. Delight yourself and flower-loving friends by planting as many of these and as many more of those on the opposite page as space will ait. Demand for Maule's Cannas and other bulbs is certain to be heavy, so ORDER EARLY.

## Maule's Four Most Popular Cannas

5B75 The President
ne Grandest Green-leaved Red Canna

### 75B75 The President

**The Finest, Largest and most Wonderful Red Canna ever offered**

The rich, glowing, immense, rounded flowers, 7 inches across when open, are so surpassingly fine that no other red Canna can compete with the "The President." The flowers are most attractive, produced on strong, erect stalks well above the large, rich green foliage, which grows about 5 feet high. Solid beds or borders of this variety are a sight to behold.

**30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen, postpaid**

### 75B29 Eureka

**The Best White Canna**

Green foliage. The best white flowering Canna yet introduced. The immense clusters of flowers are borne well above the foliage. Should be in every garden. Exceptionally free flowering. Grows 4½ feet high.

**30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen, postpaid**

### 75B50 King Humbert

**The Most Popular Canna Grown**

Immense heads of Orchid-like flowers measuring from six to eight inches across; velvety orange-scarlet, rose-tinted and margined at the base. Foliage a rich, dark bronzy chocolate, wide and luxuriant; a combination of leaf and blossom, incomparably beautiful. Grows 4 to 5 feet high. Exceedingly showy.

**25 cts. each; 3 for 70 cts.; 6 for $1.30; $2.50 per dozen, postpaid**

### 75B15 City of Portland

**A Vigorous Free Flowering Pink Canna**

3½ feet. Green foliage. The finest all around pink Canna, of its class, introduced to date. The color is a beautiful, glowing pink; the flowers are produced in the greatest profusion.

**30 cts. each; 3 for 80 cts.; 6 for $1.50; $2.75 per dozen, postpaid**

**75B90 Collection** — One root each of the above four most popular Cannas (value $1.15).....for only **$1.00** postpaid

## Two Sensational New Cannas

**Desirable acquisitions, introducing new tones of color and showing the highest development in form and habit**

### 75B25 Dr. Robert Bosch

**Admired By All Who See It**

½ feet. Green foliage. Many describe the color as ıge-scarlet, but "tango" will give a clearer impression t. Very rich and unusually attractive with its large ers held on firm, straight stems in large trusses well ve the foliage. A remarkably clean-cut large-flowered elty of excellent habit, both as to growth and flower- Sure to please all who try it.

**ts. each; 2 for 75 cts.; 6 for $2.00; $3.75 per dozen, postpaid**

### 75B53 King Midas

**A Grand Canna in Every Way**

5 feet. Green foliage. Very large flowers of glittering gamboge-yellow. An outstanding variety. The habit is all that can be desired, free-flowering and vigorous in growth and bloom. Be sure to grow this Canna. Flowers are of splendid round form and assembled into great shapely trusses borne well above the foliage.

**45 cts. each; 2 for 80 cts.; 6 for $2.25; $4.25 per dozen, postpaid**

**391 COLLECTION—One root each of Dr. Robert Bosch and King Midas Cannas (value 85 cts.) for 75 cts., postpaid**

**5B92 Special Collection** — One root each of all the above Six Named Cannas (value $2.00).....for only **$1.50** postpaid

# Maule's Prize-Winning Dahlias

On this and the following page, we offer only such varieties of Dahlias as we consider the very best as to form, co size of flower, freedom and perfection of bloom as well as length of flowering season. We send out good, strong division field-grown clumps.

## Six Best Decorative Dahlias

A collection of five exceptionally fine Dahlias: **Bashful Giant**—apricot shaded yellow; **Jersey's Beauty**—the finest pink Dahlia ever grown; **Judge Marean**—a glowing autumn coloring; **Mephistopheles**—ruby-red with golden yellow tips; **Rosa Nell**—clear bright rose; **Venus**—creamy white suffused lavender.

**77B93** One root each of these six Best Decorative Dahlias (value $7.25), postpaid, for only..... **$5.00**

## Decorative Dahlias

The flowers are full to the center throughout the season. They are thick but not ball-shaped, with broad, flat, somewhat loosely arranged petals. The points are broad or rounded; the tips may be straight or turned down and in some varieties the margins are slightly rolled back. Within recent years this type of Dahlia has been enriched with quite a number of outstanding novelties. Whether used for garden display or for cut flowers they always give the greatest satisfaction.

**76B12 Amun Ra** This is a beautiful, rich, yet pleasing, autumn tint shading from orange to golden amber. A lovely substantial flower of large size.
**$1.00 each; 3 for $2.70; 6 for $5.25, postpaid**

**76B16 A. R. Johnson** The large flowers are a rich golden apricot shade. They are substantial and borne on long stems of good upright growth.
**$1.00 each; 3 for $2.70; 6 for $5.25, postpaid**

**76B28 Bashful Giant** Truly a giant variety with mammoth size blooms which gracefully hang their heads. The color is apricot shaded yellow.
**$1.00 each; 3 for $2.70; 6 for $5.25, postpaid**

**76B40 Champagne** A variety that has quickly become very well known because of its many outstanding features. The color is distinct and most appealing. It is a lovely shade of dull gold with a hue of iridescent chamois. The flowers are large and carried on long stems.
**$1.50 each; 3 for $3.80; 6 for $6.90, postpaid**

**76B48 Delice** Probably the best known cut-flower variety in the Dahlia world. In color, a charming bright rose-pink, suffused with lavender-pink.
**35 cts. each; 3 for 90 cts.; 6 for $1.75, postpaid**

**76B54 Etendard De Lyon** Brilliant royal purple. The blossoms are formed of long, broad and curled petals and are held erect by strong, straight stems. A richly colored variety that always attracts attention.
**35 cts. each; 3 for 90 cts.; 6 for $1.75, postpaid**

**76B66 Insulinde** Another one of those lovely autumn shades combining orange, buff, and golden orange, into a scintillating mass of color. The reverse of the petals is shaded golden rose. A great flower.
**$1.00 each; 3 for $2.70; 6 for $5.25, postpaid**

**76B70 Jean Kerr** This is the most valuable of all white Decorative Dahlias. The medium sized blooms are carried on long, strong stems well above the foliage. Blooms early and freely until killed by frost.
**75 cts. each; 3 for $1.90; 6 for $3.70, postpaid**

**76B74 Jersey's Beauty** This is considered the finest pink Dahlia ever introduced. The color is a lovely rose-pink. The blooms are large, well rounded, and of artistic proportions. Jersey's Beauty has created a sensation. Wherever exhibited it has received the highest honors. The firm and massive blooms are borne profusely on strong, heavy stems.
**$2.50 each; 3 for $6.50; 6 for $12.50, postpaid**

**76B82 Judge Marean** Dahlia lovers have proven their admiration for this great flower, as it has become one of the best known varieties. The immense blooms are of heavy substance, borne freely, and carried on long stems. The color is opalescent, combining salmon, pink, red, orange, and yellow into a glowing autumn shade.
**$1.00 each; 3 for $2.70; 6 for $5.25, postpaid**

**76B92 Mephistopheles** This is usually classed as a Decorative variety, even though at times the flowers show characteristics not unlike those found in the Hybrid-Cactus type. The blooms are magnificent rich ruby-red with golden yellow tips. It is a lovely variety in every way, valued not only because of its tremendous size but also because of its free-blooming habit and lasting qualities.
**$1.00 each; 3 for $2.70; 6 for $5.25, postpaid**

**77B04 Mina Burgle** The finest scarlet Dahlia for cut-flower and garden purposes—a glowing, most brilliant scarlet. Large flowers of perfect formation are produced abundantly on long, wiry stems.
**40 cts. each; 3 for $1.05; 6 for $2.00, postpaid**

**77B12 Mont Blanc** An exceptionally fine Dahlia of excellent formation and very large size. The pure white flowers are produced on long, strong stems.
**25 cts. each; 3 for 70 cts.; 6 for $1.30, postpaid**

**77B16 Mr. C. H. Dresselhuys** The beautiful pink flowers are carried above the foliage on strong stems, dominating the whole plant in their great profusion. It is a well formed flower of heavy texture.
**75 cts. each; 3 for $1.90; 6 for $3.70, postpaid**

76B74 Decorative Dahlia, Jersey's Beauty

**77B24 Mrs. I. De Ver Warner** Artistic, well sha flowers of truly mense size. The color is a superb shade of mauve-pink. I haps no other Dahlia has found as many lovers as this standing Decorative variety. It is a really fine flower.
**$1.00 each; 3 for $2.70; 6 for $5.25, postpaid**

**77B28 Mrs. J. Harrison Dick** A foremost Decora Dahlia which is known as it has been exhibited widely. The flowers are c bright yellow, showing a soft touch of pink on the ou petals. Blooms are well rounded and carried on long ster
**40 cts. each; 3 for $1.05; 6 for $2.00, postpaid**

**77B42 Paul Michael** Deep orange-buff with shading old rose on the reverse of petals. A flower of large size and picturesque appearanc
**$1.00 each; 3 for $2.70; 6 for $5.25, postpaid**

**77B52 Queen Mary** Lovely cerise-pink with a silv beam. The flowers are large, v shaped, and of good substance. The gorgeous long stem flowers are much in demand for bouquets.
**25 cts. each; 3 for 70 cts.; 6 for $1.30, postpaid**

**77B60 Rookwood** A sparkling shade, best described bright cerise-rose. The mammoth flowers are superb for exhibition or garden decoration.
**$1.00 each; 3 for $2.70; 6 for $5.25, postpaid**

**77B68 Rosa Nell** A clear, bright rose of elegant f and large size. It is a great favo for cutting because the mammoth blooms are long stemn
**$1.00 each; 3 for $2.70; 6 for $5.25, postpaid**

**77B80 Venus** A pleasing shade of creamy white wit charming suffusion of lavender. Large well formed flowers of great appeal. A sturdy plant.
**75 cts. each; 3 for $1.90; 6 for $3.70, postpaid**

**77B84 Wizard of Oz** The combination of amber, p and salmon represents a lov autumn tint. This is a flower which embodies size, g form, length of stem, and free-blooming habit. Wizard of has for years ranked as one of the most desirable Dah for both exhibition and garden use.
**$1.50 each; 3 for $3.80; 6 for $6.90, postpaid**

## Six Popular Decorative Dahlias

This collection contains the following six attractive an free-blooming Decorative Dahlias. They will be sent pos paid.

**Delice.** Charming, bright rose-pink.
**Mina Burgle.** Beautiful rich red.
**Mont Blanc.** Pure white.
**Mrs. J. Harrison Dick.** Bright yellow, flushed pink.
**Paul Michael.** Orange-buff; reverse old rose
**Queen Mary.** Cerise-pink with a silvery beam.

**77B94** One root each of these six Popular Decorative Dahlias (value $2.65) for **$2.0**

76B32 Peony-Flowered Dahlia, Berth von Heemstead

# Peony-Flowered Dahlias

eony flowered Dahlias have broad, flat and quite irregular
n of petals, semi-double; showing a beautiful golden-
ow center. Flowers appear early and continue in great
fusion. Borne on long stems and are ideal for cutting.

32 **Berth von Heemstead** A very fine variety which originated in Hol-
l. The large flowers are yellow, attractively suffused
h bronze. Blooms freely and continuously.
**35 cts. each; 3 for 90 cts.; 6 for $1.75, postpaid**

36 **Canada** Immense flowers with pure white petals of heavy texture and extremely free
oming. Strong and sturdy plants.
**35 cts. each; 3 for 90 cts.; 6 for $1.75, postpaid**

44 **Dainty Queen** The flowers are borne on long wiry stems and literally cover the plants
n early in the season until frost. The blooms are quite
ge, with loosely arranged petals. The color of the flowers
a pleasing shade of rosy lavender gradually fading to
te toward the yellow center of the flowers.
**35 cts. each; 3 for 90 cts.; 6 for $1.75, postpaid**

58 **Fordhook Cerise** Of wiry, stiff growth and perfectly upright habit. The color
a brilliant shade of rich cerise, with just a suspicion of
nge toward the base of the petals.
**40 cts. each; 3 for $1.05; 6 for $2.00, postpaid**

08 **Mme. Von Bystein** The large blooms are a soft tint of mauve, shading
ter toward the outer edges of the petals. Blooms freely.
**35 cts. each; 3 for 90 cts.; 6 for $1.75, postpaid**

64 **Rosalia Styles** Rose-pink flushed white, with lighter colored center. Of im-
se size and fine form. A fine free bloomer.
**75 cts. each; 3 for $1.90; 6 for $3.70, postpaid**

**77B95 Collection** One root each of the above 6 named Peony-Flowered Dahlias (value $2.55) ..... for **$2.00** postpaid

# Pompon Dahlias

ompon dahlias are small, ball-shaped and perfectly double,
asuring up to 2 inches in diameter; very free flowering;
for cutting.

24 **Bacchus** Bright crimson-scarlet. A profuse bloomer.
**50 cts. each; 3 for $1.30; 6 for $2.50, postpaid**

50 **Dr. Jim** Bright purple, shading lighter. Very striking color.
**50 cts. each; 3 for $1.30; 6 for $2.50, postpaid**

78 **Jessica** A combination of amber and salmon, tinted red.
**50 cts. each; 3 for $1.30; 6 for $2.50, postpaid**

32 **Neatness** The flowers are pale salmon with a cream center.
**50 cts. each; 3 for $1.30; 6 for $2.50, postpaid**

44 **Petite John** Lovely flowers of a bright lavender-rose.
**25 cts. each; 3 for 70 cts.; 6 for $1.30, postpaid**

56 **Queen of the Whites** The best white Pompon Dahlia in existence.
**35 cts. each; 3 for 90 cts.; 6 for $1.75, postpaid**

**77B96 Collection** One root each of the above 6 named Pompon Dahlias (value $2.60) ..... for **$2.00** postpaid

# Cactus and Hybrid Cactus Dahlias

In the Cactus Dahlias the flowers are fully double, with the floral rays long, narrow, incurved or twisted. This type is very valuable; the cut blooms last exceptionally long.

The Hybrid Cactus Dahlias are fully double, with decidedly shorter petals as compared with the true Cactus Dahlias. The petals are broad, flat, incurved or twisted.

**76B04 Adelaide C. Wingate** (Hybrid Cactus)
The flowers are a glowing rose-pink, gradually shading to rich yellow in the center. It is a contrasting yet harmonious combination. Because of its excellent size and fine form it is grown extensively for cutting.
**$1.00 each; 3 for $2.70; 6 for $5.25, postpaid**

**76B08 Ambassador** A delicate buff-yellow shade with a salmon-pink suffusion. The well-shaped flowers are large and substantial. Ambassador is a free bloomer. The long-stemmed blooms are carried above the healthy green foliage.
**$1.50 each; 3 for $3.80; 6 for $6.90, postpaid**

**76B20 Attraction** (Hybrid Cactus) Of large size and elegant form. The flowers are a bright lilac rose, borne on long, strong stems.
**65 cts. each; 3 for $1.75; 6 for $3.35, postpaid**

**76B62 George Walters** (Hybrid Cactus) A combination of salmon-pink which gradually flows into a bright-yellow at the base of the petals. It makes a showy flower.
**75 cts. each; 3 for $1.90; 6 for $3.70, postpaid**

**76B88 Lawine** The color is pure white with just a suggestion of blush as the flower matures.
**25 cts. each; 3 for 70 cts.; 6 for $1.30, postpaid**

**77B20 Mrs. Edna Spencer** (Hybrid Cactus)
An exquisite variety of a charming shade of Orchid-pink. The lovely texture of the petal adds greatly to the value of this free-flowering variety. Plants make a strong growth.
**50 cts. each; 3 for $1.30; 6 for $2.50, postpaid**

**77B48 Pierrot** Flowers are very large, of the incurved type and a pleasing shade of amber bronze, occasionally tipped white.
**50 cts. each; 3 for $1.30; 6 for $2.50, postpaid**

**77B72 Senorita** (Hybrid Cactus) The massive flowers are deep crimson shaded with metallic maroon. Senorita is outstanding in many ways. Few Dahlias show such a strong, robust growth as this mammoth variety.
**$1.00 each; 3 for $2.70; 6 for $5.25, postpaid**

**77B76 U. S. A.** (Hybrid Cactus) An early and continuous bloomer of a glowing deep orange shade. The flowers are of splendid form, enormous size, and borne on substantial stems.
**$1.00 each; 3 for $2.70; 6 for $5.25, postpaid**

**77B88 Wodan** The color is a pleasing delicate salmon-rose, shading to old gold in the center. The petals are tubular, and semi-incurved.
**35 cts. each; 3 for 90 cts.; 6 for $1.75, postpaid**

## Five Desirable Cactus Dahlias

**Five Different colors of the Cactus and Hybrid Cactus Type**

**77B97 Collection** One root each of Adelaide C. Wingate, George Walters, Mrs. Edna Spencer, Pierrot and Senorita (value $3.75) for only **$2.50** postpaid

76B20 Hybrid Cactus Dahlia, Attraction

# Maule's Select Gladiolus (First Size Bulbs

The Gladiolus is one of the most popular and beautiful of the summer flowering bulbs with tall spikes of flowers, som feet or more in height. Of almost every desirable color, blotched and spotted in the most curious manner. They have ab lutely no insect enemies and no diseases, and best of all, they will grow and bloom in any soil. We have never known a one to fail with them. Try them and be convinced.

From a large list of named Gladiolus we have selected 29 varieties which we consider the best as to color, form and size of flowers. We offer 17 varieties on this page and 12 on the opposite one. Many prefer named sorts, so as to have the colors they most desire. Mixtures of all colors in the large flowered Gladiolus, as well as the Primulinus type, are offered on next page.

## 10 Choice Named Gladiolus

### 78B01 America

A beautiful soft shell-pink color, tinged lavender; growth and habit perfect. Too well known to need comment. Fine for cut flowers.
**8 cts. each; 3 for 20 cts.; 65 cts. per doz.; 25 for $1.10, postpaid**

### 78B34 Gretchen Zang

A fitting companion to the Evelyn Kirtland. Large, heavy, sparkling bloom, a beautiful soft melting shade of pink, blending into scarlet on lower petals, forming an unusual blending of colors.
**10 cts. each; 3 for 25 cts.; 90 cts. per doz.; 25 for $1.60, postpaid**

### 78B37 Halley

Enormous open flowers of a delicate salmon pink, shading lighter to the center, with a cream yellow and carmine blotch. Very early.
**10 cts. each; 3 for 25 cts.; 80 cts. per doz.; 25 for $1.45, postpaid**

### 78B52 Mrs. Francis King

Large flowers of a light scarlet color, or better described as flame pink; are about 4½ inches across. Spikes always have 5 to 6 flowers open at one time. For garden effect or cut flowers it is one of the best.
**10 cts. each; 3 for 25 cts.; 80 cts. per doz.; 25 for $1.45, postpaid**

### 78B55 Mrs. Frank Pendleton

One of the finest varieties introduced. Delicate salmon-pink with brilliant, deep red blotches in the throat, rivaling many of the finest orchids in richness of colors. One of the best.
**10 cts. each; 3 for 25 cts.; 85 cts. per doz.; 25 for $1.50, postpaid**

### 78B58 Niagara

Large, well opened flowers on long, straight spikes; the color is a rich cream, while the lower petals blend to canary yellow. Free flowering.
**12 cts. each; 3 for 30 cts.; $1.00 per doz.; 25 for $1.80, postpaid**

### 78B61 Panama

The best rose colored Gladiolus. Very long spikes of large, deep rose self-colored flowers. Always attracts attention.
**10 cts. each; 3 for 25 cts.; 80 cts. per doz.; 25 for $1.45, postpaid**

78B28 Flora Gladiolus

### 78B64 Peace

Grand white flowers, very large, with pale lilac feathering and claret blotch on lower petals. Tall, graceful spikes.
**10 cts. each; 3 for 25 cts.; 90 cts. per dozen; 25 for $1.60, postpaid**

### 78B70 Princeps

Rich, dazzling scarlet, usually marked with three white blotches on the lower petals. Called by many the Amaryllis flowered Gladiolus.
**15 cts. each; 3 for 40 cts.; $1.40 per dozen; 25 for $2.60, postpaid**

### 78B79 Schwaben

One of the very finest pale yellow varieties; a clear canary yellow shading to a soft sulphur yellow when opening.
**10 cts. each; 3 for 25 cts.; 85 cts. per dozen; 25 for $1.50, postpaid**

### 78B91 Collection

**One bulb each of the above Ten Choice Named Gladiolus (value $1.05) for postpaid 80 cts.**

78B37 Halley Gladiolus

## 7 Prize Show Named Gladiolu

### 78B07 Baron Hulot or Blue King

Color is a rich deep violet-purple; lower petals are Pan violet.
**15 cts. each; 3 for 40 cts.; $1.50 per doz.; 25 for $2.80, postp**

### 78B25 Evelyn Kirtland

A beautiful shade of rosy pink, darker at the edges, fad to shell pink at the center, with brilliant scarlet blotches lower petals. Entire flower showing a glistening, sparkl luster. The form is wide open, somewhat reflexed a slightly fluted.
**12 cts. each; 3 for 30 cts.; $1.00 per doz.; 25 for $1.80, postp**

### 78B28 Flora

Beautiful golden-yellow flowers of large size. Rich, attr tive and showy; an exceedingly pure finely colored variety.
**15 cts. each; 3 for 35 cts.; $1.25 per doz.; 25 for $2.25, postp**

### 78B40 Herada

Pure mauve, glistening and clear. Unusually striking a attractive. A new color in Gladiolus. Wonderfully decorati
**15 cts. each; 3 for 35 cts.; $1.25 per doz.; 25 for $2.25, postp**

### 78B43 Le Marechal Foch

A giant flower of the finest soft flesh-pink borne on usually strong, straight, well-filled spikes.
**10 cts. each; 3 for 25 cts.; 90 cts. per doz.; 25 for $1.60, postp**

### 78B82 War

Deep blood-red shaded crimson black. Very tall and c spicuous late bloomer. One of the best reds.
**15 cts. each; 3 for 40 cts.; $1.40 per doz.; 25 for $2.60, postp**

### 78B85 Willy Wigman

A creamy white ground delicately rose tinted with a la soft carmine conspicuous blotch on lower petals.
**12 cts. each; 3 for 30 cts.; $1.10 per doz.; 25 for $2.00, postp**

### 78B92 Collection

**One bulb each of the above 7 Named Prize Show Gladiolus (value 94 cts.) ..... for 70 cts postpaid**

B49 Gladiolus, Mrs. F. C. Peters

# Six of the Best Gladiolus

### 78B13 Cowee's Scarlet

One of the most brilliant colors we have yet seen in gladiolus, a most intense flaming scarlet red. An outstanding variety which has become very popular for garden display or cutting.

**50 cts. each; 3 for $1.25; $4.75 per dozen; 25 for $9.00, postpaid**

### 78B22 Europa

Gorgeous flowers of the purest white and much in demand for cut flowers. Spikes are strong and sturdy, carrying large, well shaped flowers, many of which are open at the one time.

**25 cts. each; 3 for 65 cts.; $2.40 per dozen; 25 for $4.50, postpaid**

### 78B31 Golden Measure

A new yellow of unusual merit, a rich golden yellow. Flowers are large, wide open and well placed on tall spikes.

**25 cts. each; 3 for 65 cts.; $2.40 per dozen; 25 for $4.50, postpaid**

### 78B49 Mrs. F. C. Peters

A beautiful combination of colors—a lovely shade of rosy-lilac with a contrasting crimson blotch in the throat and bordered with white on the lower petals. A strong, vigorous grower. Large flowers.

**40 cts. each; 3 for $1.10; $4.25 per dozen; 25 for $8.25, postpaid**

### 78B73 Purple Glory

A giant in all respects. Tall, sturdy spikes of enormous flowers of the deepest purplish-maroon with almost black blotches. Flowers are beautifully ruffled.

**35 cts. each; 3 for $1.00; $3.75 per dozen; 25 for $7.25, postpaid**

### 78B76 Rose Ash

This variety attracts the attention of all who see it. Peculiar soft, old-rose tones, fading to ashes of roses on the outer edge of petals. A very unique coloring.

**20 cts. each; 3 for 50 cts.; $1.85 per dozen; 25 for $3.50, postpaid**

**78B93 COLLECTION** — One bulb each of the above Six Best Gladiolus (value $1.95) . . for **$1.50** postpaid

# 6 Extra Fine Named Gladiolus

### 78B04 Anna Eberius

ark velvety purple, the throat a deeper shade; very large of a splendid, rich color. Unusually graceful spike, tall handsome.

**cts. each; 3 for 35 cts.; $1.25 per doz.; 25 for $2.25, postpaid**

### 78B10 Bluebird

onsidered by many as the best mid-blue. The flowers are ge, well opened and closely set on a long, strong spike.

**cts. each; 3 for 40 cts.; $1.45 per dozen; 25 for $2.75, postpaid**

### 78B16 Crimson Glow

xtra large flowers of brilliant crimson; exceedingly rich strikingly showy. Tall, stately plant; many flowers open a time.

**cts. each; 3 for 35 cts.; $1.25 per doz.; 25 for $2.35, postpaid**

### 78B19 E. J. Shaylor

A truly beautiful flower, pure, deep rose-pink and elegantly ruffled. Plants are tall and very strong; flowers are large.

**12 cts. each; 3 for 30 cts.; $1.10 per doz.; 25 for $2.00, postpaid**

### 78B46 Mrs. Dr. Norton

Pure soft white, with tips of petals suffused soft La France pink. The three lower petals have a blotch of sulphur yellow, stained at the base with fine specks of Tyrian pink.

**15 cts. each; 3 for 40 cts.; $1.40 per doz.; 25 for $2.60, postpaid**

### 78B67 Prince of Wales

An early flowering sort with fine spikes of seven to eight well expanded large flowers open at the one time. The color is a delicate apricot-pink suffused salmon. One of the leading varieties, and noticed for its color and beauty wherever shown.

**12 cts. each; 3 for 30 cts.; $1.00 per doz.; 25 for $1.85, postpaid**

**78B94 COLLECTION** — **One bulb each of the above 6 Extra Fine Named Gladiolus (value 84c) for 65c postpaid**

## SPECIAL OFFERS

### Six Popular Gladiolus

**AMERICA. Shell pink.**
**HALLEY. Salmon pink.**
**MRS. F. KING. Light scarlet.**
**PEACE. Beautiful white.**
**SCHWABEN. Pale yellow.**
**WAR. Deep blood-red.**

**78B95** 3 bulbs each of the 6 varieties (18 bulbs), value $1.60, for only..... **$1.25**

**78B97** 12 bulbs each of the 6 varieties (72 bulbs), value $5.40, for only **$4.50**

Above offers are postpaid.

## 78B87 Maule's Extra Fine Mixed Gladiolus

A superior selection of the best large flowering varieties, many of which are high priced and if sold under name would cost many times what we are charging for them in mixture. We know this to be as good a mixture as you can buy, being made up of a wide range of colors, from the richest red to the most delicate white and pastel shades. We offer these bulbs at very moderate prices, so that you may obtain a large quantity of them in order to get a greater variety of colors. Plant at intervals for a succession of bloom.

**3 for 20 cts.; 65 cts. per dozen; 25 for $1.15; 50 for $2.20; $4.00 per 100, postpaid**
**By express, not prepaid, $3.75 per 100; 200 for $7.00; 500 for $16.00**

## 78B89 Primulinus Hybrids Mixed Gladiolus

The blooms are smaller than those of the gladiolus on this and the opposite page. They are slightly hooded, and are poised like butterflies on long, graceful stems. Because of the size and the graceful pliant stems, they are especially lovely in baskets and for table decoration. The shades run from the most delicate creams and pinks through the light yellows and primrose to orange, with an occasional rose pink and soft red. We offer the choicest colors in a grand mixture.

**3 for 20 cts.; 70 cts. per dozen; 25 for $1.25; 50 for $2.25; $4.25 per 100, postpaid**

**78B99 One first-sized bulb each of Maule's 29 named select large-flowering Gladiolus, for only $3.25, postpaid**

# The Vegetable Gardener's Calendar

**WHEN AND WHAT TO PLANT at Certain Periods to Procure the Best Results**

**HOW TO PLANT** is plainly printed on each package of MAULE'S Seeds and given at the beginning of each generic variety.

Every garden to be properly arranged should be planned in advance—on paper. The object of a successful garden is to grow sufficient to meet the requirements of the family. It is a waste of time, work and seed to see how much you can grow if all the products are not utilize

Keep a record of when seeds were sown, when see lings or plants were set out, when vegetables were read to use, etc. Such information will be helpful in the su cess of your garden, another year. Jot down all data o the opposite page which we have provided for yo convenience.

## January 1 to February 25

After carefully planning your garden, on receipt of your copy of The Maule Seed Book, which is usually sent out in January, make out and send us your order for all seeds, bulbs and roots you will require for the season. GET YOUR ENTIRE ORDER IN EARLY. You will have your seeds, etc., ready to plant at the proper time.

## February 25 to March 30

### For an Early Crop of Vegetables

sow seeds of the following in-doors, in hot-beds or cold-frames to furnish plants for setting out when weather becomes warm.

| | | |
|---|---|---|
| Broccoli | Celeriac | Lettuce |
| Brussels Sprouts | Celery | Onion |
| Cabbage (Early) | Egg Plant | Pepper |
| Cauliflower | Ground Cherry | Tomatoes |

Lima Beans, Beets, Sweet Corn, Cucumbers, Melons and Squash seeds are often started in pots and transplanted out-doors when spring opens. Use small pots, two or three seeds to each, and disturb the soil as little as possible when setting out.

### Out-door Plantings

AFTER MARCH 15, or as soon as the ground can be worked which should not be attempted unless the soil is dry enough to crumble in your hand, plant

Asparagus Roots
Horse Radish Sets
Rhubarb Roots
Onion Sets and Potatoes.

Being permanent crops, these should be placed at one side of the garden.

The first seeds to be sown are

| | | |
|---|---|---|
| Asparagus | Dandelion | Onion |
| Beets | Leek | Peas (Smooth) |
| Carrots | Lettuce | Radish |
| Cress | Mustard | Spinach |

## April 1 to May 10

Set out-doors as soon as the weather becomes warm and settled, plants of

| | | |
|---|---|---|
| Broccoli | Cabbage (Early) | Lettuce |
| Brussels Sprouts | Cauliflower | Onion |

Roots and sets that may be planted are

| | | |
|---|---|---|
| Asparagus Roots | Horse Radish Sets | Potatoes |
| Garlic Sets | Onion Sets | Rhubarb Roots |

Seeds that may be sown are

| | | |
|---|---|---|
| Asparagus | Dandelion | Parsnip |
| Beans, Bush | Endive | Peas |
| Beets | Kale | Radishes |
| Carrots | Kohl-Rabi | Rhubarb |
| Chicory | Leek | Salsify |
| Collards | Lettuce | Sorrel |
| Corn Salad | Mustard | Spinach |
| Corn (Early) | Onion | Swiss Chard |
| Cress | Parsley | Turnips (Early) |

In well-prepared seed-beds, for transplanting when large enough to the garden rows, sow seeds of

| | |
|---|---|
| Brussels Sprouts | Celery |
| Celeriac | Herbs |

## May 10 to June 15

After all danger of frost is past, set out plants of

| | | |
|---|---|---|
| Egg Plants | Ground Cherry | Peppers |
| Sweet Potatoes | | Tomatoes |

If Lima Beans, Beets, Sweet Corn, Cucumbers, Melons or Squash were started earlier in-doors, transplant them as soon as the weather has become warm and settled.

The above plants are sensitive to frost so nothing is gained by setting them out until all danger of cold spells is over.

Early in May, for late crops, seeds of the following may be sown in seed-beds to be transplanted when large enough to the garden rows:

| | | |
|---|---|---|
| Broccoli | Cabbage | Ground Cherry |
| Brussels Sprouts | Cauliflower | Tomatoes |

In early May, you may plant

| | | |
|---|---|---|
| Asparagus Roots | Horse Radish Sets | Potatoes |
| Garlic Sets | Onion Sets | Rhubarb Roots |

Seeds that may be sown are

| | | |
|---|---|---|
| Beans (all kinds) | Gourds | Parsley |
| Beets, Table | Herbs | Parsnip |
| Beets, Sugar | Kale | Peanuts |
| Cabbage (Late) | Kohl-Rabi | Peas |
| Carrot | Leek | Pumpkin |
| Chicory | Lettuce | Radishes |
| Collards | Lima Beans | Rhubarb |
| Corn Salad | Mangels | Salsify |
| Corn | Melon Peach | Sorrel |
| Cress | Muskmelon | Spinach |
| Cucumbers | Mustard | Squash |
| Dandelion | Okra | Swiss Chard |
| Garden Lemon | Onion | Turnips (Early) |
| | Watermelon | |

## June 15 to July 20

Set out plants of

| | | |
|---|---|---|
| Broccoli | Cabbage (Late) | Celeriac |
| Brussels Sprouts | Cauliflower | Celery |

Seeds that may be sown are

| | |
|---|---|
| Beans, Bush | Endive |
| Beans, Bush Lima | Kale |
| Beets | Kohl-Rabi |
| Carrots | Lettuce |
| Chicory, | Okra |
| Cabbage, Chinese | Radishes (Summer and Winte |
| Collards | Ruta Baga |
| Corn | Sorrel |
| Cress | Swiss Chard |
| Cucumbers | |

Potatoes may also be planted at this time.

Many of the earlier sown seeds, by this time, will hav matured their crop. Make successional sowings; keep a ground working; when one crop is done, plant another.

Beets, Carrots and other root crops for winter storin will be better if sown at this time than earlier. Use the roo of the earlier sown seeds for table use; if left until frost i dig, they will be too tough when wanted throughout th winter.

## July 20 to August 31

The probable time of the first frost in your locality must b considered before deciding what to plant at this time. Spa should be available as many of the varieties that were plante early have matured and should be followed by others, such a

| | |
|---|---|
| Beans, Bush | Onions |
| Collards | Peas (Early varieties |
| Kale | Radishes (Summer or Winte |
| Lettuce | Spinach |
| Mustard | Turnips |

To help build up your soil, a winter cover crop should b provided. This will furnish humus when turned under ne spring. You do not have to wait until the crops are of Loosen up the soil between the rows and sow Winter Ry Clover or Winter Vetch over the entire surface.

## September 1 to October 15

Sow not later than September 15 for late fall or early sprin use:

| | |
|---|---|
| Corn Salad | Lettuce |
| Kale | Spinach |

Sow Onion seed for early spring use (we recommend Silve Skin.)

After the "first" frost, the weather for two or three weel is usually warm. Many vegetables, such as beans, lettuc etc., can be saved if corn-fodder, hay or straw is placed ove them at night when frost threatens.

## October 15 to December 31

Until October 15, set out

| | |
|---|---|
| Asparagus Roots | Onion Sets |
| Horse Radish Sets | Rhubarb Roots |

They require no protection but a covering will prove ben ficial.

If Corn Salad, Kale, Lettuce or Spinach are wanted f early spring use, plants should be covered with a few inch of hay, leaves or litter the last of November and left o during the winter.

Consult your garden notes for the year and while yo garden operations are fresh in your mind plan your ne year's garden.

We would thank you to recommend Maule's Seeds to yo neighbors and have them write us for a catalog or if yo will send us their names and addresses, we will gladly ma them The Maule Seed Book, free.

**The calendar above applies to the latitude of Philadelphia. Allow about one week's difference for every one hundred mil of latitude: North, later; South, earlier.**

# Vegetable Garden Notes

# The Flower Gardener's Calendar

**WHEN AND WHAT TO PLANT at Certain Periods to Procure the Best Results**

**HOW TO PLANT** is plainly printed on every package of MAULE'S Seeds. With every order of Bulbs and Roots a copy of our "Bulb Culture" will be sent free. If directions are followed, success is assured.

Flowers are so easily grown and can be used in so many different ways that every home should have an abundance of them. Grow them yourself for house decoration, garden display and cut-flower purposes. Fill every nook and corner of your yard. Grow some to give away. Select the early, mid-season and late blooming sorts; the tall medium and low-growing varieties for the various locations and purposes to which each is best suited.

Keep a record of your garden "doings;" when seed was planted, when germinated, when transplanted, when flowers bloomed, etc. It will not only be educational but of great value in the success of your garden another year. On the opposite page, we have provided space for your garden notes. Jot them down.

## January 1 to February 25

Sow indoors in pans, pots or shallow boxes seeds of the following half-hardy perennials which, as the plants increase in size, should be transferred to larger pots in which they may be kept growing in the house in a partially shaded location, or outdoors during the summer and taken indoors in the fall for winter decoration.

| | | |
|---|---|---|
| Abutilon | Fuchsia | Lantana |
| Asparagus | Ferns | Lemon Verbena |
| Begonia | Geranium | Oxalis |
| Calceolaria | Gloxinia | Primula |
| Cineraria | Heliotrope | Umbrella Plant |
| Cyclamen | Jerusalem Cherry | |

Pot up for winter blooming or to have plants to set outdoors after all danger of frost is over, bulbs of:

| | | |
|---|---|---|
| Amaryllis | Cooperia | Ismene |
| Atamasco Lily | Crinum | Madeira Vine |
| Caladium, Fancy Leaf | Dielytra | Oxalis |
| Calla Lilies | Garden Lilies | Spider Lily |

## February 25 to March 30

Sow indoors to provide plants for setting in the open ground after all danger of frost is past, the following:

### Hardy Annuals

| | | |
|---|---|---|
| Ageratum | Cardinal Climber | Petunia |
| Antirrhinum | Cobaea | Salvia |
| Canna | Lobelia | Thunbergia |

For best results, the above named Annuals should be started indoors. For earlier blooms than outdoor sown seed any or all of the hardy annuals which we list, may be started indoors at this time.

As soon as the ground can be worked, usually about the middle of March, sow Sweet Pea seeds.

### Half-hardy Perennials

All of the varieties mentioned in our January 1 to February 25 table may be sown now and grown in the same manner.

The following seeds should be sown now, the plants to be set in the open ground when weather is warm and settled.

| | |
|---|---|
| Blue Daisy | Pampas Grass |
| Centaurea, Gymnocarpa | Purple Feather Grass |
| Coleus | Vinca |
| Dahlia | Wistaria |

### Hardy Biennials and Perennials

Seeds of hardy biennials and perennials may be sown now indoors to provide plants for setting out when weather becomes warm. Many of these hardy perennial plants will produce flowers the first season.

### Flowering and Ornamental Bulbs

All of the varieties mentioned in our January 1 to February 25 table may be potted up now for indoor blooming or to be set outdoors after danger of frost is over. Canna roots may be started now for later planting outdoors.

## April 1 to May 10

Plants of annuals, biennials and perennials may be set outdoors after the weather has become warm and settled.

Bulbs and roots in the dormant state, or those started earlier indoors, may be set out also if the weather has become thoroughly warm.

Seeds of all annuals, biennials and perennials may be sown outdoors after all danger of frost is past, usually when the trees are coming into leaf.

The perennials and biennials are usually sown in a well-prepared seed bed. When plants are large enough to handle they should be transplanted where intended to remain.

Plants of half-hardy perennials which have been grown indoors may be taken out of pots and set out in a partially shaded location for the summer. Lift plant and repot in the fall to be again taken indoors. The pots may also be plunged in the soil up to their rim without disturbing the plant, or left to grow in the pot.

## May 10 to June 15

The same directions as given for the April 1 to May 10 table will apply equally as well to this period. Keep soil cultivated, free from weeds and apply fertilizer occasionally to stimulate growth.

Plants from earlier sowings should be thinned out or transplanted, preferably on cloudy days or after a rain.

### May 10 to June 15 (Continued)

In some sections, warm climates especially, some of the early flowering annuals will have died out. Other sowings may be made of the same varieties for flowering in early fall when the weather is most favorable for the development of the finest blooms.

Do not let any flowers go to seed; as soon as the blossoms fade, remove them to prolong the flowering period. Keep all tall growing plants tied up. Cultivate often; keep the soil loose. Your plants will thrive better; finer blooms will be had.

Seeds of hardy perennials may be sown to furnish plants for transplanting to permanent location and become established before severe weather sets in.

## July 20 to August 31

Sow seeds of hardy perennials to produce plants that will flower next year, and continue to bloom each succeeding season. Transplant before frost where intended to remain. The earlier they are transplanted the more time they will have to become established to withstand the winter.

Sow seeds of Daisy (Bellis) and Pansy in the open ground or cold frame and protect plants with a light mulching during the winter.

Place orders at this time for such bulbs as Tulips, Hyacinths, Narcissi, Crocus, etc., for winter blooming indoors or spring flowering outdoors.

## September 1 to October 15

For winter blooming indoors pot up such fall bulbs as Tulips, Hyacinths, Narcissi, Easter Lilies, etc. For spring flowering outdoors plant all fall bulbs. If you intend to plant these bulbs where annual flowers are now growing, it will be time enough when frost has killed the annual plants, which should be pulled up, put in the compost heap or burned. Dig the soil and fertilize; bone-meal is very beneficial.

Plants of half-hardy perennials which have been growing in the open ground should be taken up and repotted if wanted for indoor winter use. Plants should be cut back and when repotted it will be better to plunge the pots in the soil, in a partially shaded location, so that they may re-establish themselves. Other plants such as Petunias, Antirrhinums, etc., may be potted up in the same manner, which is best done in September as it allows the plant plenty of time to produce new growth and to establish itself before time to take it in the house.

Seeds of many annuals may be sown in boxes, pots or hanging baskets for indoor winter decoration.

## October 15 to December 31

Fall Bulbs, such as Hyacinths, Tulips, Narcissi, etc., may be planted outdoors until the ground is frozen. They may be potted for indoor winter blooming as long as supply is procurable. These bulbs usually reach us from our growers in September and should be bought as early in the fall as possible. The demand for these bulbs increases each year and we can never tell how long our supply will last, so order early to avoid disappointment.

Hardy Garden Lily bulbs are usually not ready for delivery until late in the fall, in many sections too late for outdoor planting. But if the ground is covered with a thick covering of manure, leaves or litter, the soil may be prevented from freezing and the bulbs set out when received.

After hardy bulbs and roots are planted in the fall it will prove beneficial to them if a covering of manure is applied after the ground has become frozen. Do not cover too early as the covering is intended to keep the frost in the ground, as the alternate freezing and thawing are what damages the bulbs. Many gardeners make the mistake of covering early to prevent the ground from freezing. This is wrong.

Be ever watchful for insects on your house plants. Keep leaves free from accumulations of dust. A strong force of water from hose or faucet will rid your plants of both.

While your garden results and failures (if you had any) are fresh in your mind, plan your next year's garden. Correct any mistakes you may have made, improve upon what you have done, and be ready to make up your order of Seed and Bulb requirements as soon as the Maule Seed Book is received, which should reach you about the first of the year.

If any of your friends or neighbors grow vegetables or flowers, we would appreciate it very much if you would loan them your catalog or send us their names and addresses and we will gladly send them the Maule Seed Book, free.

**The calendar above applies to the latitude of Philadelphia. Allow about one week's difference for every one hundred miles of latitude: North, later; South, earlier**

# Flower Garden Notes

See page 140 for The Vegetable Gardener's Calendar; jot down your garden records

# GENERAL INDEX OF THE MAULE SEED BOOK FOR 1927


Maule's Guarantee....Page 1
Maule's Special Offer....Page 3
Maule's Vegetable Seed Collections....Pages 19, 28, 49, 56
The Vegetable Gardener's Calendar....Page 140
Garden Notes....Pages 141, 143

List of Flower Seeds for Various Purposes....Page 81
The Flower Gardener's Calendar....Page 142
Maule's Flower Seed Collections....Pages 83, 86, 87, 88, 89, 93, 94, 97, 103, 105, 108, 110, 112, 117, 118, 119, 120, 122, 123, 124, inside front, inside back and back covers


## VEGETABLE SEEDS AND ROOTS.


PAGE

Asparagus Seed ..... 4
" Roots ..... 4

Beans, Bush..5, 6, 7, 8, 9
" " Lima..... 10
" Field ..... 9
" Pole ..... 12
" " Lima..... 11
Beets, Table....13, 14, 15
" Stock(Mangel) 16
" Sugar ..... 16
Borecole ..... 37
Broccoli ..... 4
Brussels Sprouts ..... 4

Cabbage..17, 18, 19, 20, 21, 22
Cantaloupe (Muskmelon)
Carrots, Garden. ..24, 25
" Stock or Field.. 25
Casabas ..... 43
Cauliflower ..... 23
Celeriac ..... 26
Celery .....26, 27
Chicory ..... 22
Chinese Cabbage .... 18
Citron Melon .....46, 47
Collards ..... 22
Corn Salad ..... 27
Corn, Pop ..... 32
" Sweet..28, 29, 30, 31, 32
" " For Forage 78
Cress ..... 27
Cucumbers.....33, 34, 35

Dandelion ..... 27

Egg Plant ..... 36
Endive ..... 27

French Endive ..... 22

Garden Lemon..... 33
Garlic Sets..... 48
Gourds ..... 36
Ground Cherry..... 36
Gumbo ..... 48

Herbs ..... 37
Horse Radish Sets.... 65

Kale ..... 37
Kohl Rabi ..... 36

Leek ..... 37
Lettuce .....38, 39

Mangels ..... 16
Mango Melon..... 42
Melon Peach..... 42
Mulford Cultures....8, 10, 73
Mushroom Spawn..... 48
Muskmelon..40, 41, 42, 43
Mustard ..... 48

Okra ..... 48
Onion Seed .....49, 50, 51
Onion Sets ..... 51
Oyster Plant ..... 65

Parsley ..... 52
Parsnip ..... 52
Peanuts ..... 52
Peas, Sugar..... 56
" Table.53, 54, 55, 56
Pepper .....57, 58
Peppergrass ..... 27
Potatoes ..... 76
Pumpkins .....59, 60

Radish....2, 61, 62, 63, Front Cover
Rhubarb ..... 65
Rhubarb Roots..... 65
Ruta Baga..... 73

Salsify ..... 65
Sorrel ..... 65
Spinach ..... 64
Squash .....65, 66
Sugar Corn for Forage 78
Swede Turnips..... 73
Swiss Chard ..... 14

Tobacco ..... 60
Tomato.....67, 68, 69, 70
Tomato, Husk..... 36
Turnip .....71, 72, 73

Water Cress..... 27
Watermelon..44, 45, 46, 47
Winter Radish..... 63
Witloof Chicory..... 22


## FARM AND GRAIN SEEDS.


PAGE

Alfalfa ..... 79

Barley ..... 74
Beets, Stock..... 16
Broom Corn..... 74
Buckwheat ..... 74

Cane ..... 75
Carrots Stock..... 25
Clover ..... 79
Corn, Field .....77, 78
" Flint ..... 77
" Fodder ..... 78
" Kaffir ..... 75
Cow Peas..... 76

Egyptian Wheat..... 75
Emmer ..... 75
Ensilage Corn..... 78

Feterita ..... 75

Grass, Billion Dollar.. 75
Grass Mixtures..... 80
Grasses ..... 79

Kale ..... 74

Mangels ..... 16
Millet ..... 75
Milo Maize..... 75
Mulford Cultures.8, 10, 73

Oats ..... 74

Pasture Mixtures..... 80
Peanuts ..... 52
Peas, Field ..... 75
" Cow ..... 76
Pencillaria ..... 75
Potatoes ..... 76

Rape ..... 75
Ruta Baga..... 73
Rye ..... 74

Shallu ..... 75
Soja Beans..... 76
Sorghum ..... 75
Speltz ..... 75
Spring Rye..... 74
Spring Wheat..... 74
Sudan Grass..... 79
Sunflower ..... 74

Timothy ..... 79
Turnips .....71, 72, 73

Vetch ..... 74

Wheat ..... 74
White Clover..... 80


## TREE SEEDS.


Arbor Vitæ, American 60
Apple ..... 60

Catalpa Speciosa..... 60
Cherry Mazard..... 60

Fir, Douglass..... 60

Honey Locust..... 60

Norway Spruce..... 60

Osage Orange..... 60

Pear, Kieffer..... 60

White Pine..... 60

Yellow Locust..... 60
Yellow Pine ..... 60


## FLOWER SEEDS.


Abutilon ..... 82
Achillea ..... 82
Acroclinium ..... 82
Adlumia ..... 82
African Daisy..... 84
African Gold Daisy... 98
Ageratum ..... 82
Alkanet ..... 84
Allegheny Vine..... 82
Alpine Violet ..... 96
Alyssum ..... 82
Amaranthus ..... 84
Ampelopsis ..... 84
Anchusa ..... 84
Antirrhinum .....83, Inside Back Cover
Aquilegia ..... 84
Arabis ..... 84
Arctotis ..... 84
Aristolochia ..... 85
Armeria ..... 85
Artemisia ..... 85

PAGE

Asparagus ..... 85
Asters.....86, 87, 88, 89, Inside Front Cover
Baby's Breath .....103
Balloon Vine ..... 85
Balsam ..... 90
Balsam Apple.....109
Balsam Pear.....109
Basket of Gold..... 82
Bean, Scarlet Runner.121
Beard Tongue.....113
Begonia ..... 85
Bell Flower ..... 92
Bellis ..... 98
Bidens ..... 85
Bignonia ..... 90
Bitter Sweet ..... 90
Black Cosmos..... 85
Black Dahlia..... 85
Black Eyed Susan....121
Blanket Flower.....102
Blue Daisy..... 90
Blue Lace Flower..... 90
Blue Marguerite..... 90
Bocconia ..... 91
Boltonia ..... 91
Border Pinks.....100
Boston Ivy..... 84
Brachycome ..... 91
Burning Bush .....105
Butterfly Flower..... 91

Calceolaria ..... 91
Calendula ..... 91
California Poppy.....100
Calliopsis ..... 91
Campanula ..... 92
Canary Bird Flower.. 92
Candytuft ..... 92
Canna ..... 93
Canterbury Bells.....92
Cape Aster..... 95
Cape Forget-me-not.. 84
Cape Marigold..... 91
Cardinal Climber..... 93
Carnation ..... 93
Castor Oil Bean..... 116
Cathedral Bells..... 95
Celosia ..... 94
Centaurea ..... 94
Cherry Pie.....103
Chinese Primrose.....113
Chinese Woolflower... 94
Chrysanthemum ..... 95
Cineraria ..... 95
Clematis ..... 95
Clove Pinks..... 100
Cobæa ..... 95
Cockscomb ..... 94
Coleus ..... 96
Columbine ..... 84
Coreopsis ..... 96
Cornflower ..... 94
Cornflower Aster.....117
Cosmidium ..... 96
Cosmos...97, Back Cover
Cyclamen ..... 96
Cypress Vine..... 96

Dahlia ..... 98
Daisy ..... 98
Datura ..... 98
Delphinium ..... 99
Dianthus .....99, 100
Digitalis .....100
Dusty Miller..... 94
Dutchman's Pipe..... 85

Emerald Feather..... 85
English Daisy..... 98
Eschscholtzia .....100
Euphorbia .....101
Everlasting Flowers...101
Everlasting Pea.....101

False Chamomile..... 91
False Dragon Head...113
Feather Pinks .....100
Ferns .....101
Feverfew .....101
Fire on the Mountain.101
Flags .....104
Flame Nettle..... 96
Floss Flower..... 82
Flowering Maple..... 82
Flowering Tobacco....109
Forget-me-not .....109
Four O'Clock.....106
Foxglove .....100
Fuchsia .....101

Gaillardia .....102
Geranium .....102

PAGE

Gilliflower .....117
Gladiolus .....102
Globe Amaranth.....102
Gloxinia .....102
Gomphrena .....102
Gourds, Ornamental..103
Grass Pinks.....100
Gypsophila .....103

Hardy Candytuft..... 92
Hardy Dianthus.....100
Hardy Heliotrope.....121
Hardy Larkspur..... 99
Hardy Poppy.....115
Hardy Sweet Pea.....101
Hare Bell ..... 92
Heartsease .....110, 111
Helenium .....103
Helianthus .....117
Helichrysum .....103, Back Cover
Heliotrope .....103
Hibiscus .....103
Hollyhock .....104
Hop Vine, Japanese..104
Humulus .....104

Ice Plant .....104
Indian Shot Plant.... 93
Ipomœa .....104
Iris, Japanese .....104

Jack and Bean Stalk.105
Japanese Bell Flower.113
Japanese Ivy..... 84
Jerusalem Cherry.....105
Job's Tears.....105
Joseph's Coat..... 84

Kochia .....105
Kudzu Vine, Japanese.105

Lace Fern..... 85
Lady's Ear Drop.....101
Lady's Slipper..... 90
Lantana .....105
Larkspur .....105, Inside Back Cover
Lavender .....105
Lemon Verbena.....106
Lobelia .....106
London Tufts .....121
Love in the Mist.....109
Love-in-a-puff ..... 85
Lupinus .....106

Mad Wort..... 82
Mallow .....103
Marguerite Carnation. 93
Marigold .....106
Marvel of Peru.....106
Mignonette .....107
Milfoil ..... 82
Momordica .....109
Moonflower .....104
Morning Glory.....107
Mountain Fringe..... 82
Mourning Bride .....117
Myosotis .....109

Nasturtium .....108, Inside Back Cover
Nicotiana .....109
Nigella .....109

Old Maid .....122
Ornamental Grasses...109
Oxalis .....109

Painted Daisies..... 95
Painted Tongue.....117
Pampas Grass.....109
Pansy .....110, 111
Pansy, Tufted.....122
Pelargonium .....102
Pentstemon .....113
Periwinkle .....122
Petunia .....112, 113, Back Cover
Phlox .....114
Physostegia .....113
Pincushion Flower....117
Pinks .....99, 100
Platycodon .....113
Plume Poppy ..... 91
Poor Man's Orchid... 91
Poppy .....2, 115, Front cover
Portulaca .....114
Pot Marigold..... 91
Pouch Flower..... 91
Primula .....113
Primrose .....113
Purple Feather Grass.116

PAGE

Pyrethrum .....116

Rainbow Corn.....124
Red Hot Poker.....121
Reseda .....107
Ricinus .....116
Rock Cress..... 84
Rose Moss.....114

Salpiglossis .....117
Salvia .....116
Saponaria .....116
Scabiosa .....117
Scarlet Runner Bean..121
Scarlet Sage.....116
Sea Pink ..... 85
Shasta Daisy..... 98
Silver Sage .....116
Smilax .....117
Snapdragon .....83, Inside Back Cover
Sneezewort .....103
Snow on the Mountain .....101
Spice Pinks.....100
Stocks .....117
Stokesia .....117
Straw Flower.....103, Back Cover
Summer Cypress.....105
Summer Fir..... 85
Sunflower .....117
Sun Plant .....114
Swan River Daisy.... 91
Sweet Alyssum..... 82
Sweet Peas.118, 119, 120, Inside Back Cover
Sweet Scabious..... 117
Sweet Sultans..... 94
Sweet William.....121

Tagetes .....106
Texan Pride .....114
Thrift ..... 85
Thunbergia .....121
Tickseed ..... 91
Torch Flower.....121
Tree Celandine..... 91
Tritoma .....121
Trumpet Creeper..... 90
Trumpet Flower..... 98
Tufted Pansy.....122

Umbrella Plant.....121

Valeriana .....121
Verbena .....122
Vinca .....122
Viola .....122
Viola, Tufted .....122
Violet .....122
Virgin's Bower ..... 95

Wallflower .....121
Wax Work ..... 90
White Moonflower....104
Wild Flower Garden..124
Wistaria .....124
Woolflower ..... 94

Xeranthemum .....122

Yarrow ..... 82
Youth and Old Age.123, 124, Back Cover

Zea Japonica.....124
Zinnia.....123, 124, Back Cover


## FLOWERING AND ORNAMENTAL BULBS AND ROOTS.


Adam's Needle.....131
Album Lily.....127
Amaryllis .....127
Anchusa .....84, 131
Anemone, Japonica....130
Aquilegia .....84, 132
Aster, Hardy.....131
Atamasco Lily .....125
Auratum Lily.....127

Baby's Breath....103, 131
Baptisia .....90, 132
Barbadoes Lily.....127
Bell Flower Japanese..129
Blanket Flower...102, 132
Bleeding Heart.....129
Bocconia .....91, 132
Buddleia .....130
Butterfly Bush.....130

Caladium, Esculentum 126
Caladium, Fancy Leaf 126

PAGE

Calla Lilies .....125
Cannas .....134, 135
Centaurea .....133
Chrysanthemum...95, 132
Cinnamon Vine .....126
Clematis .....129
Columbine .....84, 132
Cooperia .....126
Coreopsis .....96, 131
Crinum .....125

Dahlias .....136, 137
Daisy, Shasta .....98, 131
Day Lily .....129
Delphinium .....99, 133
Dielytra .....129
Dropwort .....130

Elephant's Ear.....126
Everlasting Pea.....131

Fairy Lily .....125
False Indigo.....90, 132
Flags .....128

Gaillardia .....102, 132
Gladiolus .....138, 139
Gloriosa Lily .....127
Golden Crown Lily...129
Golden Glow.....129
Golden Rayed Lily...127
Gypsophila .....103, 131

Hardy Aster .....131
Hardy Heliotrope.....132
Hardy Larkspur...99, 133
Hardy Sweet Peas....131
Hemerocallis .....129
Henryi Lily .....127
Hibiscus .....103, 129
Hollyhock .....104, 132
Hyacinthus, Candicans .....126

Iris .....128, 130
Ismene .....125

Japanese Bell Flower..129
Jerusalem Cross.....131

Kansas Gay Feather.. 107, 132

Liatris .....107, 132
Lillies, Atamasco.....125
" Fairy .....125
" Calla .....125
" Golden Crown.129
" Hardy Garden.127
" White Spider..125
Lychnis .....131

Madeira Vine.....126
Mallows .....103, 129
Michaelmas Daisies...131
Mignonette Vine.....126

Nymphæa, Odorata...130

Oxalis .....126

Peonies .....133
Perennial Corn Flower.133
Persian Daisy.....132
Peruvian Daffodil.....125
Phlox, Perennial.....128
Platycodon .....113, 129
Plume Poppy.....91, 132
Plumy Bleeding Heart.129
Purple Cone Flower...130
Pyrethrum .....116, 132

Red Hot Poker.....130
Regale Lily .....127
Roseum Lily .....127
Royal Lily.....127
Rudbeckia .....129, 130

Sea Lavender.....129
Shasta Daisy.....98, 131
Speedwell, Japanese...130
Spider Lily, White....125
Spirea .....130
Statice .....129
Summer Lilac.....130
Surprise Offer.....125

Tiger Lily, Double....127
Torch Flower.....130
Tritoma .....130
Tuberoses .....126

Valeriana .....132
Veronica .....130

Water Lily .....130
Windflower, Japanese.130

Yucca .....131





HAMMOND PRESS
W. B. CONKEY COMPANY
CHICAGO

# WM. HENRY MAULE

## PHILADELPHIA, PA.

A7B2

**Write your Name and Address plainly below.** **Date** _____

**Name** _____
(Mr., Mrs. or Miss; write name plainly and always the same way)

**R. D. or Street** _____

**Post Office** _____

**County** _____ **State** _____

**Express or Freight Office** { If different from P. O. } _____

*Send by* Parcel Post ☐ Express ☐ Freight ☐ Mark a cross (x) in square to indicate preference in shipping.

**When goods offered at "Not Prepaid" prices are wanted by PARCEL POST, the required postage should be added and included with your remittance.**

PLEASE DO NOT WRITE IN THIS SPACE

**Amount Enclosed**

Money Order....$_____

Check or Draft....$_____

Cash.....$_____

Stamps..$_____

TOTAL..$_____

**CONDITION OF SALE**—All the Seeds, Bulbs and Roots here ordered are Guaranteed as to Vitality and Purity to the full amount of the purchase price. We will refund the money paid for them or replace them without extra cost any time within the year if you are not satisfied with the results obtained. We cannot guarantee the crop as success depends largely upon cultivation, soil and climatic conditions. And it is also recognized that a mistake may be made and it is, therefore, mutually agreed that in no case shall Wm. Henry Maule Co. be liable for more than the amount actually paid for the Seeds, Bulbs or Roots.

| QUANTITY | NUMBER | ORDER BY NUMBER AND NAME ARTICLES WANTED | PRICE | | |
|---|---|---|---|---|---|
| | | | | | 1 |
| | | | | | 2 |
| | | | | | 3 |
| | | | | | 4 |
| | | | | | 5 |
| | | | | | 6 |
| | | | | | 7 |
| | | | | | 8 |
| | | | | | 9 |
| | | | | | 10 |
| | | | | | 11 |
| | | | | | 12 |
| | | | | | 13 |
| | | | | | 14 |
| | | | | | 15 |
| | | | | | 16 |
| | | | | | 17 |
| | | Use the other side of this order sheet for additional items. *Amount carried forward* | | | |

We want more people to plant Maule's Seeds. Some of your neighbors surely have a garden. Send us their names and addresses on the other side of this order sheet. We will appreciate the favor and gladly mail them a catalog free.

# Extra Order Sheets and Return Envelopes Furnished on Request

| QUANTITY | NUMBER | ORDER BY NUMBER AND NAME ARTICLES WANTED | PRICE | | |
|---|---|---|---|---|---|
| | | **Amount carried forward** | | | |
| | | | | | 18 |
| | | | | | 19 |
| | | | | | 20 |
| | | | | | 21 |
| | | | | | 22 |
| | | | | | 23 |
| | | | | | 24 |
| | | | | | 25 |
| | | | | | 26 |
| | | | | | 27 |
| | | | | | 28 |
| | | | | | 29 |
| | | | | | 30 |
| | | | | | 31 |
| | | | | | 32 |
| | | | | | 33 |
| | | | | | 34 |
| | | | | | 35 |
| | | | | | 36 |
| | | | | | 37 |
| | | | | | 38 |
| | | | | | 39 |
| | | | | | 40 |
| | | | | | 41 |
| | | | | | 42 |
| | | | | | 43 |
| | | | | | 44 |
| | | **Total Amount** | | | |

**NOTICE: Please write below the names and addresses of any of your neighbors who would be interested in our catalog. We will gladly mail them a copy, free.**

| NAMES | R. D. OR STREET | POST OFFICE | STATE |
|---|---|---|---|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

# WM. HENRY MAULE

## PHILADELPHIA, PA.

A7B1

**Write your Name and Address plainly below.** **Date** _____

**Name** _____
(Mr., Mrs. or Miss; write name plainly and always the same way)

**R. D. or Street** _____

**Post Office** _____

**County** _____ **State** _____

**Express or Freight Office** { If different from P. O. } _____

*Send by* **Parcel Post** ☐ **Express** ☐ **Freight** ☐ **Mark a cross (x) in square to indicate preference in shipping.**

**When goods offered at "Not Prepaid" prices are wanted by PARCEL POST, the required postage should be added and included with your remittance.**

PLEASE DO NOT WRITE IN THIS SPACE

**Amount Enclosed**

**Money Order....$** _____
**Check or Draft....$** _____
**Cash.....$** _____
**Stamps..$** _____
**TOTAL..$** _____

**CONDITION OF SALE**—All the Seeds, Bulbs and Roots here ordered are Guaranteed as to Vitality and Purity to the full amount of the purchase price. We will refund the money paid for them or replace them without extra cost any time within the year if you are not satisfied with the results obtained. We cannot guarantee the crop as success depends largely upon cultivation, soil and climatic conditions. And it is also recognized that a mistake may be made and it is, therefore, mutually agreed that in no case shall Wm. Henry Maule Co. be liable for more than the amount actually paid for the Seeds, Bulbs or Roots.

| QUANTITY | NUMBER | ORDER BY NUMBER AND NAME ARTICLES WANTED | PRICE | | |
|---|---|---|---|---|---|
| | | | | | 1 |
| | | | | | 2 |
| | | | | | 3 |
| | | | | | 4 |
| | | | | | 5 |
| | | | | | 6 |
| | | | | | 7 |
| | | | | | 8 |
| | | | | | 9 |
| | | | | | 10 |
| | | | | | 11 |
| | | | | | 12 |
| | | | | | 13 |
| | | | | | 14 |
| | | | | | 15 |
| | | | | | 16 |
| | | | | | 17 |
| | | Use the other side of this order sheet for additional items. *Amount carried forward* | | | |

We want more people to plant Maule's Seeds. Some of your neighbors surely have a garden. Send us their names and addresses on the other side of this order sheet. We will appreciate the favor and gladly mail them a catalog free.

## Extra Order Sheets and Return Envelopes Furnished on Request

| QUANTITY | NUMBER | ORDER BY NUMBER AND NAME ARTICLES WANTED | PRICE | | |
|---|---|---|---|---|---|
| | | Amount carried forward | | | |
| | | | | | 18 |
| | | | | | 19 |
| | | | | | 20 |
| | | | | | 21 |
| | | | | | 22 |
| | | | | | 23 |
| | | | | | 24 |
| | | | | | 25 |
| | | | | | 26 |
| | | | | | 27 |
| | | | | | 28 |
| | | | | | 29 |
| | | | | | 30 |
| | | | | | 31 |
| | | | | | 32 |
| | | | | | 33 |
| | | | | | 34 |
| | | | | | 35 |
| | | | | | 36 |
| | | | | | 37 |
| | | | | | 38 |
| | | | | | 39 |
| | | | | | 40 |
| | | | | | 41 |
| | | | | | 42 |
| | | | | | 43 |
| | | | | | 44 |
| | | Total Amount | | | |

**NOTICE:** Please write below the names and addresses of any of your neighbors who would be interested in our catalog. We will gladly mail them a copy, free.

| NAMES | R. D. OR STREET | POST OFFICE | STATE |
|---|---|---|---|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

# Maule's Special Collections of the Finest Flower Seeds

## *Any 2 of these Collections for 60¢*
## *All 4 Collections shown here for $1.00*

The flowers as shown here are from ⅓ to ½ natural size

**GIANT SWEET PEAS**
4173 *Collection*—One packet each of the four named varieties (value 40c) *for* **35c**
1922 Giant Sweet Pea Mixture
*Pkt.* 10c; ½ oz. 20c; oz. 30c

**SNAPDRAGONS**
4113 *Collection*—One packet each of the four named varieties (value 40c) *for* **35c**
940 All Colors Mixed
*Pkt.* 10c; ⅛ oz. 25c

**ANNUAL LARKSPUR**
4149 *Collection*—One packet each of the four separate colors (value 45c) *for* **35c**
1424 All Colors Mixed
*Pkt.* 10c; ¼ oz. 30c

**DWARF NASTURTIUMS**
4153 *Collection*—One packet each of the four named varieties (value 40c) *for* **35c**
1558 All Colors Mixed
*Pkt.* 10c; oz. 20c

# MAULE'S SEEDS

1263
EARLY CRIMSON
PKT. 10c

1264
EARLY WHITE
PKT. 10c

1262
EARLY PINK
PKT. 10c

1258
DOUBLE PINK BEAUTY
PKT. 15c

1644
HOWARD'S STAR
PKT. 10c

1635
ROSY MORN
PKT. 10c

1659
BALCONY WHITE
PKT. 20c

1663
BURPEE'S BLUE
PKT. 25c

1372
FIREBALL
PKT. 10c

1379
SNOWBALL
PKT. 10c

1378
ROSE QUEEN
PKT. 10c

1377
GOLDEN BALL
PKT. 10c

2049
SALMON ROSE
PKT. 10c

2046
SCARLET
PKT. 10c

2048
WHITE
PKT. 10c

2050
GOLDEN YELLOW
PKT. 10c

## STRAWFLOWERS or HELICHRYSUM

4147 *Collection*—One packet each of the four Named Varieties (value 40c) *for* **35c**

1374 All Colors Mixed
*Pkt.* 10c; ¼ oz. 25c

## COSMOS

4142 *Collection*—One packet each of the four separate colors (value 45c) *for* **35c**

1265 Early Mixed Colors
*Pkt.* 10c; ¼ oz. 25c
1266 Double Crested Mixed
*Pkt.* 15c; ⅛ oz. 40c

## PETUNIAS

4157 *Collection*—One packet each of the four Petunias (value 65c) *for only* **35c**

1640 All Colors Mixed
*Pkt.* 10c; ⅛ oz. 45c

## SPECIAL OFFERS

Any two collections (your selection) *for* **60c**
or all four collections *for only* **$1.00**
***All Flowers are about ⅓ natural Size***

## GIANT ZINNIAS

4185 *Collection*—One packet each of the four separate colors (value 40c) *for* **35c**

2054 All Colors Mixed—*Pkt.* 10c; ⅛ oz. 25c